

AD-A147 918


FATE AND DISPOSITION OF TRICHLOROETHYLENE IN SURFACE
SOILS(U) AIR FORCE INST OF TECH WRIGHT-PATTERSON AF OH
T J WALKER11984 AFIT/CI/NR-84-92D


1/4

UNCLASSIFIED

F/G 13/2

NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

(1)

AD-A147 918

AD-A147 918

1979 84

UNCLASS

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		REAL INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER AFIT/CI/NR 84-92D	2. GOVT ACCESSION NO. ADA 147 718	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Fate and Disposition of Trichloroethylene in Surface Soils		5. TYPE OF REPORT & PERIOD COVERED THESIS/DISSERTATION
7. AUTHOR(s) Thomas Joseph Walker		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS AFIT STUDENT AT: Purdue University		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS AFIT/NR WPAFB OH 45433		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE 1984
		13. NUMBER OF PAGES 350
		15. SECURITY CLASS. (of this report) UNCLASS
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVED FOR PUBLIC RELEASE; DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES APPROVED FOR PUBLIC RELEASE: IAW AFR 190-1 9 Nov 84 Lynn E. Wolaver Dean for Research and Professional Development AFIT, Wright-Patterson		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number)		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) ATTACHED		

DTIC
ELECTE
NOV 29 1984
E

FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASS

84 11 15 012

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

ABSTRACT

Author: Thomas Joseph Walker, Major, USAF, RSC

Title: Fate and Disposition of Trichloroethylene in Surface Soils

Date: 1984

Number of Pages: 350

Degree: Ph.D.

Institution: Purdue University

Trichloroethylene (TCE) is a widely detected contaminant in groundwater. This study investigated fate of TCE in two similar soils with differing organic carbon contents. TCE was applied to soil columns in one 5 or 10 ml quantity, then eluted with 50 or 100 ml of water/day.

The 1.4% organic carbon soil retarded TCE elution more than did the 0.53% soil. Column effluent TCE reached 840-1,100 mg/l with the 0.53% organic carbon soil having higher TCE concentrations. For columns subjected to 10 ml TCE, effluent TCE remained constant at approximately 1,100 mg/l until 50-60% of applied TCE was eluted. Water application rate had no measurable effect on elution.

Batch isotherms for both soils and two particle sizes (fine, < 0.150 mm; coarse, < 2 mm) paralleled Freundlich theory. Adsorptive capacity increased with increased organic carbon content and decreased particle size. Based on normalized organic carbon content, adsorption was dependent upon inorganic surface area.

Biodegradation of TCE in the soils, based on effluent TCE and chlorides, was not enhanced by addition of ammonia. Warburg studies showed TCE inhibited biological activity in unacclimated soil. Acclimated soil of both types from 2.5 and 15 inch depths showed degradation of TCE at 55 mg/l but not 110 or 550 mg/l. No evidence of cis or trans-1,2-dichloroethylene was found in column effluents. Degradation (biological and abiotic) accounted for 0.3% or less of TCE. Volatilization accounted for 15.6-32.8% of TCE applied.

PURDUE UNIVERSITY

Graduate School

This is to certify that the thesis prepared

By Thomas Joseph Walker

Entitled Fate and Disposition of Trichloroethylene in Surface Soils

Complies with University regulations and meets the standards of the Graduate School for originality and quality

For the degree of:

Doctor of Philosophy

Signed by the final examining committee:

James F. Ebel, chair

John M. Bell
Paul H. H. H. H.

Approved by the head of school or department:

July 25 1984 Harold L. Michael

This thesis ☒ is not to be regarded as confidential



Accession For	
NTIS GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By _____	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A-1	

James F. Ebel
Major professor

FATE AND DISPOSITION OF TRICHLOROETHYLENE

IN SURFACE SOILS

A Thesis

Submitted to the Faculty

of

Purdue University

by

Thomas Joseph Walker

In Partial Fulfillment of the

Requirements for the Degree

of

Doctor of Philosophy

August 1984

To Jane, Jenny, Rachel, and Kate -
your love made this possible.

ACKNOWLEDGEMENTS

The author expresses his sincere gratitude and appreciation to Dr. James E. Etzel for his continued guidance, encouragement, and advice throughout the author's academic program and laboratory research. Appreciation is also expressed to members of his committee, Drs. John M. Bell, Ronald F. Wukasch, and Gordon S. Born for their interest, advice, and support. Additional thanks go to Drs. Don Franzmeier, Pat Belcastro, Gary Carlson, and Don Edelen for their help in initiating and continuing the research.

The entire environmental engineering staff is thanked for their contributions to the author's education and development. Especially worth noting is the experience and insight obtained while studying, working, and relaxing with the fellow graduate students.

Acknowledgement is made of the Air Force Institute of Technology which supported the author's academic program. Additional gratitude is extended to the Air Force Engineering and Services Center which supported the author's research investigation.

TABLE OF CONTENTS

	Page
LIST OF TABLES.....	vi
LIST OF FIGURES.....	xi
ABSTRACT.....	xiv
INTRODUCTION.....	1
LITERATURE REVIEW.....	4
TCE Manufacture and Use.....	4
Properties of TCE.....	7
Health Aspects of TCE.....	9
TCE Occurrence in Groundwater.....	12
Soil Environment.....	15
Chemical Transport in Soil.....	21
Degradation.....	51
Summary.....	59
MATERIALS AND METHODS.....	61
Description of Soils.....	61
Soil Sample Collection.....	63
Soil Analyses.....	64
Chemical Analyses.....	66
Trichloroethylene Analyses.....	67
Adsorption Isotherms.....	78
Warburg Respirometry Studies.....	82
PRELIMINARY INVESTIGATIONS.....	85
Soil Analyses.....	85
Soil Column Setup.....	89
Effluent Collection.....	94
Variation in GC Reponse.....	99
Application of Water to Columns.....	102
Application of TCE to Soil.....	105

TABLE OF CONTENTS, Continued

	Page
RESULTS AND DISCUSSION.....	112
Batch Adsorption Studies.....	112
Column Elution Studies.....	132
Cumulative TCE Elution.....	174
Biodegradation Studies.....	179
Abiotic Degradation.....	206
TCE Mass Balance.....	208
Findings as Applied to an Actual Release to the Environment.....	215
SUMMARY.....	217
CONCLUSIONS AND RECOMMENDATIONS.....	225
Conclusions.....	225
Recommendations for Future Research.....	227
LIST OF REFERENCES.....	229
APPENDICES	
Appendix A. Sample Calculations.....	239
Appendix B. Tabulated Data from Soil Column Studies.....	243
Appendix C. Tabulated Data from TCE:Soil Adsorption Studies.....	330
Appendix D. Tabulated Data from TCE:Soil Warburg Respirometry Studies.....	335
VITA.....	350

LIST OF TABLES

Table	Page
1. Recent Annual TCE Production.....	5
2. Physical Properties of TCE.....	5
3. TCE Nomenclature and Identity Information....	8
4. Synthetic Organic Chemicals Most Commonly Found in Groundwater (92).....	13
5. Occurrence of TCE in Drinking Water (92).....	13
6. Projected Cancer Risks for Drinking Water Concentrations of TCE (92).....	16
7. Variation in Concentration of Microorganisms with Depth for a Typical Mineral Soil (1)....	16
8. Particle Size Information from Representative Soil Adsorption Studies.....	37
9. Reported Equilibration Times for Batch Isotherm Studies.....	39
10. Parameters from Packed Column Adsorption Studies.....	41
11. Summary of Data from Packed Column Study (77)	42
12. Analyses Conducted by the Soil Characterization Laboratory.....	65
13. GC Linearity Data for Headspace Analysis....	73
14. TCE Recovery from Composite Soil Samples....	78
15. CEC, Organic Carbon, Particle Size Distribution, and pH of Soils.....	86
16. Physical Parameters of Soils.....	87

LIST OF TABLES, Continued

Table	Page
17. Calculated Soil and Organic Carbon Mass.....	88
18. Loss of TCE through Pierced Septa.....	100
19. Variation in FID Response Due to Sample Matrix.....	100
20. Variation in FID Response with Sample Volume.	103
21. Calculated TCE Adsorption.....	106
22. Operating Conditions for Column Soil Studies.	110
23. Summary of Experimental Values Used to Determine Soil Adsorption Isotherms for TCE..	114
24. Freundlich Constants Determined from Equilibrium Adsorption Isotherms for TCE Applied to Soils.....	115
25. Calculated X/M Values for Various TCE Concentrations.....	115
26. Data from Time of Adsorption Experiment for Chalmers Soil Subjected to TCE Application...	122
27. Data from Time of Adsorption Experiment for Russell Soil Subjected to TCE Application....	124
28. Summary of Data from Glass Adsorption Study with TCE.....	129
29. Summary of Data from Gravel Adsorption Study with TCE.....	129
30. Mean, Standard Deviation, and Range of Daily Volume of Effluent Collected from Chalmers Soil Columns.....	134
31. Mean, Standard Deviation, and Range of Daily Volume of Effluent Collected from Russell Soil Columns.....	136
32. Maximum, Minimum, and Mean pH for Soil Column Effluents.....	160
33. Summary of Soil Column Effluent Chloride Measurements.....	183

LIST OF TABLES, Continued

Table	Page
34. Total Oxygen Uptake from Acclimated Soil Warburg Studies When Supplemented with TCE or Glucose.....	192
35. Percent Substrate Respired from Acclimated Soil Warburg Studies When Supplemented with TCE or Glucose.....	193
36. Rate of TCE Respiration from Acclimated Soil Warburg Studies When Supplemented with TCE...	194
37. Rate of Endogenous Respiration and Carbon Dioxide Production for Soil Samples from Columns at Various Depths.....	203
38. TCE Eluted in Soil Column Effluents.....	209
39. Concentration and Mass of TCE Remaining on Soil Columns After Elution.....	212
40. TCE Mass Balance for Soil Columns Operated Continuously with Water Application for 132 Consecutive Days.....	214
Appendix	
Table	
B1. Cross Reference of Column Study Day with Calendar Date.....	244
B2. Daily Data for Columns C1, C2, and C3.....	245
B3. Daily Data for Columns C4, C5, and C6.....	254
B4. Daily Data for Columns C7, C8, and C9.....	263
B5. Daily Data for Columns C10, C11, and C12.....	271
B6. Daily Effluent Volume from Chalmers Soil Control Column.....	280
B7. Daily Data for Columns R1, R2, and R3.....	282
B8. Daily Data for Columns R4, R5, and R6.....	291
B9. Daily Data for Columns R7, R8, and R9.....	300
B10. Daily Data for Columns R10, R11, and R12.....	309

LIST OF TABLES, Continued

Table	Page
B11. Daily Effluent Volume from Russell Soil Control Column.....	318
B12. TCE Time of Saturation.....	320
B13. pH of Chalmers Soil Column Effluent.....	321
B14. pH of Russell Soil Column Effluent.....	322
B15. Effluent Volume and TCE Concentrations Used to Determine TCE Eluted from Columns by Simpson's Approximation.....	323
B16. Cumulative Mass of TCE Eluted from Chalmers Soil Columns.....	324
B17. Cumulative Mass of TCE Eluted from Russell Soil Columns.....	325
B18. Cumulative Mass of TCE Eluted Based Upon Comparison to a CSTR (53).....	326
B19. Ammonia Concentrations in Soil Column Effluents.....	327
B20. Nitrate Concentrations in Soil Column Effluents.....	328
B21. Chloride Concentrations in Soil Column Effluents.....	329
C1. Data for Determination of Soil Adsorption Isotherms.....	331
C2. Data for Determination of X/M Values in Time of Adsorption Experiment.....	332
C3. Data for Determination of Glass Adsorption Isotherm.....	334
C4. Data for Determination of Gravel Adsorption Isotherm.....	334
D1. Warburg Data for Unacclimated Chalmers Soil Supplemented with TCE from 2.5 Inch Depth....	336
D2. Warburg Data for Acclimated Chalmers Soil Supplemented with TCE from 2.5 Inch Depth....	338

LIST OF TABLES, Continued

Table	Page
D3. Warburg Data for Acclimated Chalmers Soil Supplemented with TCE from 15 Inch Depth.....	340
D4. Warburg Data for Acclimated Chalmers Soil Supplemented with TCE from 31 Inch Depth.....	342
D5. Warburg Data for Acclimated Russell Soil Supplemented with TCE from 2.5 Inch Depth....	344
D6. Warburg Data for Acclimated Russell Soil Supplemented with TCE from 15 Inch Depth.....	346
D7. Warburg Data for Acclimated Russell Soil Supplemented with TCE from 31 Inch Depth.....	348

LIST OF FIGURES

Figure	Page
1. Possible Routes of Reductive Dechlorination (46).....	58
2. GC Response for Different Sample Volumes.....	74
3. Diagram of Soil Column.....	90
4. Extrusion of Soil Core Into Column.....	92
5. Collection of Sample without TCE Analysis....	95
6. Collection of Sample with TCE Analysis.....	95
7. Variation in FID Response with Different Sample Volumes.....	104
8. Column Study Assembly.....	108
9. TCE Adsorption Isotherm for Composite Mixture of Chalmers Soil.....	116
10. TCE Adsorption Isotherm for Composite Mixture of Russell Soil.....	117
11. Adsorption Equilibration for Coarse Particle Soil with TCE Concentration of 220 mg/l.....	126
12. Adsorption Equilibration for Coarse Particle Soil with TCE Concentration of 880 mg/l.....	126
13. Adsorption Equilibration for Fine Particle Soil with TCE Concentration of 220 mg/l.....	127
14. Adsorption Equilibration for Fine Particle Soil with TCE Concentration of 880 mg/l.....	127
15. Composite TCE Elution Curve: Chalmers Soil Columns C1, C2, and C3.....	141

LIST OF FIGURES, Continued

Figure	Page
16. Composite TCE Elution Curve: Chalmers Soil Columns C4, C5, and C6.....	142
17. Composite TCE Elution Curve: Chalmers Soil Columns C7, C8, and C9.....	143
18. Composite TCE Elution Curve: Chalmers Soil Columns C10, C11, and C12.....	144
19. Composite TCE Elution Curve: Russell Soil Columns R1, R2, and R3.....	145
20. Composite TCE Elution Curve: Russell Soil Columns R4, R5, and R6.....	146
21. Composite TCE Elution Curve: Russell Soil Columns R7, R8, and R9.....	147
22. Composite TCE Elution Curve: Russell Soil Columns R10, R11, and R12.....	148
23. Time of Saturation for TCE and Water.....	159
24. Composite TCE Elution Curves for 5 ml TCE Application to Soil Columns.....	162
25. Composite TCE Elution Curves for 10 ml TCE Application to Soil Columns.....	163
26. Composite TCE Elution Curves for 50 ml/day Water Application Rate to Soil Columns.....	164
27. Composite TCE Elution Curves for 100 ml/day Water Application Rate to Soil Columns.....	165
28. Composite TCE Elution Curves for Chalmers Soil Columns.....	166
29. Composite TCE Elution Curves for Russell Soil Columns.....	167
30. Cumulative Mass Elution of TCE from Soil Columns.....	176
31. Cumulative Percentage Elution of TCE from Soil Columns.....	177

LIST OF FIGURES, Continued

Figure	Page
32. Warburg Oxygen Uptake for Unacclimated Chalmers Soil Supplemented with TCE for 2.5 Inch Depth.....	186
33. Warburg Oxygen Uptake for Acclimated Chalmers Soil Supplemented with TCE for 2.5 Inch Depth	189
34. Warburg Oxygen Uptake for Acclimated Chalmers Soil Supplemented with a Glucose Substrate...	190
35. Warburg Oxygen Uptake for Acclimated Chalmers Soil Supplemented with TCE for 15 Inch Depth.	196
36. Warburg Oxygen Uptake for Acclimated Chalmers Soil Supplemented with TCE for 31 Inch Depth.	197
37. Warburg Oxygen Uptake for Acclimated Russell Soil Supplemented with TCE for 2.5 Inch Depth.....	198
38. Warburg Oxygen Uptake for Acclimated Russell Soil Supplemented with TCE for 15 Inch Depth.	199
39. Warburg Oxygen Uptake for Acclimated Russell Soil Supplemented with TCE for 31 Inch Depth.	200
40. Warburg Oxygen Uptake for Acclimated Russell Soil Supplemented with a Glucose Substrate...	201

ABSTRACT

Walker, Thomas Joseph. Ph.D., Purdue University, August 1984. Fate and Disposition of Trichloroethylene in Surface Soils. Major Professor: Dr. James E. Etzel.

Trichloroethylene (TCE) is widely detected as a contaminant in groundwater due to discharges or spills. This study investigated the fate of TCE in two similar soils with differing organic carbon contents. TCE was applied to soil columns in one 5 or 10 ml quantity, then eluted over 132 consecutive days with 50 or 100 ml of water/day.

The 1.4% organic carbon soil retarded elution of TCE more than did the 0.53% soil. Column effluent TCE reached 840-1,100 mg/l with the 0.53% organic carbon soil having higher TCE concentrations. For columns subjected to 10 ml TCE, effluent TCE remained constant at approximately 1,100 mg/l until 50-60% of applied TCE was eluted. Water application rate had no measurable effect on elution.

Batch isotherms for both soils and two particle sizes (fine, < 0.150 mm; coarse, < 2 mm) paralleled the Freundlich theory. Adsorptive capacity increased with increased organic carbon content and decreased particle size. Based on normalized organic carbon content, adsorption was found to be dependent upon inorganic surface area. Equilibration

time studies for 220-880 mg/l TCE showed adsorption to be complete within 20 hours.

Biodegradation of TCE in the soils, based on effluent TCE and chlorides, was not enhanced by addition of ammonia to elution water. Warburg studies showed TCE was inhibitory to biological activity at concentrations of 55-1,100 mg/l in unacclimated soil. Acclimated soil of both types from 2.5 and 15 inch depths showed degradation of TCE at 55 mg/l but not 110 or 550 mg/l. Addition of ammonia enhanced mass of TCE respired but not respiration rate. No evidence of cis or trans-1,2-dichloroethylene was found in column effluents. In all, degradation (biological and abiotic) accounted for 0.3% or less of TCE.

A mass balance indicated TCE retention in the soil directly correlated with soil organic carbon content. Elution and volatilization were major sinks for TCE. Volatilization accounted for 15.6-32.8% of TCE applied.

INTRODUCTION

Groundwater serves many individuals and municipalities throughout the United States, with estimates that 40-50% of our population depend upon it as a drinking water source (36,57). In most locations, groundwater has been and will continue to be a reliable and healthful source of water.

Recent evidence, though, has indicated that much of the groundwater within the country, particularly in urban and industrial areas, may be contaminated with anthropogenic organic chemicals. Presence of some of these chemicals in groundwater poses serious public health problems because of their toxicity. These compounds are usually present in groundwater due to accidental spills or illicit dumping (46).

Environmental regulatory agencies and legislative bodies have recognized the need to control and regulate the entry of hazardous chemicals into the environment. Examples of this control legislation include the Safe Drinking Water Act, the Clean Water Act, Toxic Substance Control Act, and Resource Conservation and Recovery Act (46,51,87,89). While this legislative emphasis has been aimed to reduce or

eliminate the purposeful entry of organics into the environment, discharges of chemicals by spills or illegal release have occurred and will probably continue to occur.

The gravity of the health effects of groundwater contamination is nearly matched by the cost to identify the extent and magnitude of a contaminated zone within an aquifer. Problems are encountered because of the lack of research on the phenomena that control contaminant transport in concentrations that vary over several orders of magnitude (35,36,37). Extensive research has been conducted on the transport of pesticides in the environment. Very little literature, though, has addressed the problems associated with organic contaminant transport, particularly at concentrations in the high mg/l range that would be associated with the release or discharge of a chemical in the environment.

The purpose of this research was to investigate the fate of one particular chemical, trichloroethylene, as introduced to soil columns in a non-solution form such as in a spill or discharge. Subsequent elution of the trichloroethylene with deionized water was used to simulate rainfall. Trichloroethylene was chosen because of its classification as a priority pollutant (89), its widespread use (80), and its frequent occurrence in groundwater (63,74). The soils chosen for this research possessed different organic carbon

contents and represented typical soils commonly found throughout the country.

The literature contains no evidence of comprehensive research on the fate of trichloroethylene in soils, especially at high concentrations. Therefore, the goal of this project was to determine this fate as a result of elution and the adsorptive:desorptive and degradative properties of the soil. An understanding of these factors would allow a better estimate of the necessity or urgency to contain or clean up spills of trichloroethylene on surface soils to prevent groundwater contamination.

LITERATURE REVIEW

In order to properly plan the proposed research investigation on the consequence of an accidental spill of trichloroethylene onto soil, an understanding of why TCE is of concern and how it can be transported in the environment was desirable. Included in this review are the major areas of: manufacture, use, properties; health aspects; groundwater contamination potential; soil environment interactions; and, most extensively, chemical transport in soil. The information on all of these factors was then used to decide the protocol for the research studies.

TCE Manufacture and Use

Trichloroethylene (TCE) is a chemical that has been of important industrial significance since the 1920's. It was first synthesized in Europe in 1864 and patented in 1906 (87,97) but commercial production of TCE in the United States did not begin until 1935 (87). Production is primarily by three chemical companies: Dow Chemicals, Ethyl Corporation, and PPG Industries (80). Recent annual U.S. production figures are listed in Table 1.


Table 1. Recent Annual TCE Production.

Year	Annual Production (million of pounds)	Reference
1970	610	78
1973	452	78
1974	434	78
1975	515	91
1981	365	80


Table 2. Physical Properties of TCE.

Property		Reference
Boiling point, C, (760 mm Hg)	86.7	45,103
	87.0	94
Melting point, C	-87.1	45,103
	-86.8	76
	-73.0	94
Vapor pressure, mm Hg, 20C	57.8	45
	57.9	94
	58.0	43
Vapor density, boiling point, 1 atm, g/liter	4.45	45
Specific gravity (liquid)	1.46	45
Octanol/Water Partition Coefficient	195	94
Log Octanol/Water Partition Coefficient	2.29	94
Solubility in water, 20C, mg/l	1,100	45,51
Henry's Law Constant, atm-m ³ /mol	11.7x10 ⁻³	96

TCE is commercially produced by two different processes (31,45,97). The most widely used method which accounts for 90% of production, is a dual step process in which acetylene is initially chlorinated to tetrachloroethane in a packed tower at 50°C. The tetrachloroethane is then removed and processed through a dehydrochlorination step. This can be done by alkaline hydrolysis with calcium hydroxide in water or by thermal decomposition in the presence of an activated charcoal catalyst at 300-500°C. The reactions involved are:



The other process involves oxychlorination of 1,2-dichloroethane:



TCE is used in a variety of ways and in many different products. Approximately 90% of TCE is used as a solvent in liquid or vapor degreasing of metal parts before some type of metal finishing (15,76,87,91). Approximately 5% of TCE is used as a dry cleaning solvent, an extractant in food and medicine production, or as a solvent for such things as cleaning septic tanks (63,87,91). The remaining 5% is used as a chemical intermediate or solvent in the production of pesticides, waxes, gums, resins, tars, and chemicals such as chloroacetic acid (87,91). TCE has found some limited use as a surgical anesthetic and analgesic but is no longer

widely used for these purposes (15,76,87,97,103). Until recently, it was also a common constituent of many consumer products such as spot removers, rug cleaners, and air fresheners (51) but recent events which classed TCE as a hazardous substance prompted discontinuance of its use for these materials.

Properties of TCE

TCE is a colorless liquid with a sweetish odor that resembles chloroform. It is an unsaturated chlorinated hydrocarbon that is sparingly soluble in water but is readily miscible with organic solvents such as ether, chloroform, or alcohol (15,45,76,103). Its important physical properties are listed in Table 2 while nomenclature and other information are shown in Table 3. Since its octanol/water partition coefficient is 195 and therefore in the range of 100 to 1000, Roberts et al. (74) classify it as moderately hydrophobic. The United States Environmental Protection Agency (EPA) has designated it a "Hazardous Substance" (89) and has included it on the list of 129 priority pollutants (41,94).

Table 3. TCE Nomenclature and Identity Information.

Parameter	Value
Chemical Name	ethene, trichloro-
Common Names	ethylene, trichloro- acetylene trichloride ethinyl trichloride trichloroethylene TCE Trilene Trike
CAS Registry Number	79-01-6
Empirical Formula	C ₂ HCl ₃
Structural Formula	$ \begin{array}{c} \text{Cl} \quad \quad \text{Cl} \\ \diagdown \quad \diagup \\ \text{C} = \text{C} \\ \diagup \quad \diagdown \\ \text{Cl} \quad \quad \text{H} \end{array} $
Molecular Weight	131.40
Percentage Composition:	
	Carbon: 18.28%
	Hydrogen: 0.77%
	Chlorine: 80.95%

Note: Data for this table summarized from references 15, 45, 76, 87, 97, and 103.

Health Aspects of TCE

Any effect of TCE upon man is generally due to exposure through inhalation, skin absorption, and/or ingestion (15,43,76,87). Each of these routes of exposure present distinct problems separately and in combination.

Inhalation is the route of exposure most widely studied and cited in the literature because TCE is used so extensively in industry (87,97). The most predominant physiological effect due to inhaling TCE is depression of the central nervous system (CNS). This effect is the limiting factor used to determine Threshold Limit Values for industrial airborne exposures (15,43). CNS depression, along with loss of visual acuity, loss of coordination, mental confusion and fatigue, is of particular concern with acute exposures. For instance, in a two hour exposure of a volunteer to an airborne concentration of 1,000 parts per million (ppm) TCE, Vernon and Ferguson (93) found adverse effects on the subject's motor skills and visual perception. The same effects were absent after similar exposures at concentrations of 300 and 100 ppm (93). This parallels studies of industrial exposures in which reported effects are generally associated with high transient concentrations instead of time weighted average values during a particular shift (43).

Liver and kidney damage in man has not been definitely linked to TCE exposure in industrial settings (43 87,97,

103). However, liver failure, following use of TCE as an anesthetic, has been observed in patients with complications such as malnutrition, toxemias, and burns (88). Additionally, liver damage in laboratory rats was demonstrated in studies of the synergistic effects of TCE and drugs (5,13).

Absorption of TCE through intact skin is possible but is not significant enough to cause systemic injury. It can, however, defat the skin and cause topical dermatitis (15,43,97).

Little information was found concerning the toxicity and distribution of TCE due to oral ingestion. TCE is reported to be readily absorbed from the gastrointestinal tract since it is a small, uncharged, lipophilic molecule (47,61). The acute oral LD₅₀ of TCE in rats is reported as 4,920 mg/kg (60). Acute poisoning of humans due to ingestion of TCE has produced symptoms of gastrointestinal upset, narcosis, and occasional cardiac abnormalities. Reports indicate these symptoms have been produced in adults who ingested 15-25 milliliters (ml) of TCE. Similar symptoms were produced in a child who ingested only 5 ml (61). The reviewed literature contained no reference to the effects of chronic ingestion of low levels of TCE.

TCE was classified as a possible carcinogenic agent as a result of a National Cancer Institute (NCI) study that

indicated oral ingestion of TCE can result in hepatocellular carcinomas in mice. In the NCI study, male and female rats and mice were intubated daily for 18 months with TCE dissolved in corn oil. Average daily TCE doses given were: male and female rats, 549 and 1,097 milligrams/kilogram body weight (mg/kg); male mice, 1,169 and 2,339 mg/kg; female mice, 869 and 1,739 mg/kg. While none of the rats developed hepatocellular carcinomas, 30.6% of the mice given the low dose and 43.2% of the mice given the high dose developed hepatocellular carcinomas (43,60,61).

The NCI study was criticized immediately upon publication because of the single daily administration of very large quantities of TCE. With such quantities, the distribution, metabolism, and elimination of TCE could have differed significantly from that at lower doses (61). Another criticism pointed out that TCE used in the bioassays contained epichlorohydrin and epoxibutane as stabilizers at levels high enough to possibly suggest they could have accounted for the carcinogenicity in the study. Regardless of criticism, the results of the study have generally been accepted because the grade of TCE used was representative of TCE used industrially (60,88).

Despite the NCI study, there is apparently no evidence that definitely links TCE to cancer in man (43). Furthermore, TCE has not been found to exhibit teratogenic or mutagenic properties in studies with lab animals by

either oral or inhalation routes of exposure (48,61,88, 97).

TCE Occurrence in Groundwater

Since TCE does not occur naturally in the environment (51,63), its existence in groundwater must be considered anthropogenic pollution (74). Indeed, the wide use of TCE offers such tremendous potential for pollution, it has been described as being "ubiquitous" in the environment (51,94). However, as shown by Table 4, other synthetic organic chemicals besides TCE are found in groundwater. In most cases, contaminated groundwater contains more than one of these chemicals with one or two of the compounds present at relatively high concentrations and one or more other compounds present at lower concentrations (20).

Generally, industrial discharges such as accidental spills, leaking storage tanks, illicit dumping, and improper disposal at dump sites have been cited as major sources of contamination (51,63). Specifically, the EPA listed the Findley, Minnesota waste dump as the most hazardous of 418 waste sites targeted for cleanup. One of their major violations had resulted in significant TCE contamination of the local aquifer (59). In the first criminal charges filed under the Resource Conservation and Recovery Act (RCRA), a federal grand jury indicted a leather tannery in Massachusetts for illegal disposal and

Table 4. Synthetic Organic Chemicals Most Commonly Found in Groundwater (92).

Trichloroethylene	Benzene
Tetrachloroethylene	Chlorobenzene
Carbon Tetrachloride	Dichlorobenzenes
1,1,1-Trichloroethane	Trichlorobenzenes
1,2-Dichloroethane	1,1-dichloroethylene
Vinyl Chloride	cis-1,2-dichloroethylene
Methylene Chloride	trans-1,2-dichloroethylene

Table 5. Occurrence of TCE in Drinking Water (92).

Survey	No. Samples	No. Positive	Range of TCE, ug/l
State Data	2,894	810	Trace - 35,000
NOMS	113	28	0.2 - 49
NSP	142	36	Trace - 53
CWSS	452	15	0.5 - 210

Note: State Data - from various state reports on local contamination problems in response to contamination incidents.

NOMS - National Organics Monitoring Survey

NSP - National Screening Program

CWSS - Community Water Supply Systems

storage of TCE (49). In another case, improper use of TCE to remove grease from a septic tank contaminated seven private wells in Long Island, New York (35,51). In Los Angeles County, California, 31 municipal wells in the San Gabriel Valley were closed because of high levels of TCE (20). In Bucks and Montgomery counties of Pennsylvania, 15 communities or towns also closed wells because of TCE contamination (20,63).

TCE contamination is not limited to these examples. Of the 14 chemicals listed in Table 4, TCE has been the one detected most frequently in groundwater samples (20,92). The extent and magnitude of TCE contamination is illustrated by data from the EPA shown in Table 5. The table shows contamination levels as high as 35,000 micrograms/liter (ug/l) but most levels reported were less than 10 ug/l. The state data show higher levels of contamination because these samples were analyzed in response to particular incidents such as spills, monitoring of hazardous waste sites, or citizen complaints of taste and odor problems (92).

Since TCE may be present in groundwater used as a drinking water source, the question arises as to what is a safe level to prevent health risks to humans? As yet, this question has not been fully answered, but various levels have been recommended. In 1978, as recommended by the EPA Criteria and Standards Division, the suggested no adverse

response level (SNARL) was 4.5 ug/l (63). In 1980, the National Academy of Science Safe Drinking Water Committee (NAS) recommended a SNARL of 15 mg/l which did not account for TCE's potential as a carcinogen (61). This potential was taken into account in later calculations by both the NAS and the EPA's Cancer Assessment Group (CAG) to calculate concentrations which, if consumed over a lifetime (70 years) at two liters per day, might result in excess lifetime cancer risks of 10^{-4} (1:10,000), 10^{-5} (1:100,000), and 10^{-6} (1:1,000,000) (92). These concentrations are shown in Table 6. The two groups calculated different concentrations for the cancer risks but all values were within the EPA's probable recommended Minimum Contaminant Level of 5-500 ug/l (92).

Soil Environment

The total soil environment is made up of solid, liquid, and gaseous phases which contain their own physical, chemical, and biological environments. Within these phases are gas:liquid, liquid:solid, and solid:gas interfaces which contribute to the complexity of the soil.

The solid phase is made up of minerals, amorphous precipitates, and organic particles that vary extensively in composition, particle size distribution, and particle surface area depending upon the soil type and depth (1,2). The variation of a soil with depth in its horizontal layers or horizons is one way to classify a particular soil.

Table 6. Projected Cancer Risks for Drinking Water Concentrations of TCE (92).

Projected Cancer Risk	TCE Concentration in Water, ug/l	
	CAG	NAS
10 ⁻⁴	280	450
10 ⁻⁵	28	45
10 ⁻⁶	2.8	4.5

Table 7. Variation in Concentration of Microorganisms with Depth for a Typical Mineral Soil (1).

Depth, cm	Organisms/gram of soil (thousands)				
	Aerobic Bacteria	Anaerobic Bacteria	Actinomycetes	Fungi	Algae
3-8	7,800	1,950	2,080	119	25
20-25	1,800	379	245	50	5
35-40	472	98	49	14	0.5
65-75	10	1	5	6	0.1
135-145	1	0.4	-	3	-

Basically, soils consist of a profile with three layers, the A, B, and C horizons. The surface soil, or A horizon, contains the roots of plants, small animals, and the highest density of microorganisms since it also contains the highest concentration of organic material. Below this is the B horizon, which has less organic matter, roots, and microorganisms. The C horizon, which underlies the B horizon, has very little organic material and a low concentration of microorganisms (1,7).

The organic matter of soil has resulted from the decomposition of plant and animal remains that come in contact with the soil. As the soil microorganisms decompose a residue, the original material is converted to organic complexes which contain, among other things, aromatic and unsaturated ring structures carboxyl, phenolic hydroxyl, alcoholic hydroxyl, carbonyl, methoxyl, and amino groups (2). As reported by Felsot and Dahm (23), because of these functional groups, organic matter contributes 25-90% of the Cation Exchange Capacity (CEC) of many soils.

Black (7) defines the CEC as the sum of the exchangeable cations of a soil. It indicates the measure of the cations held by the clay and organic matter of soil which can be reversibly replaced by cations of acid and salt solutions. The CEC is usually expressed in terms of milliequivalents of ions exchangeable per 100 grams of soil.

The soil particles themselves consist of aggregates of individual particles of silt, sand, and clay. These particles are classified according to size by the following scheme: clay, 0-2 μm ; silt, 2-50 μm ; sand, 0.050-2 mm (11). These particles usually occupy only 40-80% of the soil volume. The rest of the space is composed of pores filled with air and water.

The amount of pore space within a soil depends upon the texture, structure, and organic matter of the soil. Clays generally have a high percentage of pore space with very small pores while sandy soils have large pores but less pore space. Soils high in organic matter also have small pores, or micropores, which contribute to their ability to retain water (28). One aspect of micropores is that the water retained within them may be considered immobile compared to the mobile water which flows through larger pores. The pore space occupied by immobile water has been called the immobile domain with the rest of the pore space classified as the mobile domain (74). Consistent with this nomenclature is that of Houle and Long (33) who report that the effective pore space or porosity of most soils is only 90% of the total volume of pore space within the soil.

The water phase within the soil contains two components. One is the free or gravitational water that freely flows through the pores due to gravity. The other component is water which is held by the soil due to capillary

action because of the polar nature of water molecules and hydrogen bonding with polar surfaces of the soil. This water is held with a tension of about $1/3$ atmosphere and will not freely drain from the soil (2). When the water content of a soil is due to that held by capillary action, the pores also contain large amounts of air and the soil is considered unsaturated. When the pore space is completely filled with water, practically no air or gas phase is present and the soil is saturated (11).

It is clear, then, that the gas and liquid phases of the soil are interrelated. As water moves into the pores, the gas is displaced; the converse is also true. The gas phase within the soil is not exactly the same as that of the atmosphere because of oxygen consumption and carbon dioxide production by microorganisms and plant roots. The carbon dioxide content of soil air usually ranges from 0.3 to 3.0% compared to 0.03% for the atmosphere (2). The oxygen content in soil air is normally below 21% with a drop proportional to the carbon dioxide increase. Since a concentration gradient exists between the atmosphere and the soil air, it is understandable that the surface soil has an oxygen concentration similar to the atmosphere while the lower horizons show lower oxygen contents. Also, the carbon dioxide levels in soil air generally increase with increasing horizon depth (2,28). Saturated soils, however, can quickly become anaerobic because the oxygen demand by

soil microorganisms can deplete the dissolved oxygen within a few hours (1,2).

Alexander (1) lists the five major groups of soil microorganisms as bacteria, actinomycetes, fungi, algae, and protozoa. Bacteria are the most prominent group because they usually outnumber the other four groups combined. Bacteria are usually attached to the soil particles through electrostatic attractions or due to their extracellular secretions. The number of organisms that move with the soil water is very limited since they usually remain attached to the soil particles.

The concentration of bacteria and other microorganisms can vary widely depending upon the type, moisture content, and organic composition of the soil. Concentration of microorganisms generally parallels the concentration of organic matter in soil as discussed earlier. Table 7 shows the variation in concentration of microorganisms with depth of a mineral soil as reported by Alexander (1). Additionally, Alrichs (2) states that nearly all microorganisms are found in the A horizon and that organic molecules that reach the lower horizons stand a greatly reduced chance of biodegradation.

Other factors affect the population of microorganisms and their proliferation. The optimum moisture level for growth of many aerobic soil bacteria is reported as 50-75% of the moisture holding capacity of soil. Fluctuations in

this moisture level can cause fluctuations in the numbers of microorganisms (1,27). Another factor is addressed by Alrichs(2) who states that the microorganisms usually exist in a substrate limited growth until incorporation of additional organic matter stimulates activity and growth. A neutral pH is considered optimum for most microorganisms (1,27), but many can exist at pH as low as 3.0 (1). Temperature affects the rate of growth; an increase in temperature stimulates biological activity up to a point, while a decrease in temperature can curtail activity. Nitrogen is the key nutrient required to decompose organic matter. If the soil is high in readily available nitrogen, then the microorganisms need no additional source. Conversely, substrates with low nitrogen content may require addition of ammonium or nitrate sources of nitrogen before biodegradation of organics can occur (1).

Chemical Transport in Soil

With an understanding of the toxicity of TCE and the nature of the soil environment, attention can be turned to the factors that govern the transport of TCE through soil. Abundant literature is available concerning experimental studies of the fate of organic chemicals in soil or sediment systems. The vast majority of these studies have dealt with pesticides while a number of others are concerned with trace level organics in aquifers. While TCE has not been one of the chemicals widely studied, concepts

and principles from studies with other chemicals apply and can yield valuable information.

When a chemical is introduced into the soil environment, the four processes that basically affect how that chemical is transported through the soil are volatilization, dispersion, sorption, and degradation (10,28,74,77). Each of these processes will be discussed with particular emphasis on adsorption and degradation.

Volatilization

Trichloroethylene, as evidenced by its Henry's Law constant, is volatile. In surface waters, volatilization is considered the most significant fate of TCE (52,94). Dilling et al. (19) found the evaporative half-life of a 1.0 mg/l aqueous solution of TCE to be 21 minutes when stirred, but approximately 90 minutes when only intermittently stirred. Jensen and Rosenberg (34) found that a TCE concentration of 1.0 mg/l had an evaporative half-life of 3.44 days in a partly open 20-liter tank under quiescent conditions.

Little data is available on volatilization rates of TCE or other chemicals from soil. Two studies which briefly addressed this are those of Bouwer et al. (10) and Tomson et al. (83), both of which involved trace organic behavior in rapid infiltration sites. Neither of these studies, however, quantitatively accounted for volatilization losses. Bouwer et al. (10) reported that

volatilization appeared to be the most important mechanism for chloroform removal in soil columns flooded with municipal wastewater that had been biologically treated. To a lesser degree, tetrachloroethylene and 1,1,1-trichloroethane were lost as a result of volatilization. In similar studies, Tomson et al. (83) estimated volatilization losses for a number of volatile organics, including TCE. Their estimates were based upon factors from conditions dissimilar to their own studies and showed greater than 99% volatilization losses for some of the compounds. However, as they pointed out, their estimates showed much greater losses than were accounted for by mass balances on the influent and effluent streams and illustrated the difficulty in predicting volatilization losses.

Dispersion

Flow through a porous medium can cause a chemical in solution to disperse or spread due to varied permeability of the medium, fluid mixing through pores, and molecular diffusion (30,74,77). Soil contains tortuous pore structures that provide varied path lengths for fluid movement which allows for a degree of mixing. This effect has been termed hydrodynamic dispersion. Additionally, the diffusion of a chemical into stagnant pores or immobile domains will also spread the movement of a chemical by slow

release from the pores when the chemical or concentration front has passed (30).

Dispersion is accounted for in the following transport equation that describes one dimensional flow in a saturated, unconsolidated, homogeneous medium (6,24):

$$-u \frac{\partial C}{\partial x} + D \frac{\partial^2 C}{\partial x^2} - \frac{\rho_b}{e} \frac{\partial S}{\partial t} + \left(\frac{\partial C}{\partial t} \right)_{rn} = \frac{\partial C}{\partial t} \quad (1)$$

where D = dispersion coefficient

C = solute concentration in aqueous phase

u = average fluid velocity

x = distance in direction of flow

e = soil porosity

ρ_b = soil bulk density

S = mass of solute adsorbed per unit dry mass of soil

t = time

rn = reaction term

In use of this equation, Roberts et al. (74) state that the value of D determined by laboratory studies or theory was not a good predictor of D for natural aquifers due to the wide spatial variations in the permeability of aquifers. For aquifers or large field studies, dispersion should be accounted for by tracer studies (24,74).

In their study of some nonpolar organic compounds (chlorinated benzenes, toluene, and tetrachloroethylene), Schwarzenbach and Westall (77) did not attempt to quantitatively account for dispersion. In solving the

transport equation for different theoretical adsorption rate constants, they considered dispersion to be insignificant. In studies of movement of the chlorobenzenes through columns packed with fine sand, they graphically compared experimentally determined elution curves with computed elution curves using various known dispersion coefficients. The experimental curves were similar to computed curves for values of dispersion coefficients larger than what they expected for the particle size distribution and fluid velocity used. They attributed the added dispersion to that due to experimental apparatus and sampling technique.

Adsorption

Definition and Description. Adsorption, according to Weber (99), is a surface phenomenon that involves the concentration of a substance at an interface between two phases. While these interfaces can be liquid:liquid, gas:liquid, or gas:solid, the one of interest in this study was the liquid:solid interface. The two main driving forces in adsorption are:

1. The solvophobic (or hydrophobic, in aqueous systems) nature of the solute within the solvent.
2. The degree of affinity of a solute (or adsorbate) for the solid surface (or adsorbent).

Adsorption is commonly classified into three different types: exchange, chemical, and physical.

Exchange adsorption is a result of electrical attraction of an adsorbate for an adsorbent which allows ions in solution to bind with charged sites on the solid surface (28,99). Chemical adsorption (or chemisorption) also involves specific site bonding, but instead of ionic bonding, a chemical bond is formed between the adsorbate and adsorbent which prevents free movement of the molecule on the surface. Chemisorption is also characterized by a high heat of adsorption (30-80 kcal/mole) (28,99). This allows adsorbent site saturation at low adsorbate concentration and adsorption at elevated temperatures where physical adsorption is not of much consequence (28). In physical adsorption, the heat of adsorption is generally low (2-10 kcal/mole) and the adsorbed molecule is not fixed to a specific site but can freely move around the surface. This adsorption is largely due to Van der Waal's (or intermolecular) forces which attract nonionic, nonpolar molecules such as hydrocarbons in water (8,99). Other intermolecular forces that act in adsorption are direct and induced ion-dipole and dipole-dipole interactions and transient dipole-induced dipole interactions termed Van der Waal's--London Interactions. Adsorptive forces also include hydrogen bonding and hydrophobic interactions between the solute and adsorbate (28).

While distinctions are made between the different types of adsorption, it is commonly agreed that adsorption

of an organic molecule can rarely be attributed to only one type. Rather, it is felt that adsorption can be a combination of any or all of the different types, particularly a combination of physical and chemical adsorption which are not always easily differentiated (8,28,99). This is particularly true in soils, which are composed of heterogeneous substances (28).

Isotherms. When an adsorption system is in equilibrium, a definite distribution of solute exists between the liquid and solid phases. This distribution is described by an isotherm which relates the mass of solute adsorbed (adsorbate) per unit mass of adsorbent to the equilibrium concentration of solute in the liquid phase. To establish data to describe an isotherm, a known amount of adsorbent is added to a known amount (or concentration) of solute (or adsorbate) in solution. The system is allowed to reach equilibrium with the amount of adsorbate removed from solution in the liquid phase considered to be adsorbed. This data can be used in a number of different equations to generate isotherms such as the Langmuir, Freundlich, or linear (28,99).

The Langmuir equation was developed from a kinetic and thermodynamic conceptual basis for the adsorption of gases onto solids. The assumptions used in its development were: (1) constant energy of adsorption which is independent of surface coverage; (2) adsorption is localized with no

interaction between adsorbate molecules; and (3) maximum adsorption consists of a saturated monolayer of solute molecules (8,28,99). The equation can be written as:

$$X/M = \frac{Q^{\circ}bC}{1+bC} \quad (2)$$

Where X/M = mass of solute adsorbed per unit mass of adsorbent

Q° = mass of adsorbed solute per unit mass of adsorbent required to form a complete monolayer on the surface

b = a constant indicative of the energy of adsorption

C = equilibrium concentration of solute in solvent

An equation related to the Langmuir isotherm is the Brunauer, Emmet, and Taylor (BET) isotherm. It is conceptually similar to the Langmuir except the BET assumes multilayer adsorption on the surface sites (99). The BET is rarely used to describe adsorption and will not be discussed further. In fact, the Langmuir equation is very seldom used in soil adsorption systems because the heterogeneity of the soil surfaces quite possibly invalidates the assumption of constant energy of adsorption (28). Of the literature reviewed for this research, no use of the Langmuir isotherm was found.

An often used equation in soil adsorption studies is the Freundlich isotherm, an empirical equation stated as:

$$X/M = K_F C^{1/n} \quad (3)$$

Where X/M = mass of solute adsorbed per unit mass of adsorbent

C = equilibrium concentration of solute

K_F = an equilibrium constant indicative of adsorptive capacity

$1/n$ = a constant indicative of adsorption intensity

This equation has a major disadvantage in that it places no limit on the amount of adsorption that can occur on a surface as equilibrium concentration increases. Theoretically, it can predict that adsorption will increase infinitely, however, it should not be extrapolated past the range of solute concentrations over which it is developed (8,99). The Freundlich equation agrees reasonably well with the Langmuir equation over moderate concentrations of C but not well at high concentrations. It does not reduce to a linear equation at low concentrations as does the Langmuir (99). Nevertheless, it has been widely used in soil adsorption studies with a variety of compounds such as: benzene (75); 2,4-D amine and atrazine (66); hexachlorocyclohexane (95); 2,4,5-T (47); organophosphorous and carbamate insecticides (23); DDT, dieldrin, lindane, diazinon, and parathion (79); and TCE (70). In the majority of these studies, the value of the constant $1/n$ is very close to unity.

Another equation often used is a form of the Freundlich equation with $1/n$ equal to one. In this case, the equation describes a distribution or partitioning

between the two phases by a linear relationship (28,38).
The equation for the linear isotherm is:

$$X/M = K_p C \quad (4)$$

Where X/M = mass of solute adsorbed per unit mass of adsorbent

C = equilibrium concentration of solute

K_p = linear partition coefficient

This isotherm equation has found wide use in many soil adsorption studies, particularly at low solute concentrations. Included among the compounds to which this isotherm has been applied are: polynuclear aromatic hydrocarbons (PAHs) (55,56); toluene, tetrachloroethylene, and chlorinated and methylated benzenes (77); pyrene, methoxychlor, naphthalene, and benzene (38); and various polychlorinated biphenyls (PCBs) (50).

Related to the linear partition coefficient or constant, K_p , is a coefficient, K_{oc} , based upon the fraction of organic carbon present in the adsorbent (28,30,38,39,55). The relationship is:

$$K_{oc} = \frac{K_p}{f_{oc}} \quad (5)$$

Where f_{oc} = fraction of organic carbon in the adsorbent

Similarly, in several studies (23,65,75) the Freundlich equilibrium constant, K_F , was normalized on the basis of organic carbon as:

$$K_{OCF} = \frac{K_F}{f_{oc}} \quad (6)$$

Organic Carbon. The use of the coefficients of Equations 5 and 6 emphasizes the importance of organic carbon content in adsorption. These coefficients allow comparison of adsorption of neutral molecules based solely upon organic carbon content without regard for adsorption due to other properties of the soil. Thus, for a series of soils tested with the same compound (assuming no other property affects adsorption), the K_{OC} or K_{OCF} for each of the soils should not vary significantly from the average for all of the soils (28,30,38). Laboratory studies have illustrated the relation between adsorption and organic carbon content.

Means et al. (55) studied the adsorption of four PAHs on 14 different soils and sediments which had organic carbon contents of 0.11 to 2.38%. They found a significant correlation between the K_p for each PAH and the organic carbon content of each soil. The soils with the higher organic carbon content exhibited higher K_p 's which, when converted to K_{OC} 's, converged on the mean value for all the adsorbents studied. The average K_{OC} 's were then used to compare the strength of adsorption of the different PAHs.

Schwarzenbach and Westall (77) also reported a highly significant correlation between K_p and organic carbon content but only when the adsorbents contained more than 0.1% organic carbon. Their study, conducted with a series of chlorinated benzenes and natural aquifer materials,

found little correlation for K_p when the organic carbon content was less than 0.1%.

Sharom et al. (79) compared the adsorption of aqueous insecticide solutions on four different soils with organic carbon contents of 0.7, 2.5, 2.8, and 75.3%. The insecticides included six organophosphorus, four organochlorine, and two carbamate insecticides of different chemical structures and water solubilities that ranged from 0.0012 mg/l to a totally miscible compound. The K_F values obtained from batch isotherm tests for each of the 12 solutions decreased for each of the soils in the order of decreasing organic carbon content. This relationship was also reported by Richter (70) in a study of TCE in aqueous solutions at concentrations up to 1.1 mg/l with peat and a variety of inorganic soils.

Felsot and Dahm (23) approached the organic carbon: adsorption relationship in a different way. They initially determined adsorption isotherms for some organophosphorus and carbamate insecticides with various soils, then oxidized the organic matter of the soils with hydrogen peroxide. Redetermination of adsorption isotherms with the oxidized soils showed that adsorption decreased within the same soils in proportion to the fraction of organic carbon destroyed.

Octanol:Water Partition Coefficient. According to Karickhoff (39), the organic carbon in soil acts in the

same manner as a solvent in a water:immiscible solvent extraction. Based upon this concept, he proposed a correlation between the linear partition coefficient (K_p) and a solvent:water partition coefficient. He developed this correlation for a series of polycyclic aromatic compounds and chlorinated hydrocarbons that had water solubilities ranging from 1 microgram/liter ($\mu\text{g/l}$) to 1,000 milligrams/liter (mg/l) (38). He correlated the octanol:water partition coefficient (K_{ow}) of the individual compounds with K_{oc} 's determined for the individual compounds and averaged for three different sediments used as adsorbents. Linear least squares fitting of the data resulted in the following relationship:

$$K_{oc} = 0.63 K_{ow} \quad (7)$$

From Equation 5,

$$K_p = 0.63 K_{ow} f_{oc} \quad (8)$$

A similar relationship was developed by Schwarzenbach and Westall (77) as:

$$\log K_p = 0.72 \log K_{ow} + \log f_{oc} + 0.49 \quad (9)$$

These equations are useful to predict K_p within a factor of two for nonpolar organics and soil or sediment but are truly valid only for the compounds and range of concentrations used in the studies. Extrapolation beyond this may increase the error of the estimate (38,77).

Other Factors. Of the literature reviewed, only Felsot and Dahm (23) reported a high correlation between adsorption

and CEC of adsorbate. Since they found an even higher correlation between the organic carbon content and CEC, they concluded the correlation between adsorption and CEC was related more to the organic content of the CEC than to the CEC itself. Others (40,50,55,75) reported the CEC of soil adsorbents but made no correlation between adsorption and CEC. In these studies (40,50,55,75) the soils with higher organic carbon content generally had higher CECs except for some soils with significant clay contents.

The pH of a soil system can affect adsorption for weak acid and weak base organics. These compounds can exist in either an ionized or non-ionized form depending upon pH. At low pH, weak acids are in the free acid state while weak bases are cationic; both compounds are adsorbed more highly in these forms than at higher pH (28,47). Generally, though, adsorption of nonpolar compounds shows no marked pH effect unless the pH of the soil solution was changed drastically enough to produce a change in soil components which affected adsorption (27). There is little discussion on pH effects in the literature. Felsot and Dahm (23) found no correlation between adsorption and soil pH. Other studies (40,47,50,55,56,65,75,95) list soil pH values but do not discuss them in any way.

One aspect of pH effects is that pH, organic matter, CEC, and other soil properties are so interrelated it can be difficult to separate the effect of pH alone (28).

Additionally, soil pH measurements are determined on slurries of 1:1 or 1:2 soil:water ratios (7,64) which might not accurately define the hydrogen ion activity of the soil.

Surface Effects. Since adsorption is a surface phenomenon, the extent of adsorption should be proportional to the surface area of the adsorbent (99) which, in the case of soil adsorbents, is related to the particle size (38,77). Surprisingly, few references to the effect of particle size were found. In addition, there was no general agreement on the particle size to be used for batch isotherm tests as illustrated by Table 8 which presents data from some representative studies.

Karickhoff et al. (38) were concerned not with increase in surface area with the decrease in particle size, but with the difference in organic carbon content with different particle size fractions. They reported the organic content of soils is most heavily found in the fines fraction (less than 50 microns). They reported that adsorption by smaller particles is basically due to the organic carbon content, not increased surface area. However, when correcting for organic carbon content by use of K_{OC} , they found, for the same organic compound, the K_{OC} of the sand fraction to be less than 50% of the K_{OC} for the fines fraction. This indicated a certain dependence upon particle size. For nonporous adsorbents, such as sand

particles, surface area available for adsorption is inversely related to particle diameter (99).

Schwarzenbach and Westall (77) approached this factor in a different manner. Their concern was that washing soil samples prior to use in adsorption studies can affect the results of the study. They found that increased length of washing lowered the K_p of a sand for a series of chlorobenzenes. The lowered K_p resulted from removal of clay and silt particles which were attached to the sand particles but could be removed through continued agitation and washing. They concluded that to obtain representative sorption data of a particular sample, soil should not be washed before use.

As shown by Table 8, various particle sizes have been used to develop isotherms. These studies, though, provide no duplication of compound with different particle sizes to see if a difference in adsorptive capacity exists due to particle size. A difference may not be expected for nonporous adsorbents. For highly porous organic fractions, however, breaking large particles into smaller particles might open sealed interior pores and surface areas normally not available for adsorption. Such an increase in surface area could increase adsorptive capacity which would indicate a dependence of adsorptive capacity on particle size (99).

Table 8. Particle Size Information From Representative Soil Adsorption Studies.

Particle Size, mm	Particle Size Effect Discussed	Type of Study	Reference
< 0.833	No	(1)	56
< 0.075	No	(1)	70
< 4	No	(2)	40
< 0.833	No	(1)	55
Not listed	No	(1)	75
(3)	Yes	(1)	38
< 0.150	No	(1)	95
Not listed	No	(1)	47
(4)	Yes	(1)	50
< 2	No	(1)	65
< 2.3	No	(1)	23
< 0.125	Yes	(1)	77
0.63-0.125	Yes	(1)	77

- Notes:
1. Batch isotherm studies.
 2. Packed column elution study.
 3. Separated into silt, sand, clay fractions.
 4. Results discussed on basis of surface area measurements.

Adsorption Equilibrium. Three steps are involved in the overall adsorption process (99):

1. Transport of the adsorbate through the bulk of the solution to the surface of the adsorbent (film diffusion).
2. Diffusion into the pores of the adsorbent (pore diffusion).
3. Adsorption at the surface.

For nonporous adsorbents, step 2 is fairly insignificant (28). Since the adsorption step itself is quite rapid, the rate limiting step in soil:water adsorption systems is usually either step 1 or 2 (23,99).

If one assumes similarity with carbon adsorption, the rate limiting step depends upon the degree of contact the particle has with the aqueous solution. In batch isotherm tests, the system is continuously shaken so the degree of agitation is high. In this case, step 2 or 3 would be the rate limiting step. In column studies, a laminar boundary layer may surround the soil particle and step 1 can control (98).

In batch isotherm studies, equilibration times vary depending upon the compound, concentration, and adsorbent. Some investigators do not determine an equilibration time but use a standard 24 or 48 hour contact time. Table 9 lists some equilibration times from isotherm studies. Compared to batch studies, the number of soil column

Table 9. Reported Equilibration Times for Batch Isotherm Studies.

Compounds(s)	Concentration Ranges, ug/l	Equilibration Time, Hours	Reference
TCE	11 - 1,100	18	70
Chlorobenzenes	20 - 100	18	77
PAHs	0.02 - 100	20	55
Benzene	3 - 1,000	16	75
2,4,5-T	510 - 45,000	24	47
Organophosphorus and carbamate insecticides	40 - 400	2	23

studies reported is small. Some parameters of applicable packed column tests are listed in Table 10.

A concept of interest in soil column studies is local equilibrium. This condition is achieved when the rate of mass transfer of a solute to an adsorption site is fast compared to the pore velocity of water through the soil (34,40). In effect, this concept could indicate that flow rate affects adsorption.

Flow rate. One study of chlorobenzene (CB), 1,4-dichlorobenzene (DCB), and 1,2,3- and 1,2,4-trichlorobenzenes (TCBs) reported the effect flow rate had upon these compounds in a packed column of fine sand. The feed to the column was with a constant concentration, C_0 , of the compound at actual flow velocities of 8.7×10^{-4} cm/sec (low) and 1.0×10^{-2} cm/sec (high). They reported effluent volumes in terms of pore volumes (PV) of water passed through the column with break-through considered when the concentration in the effluent (C_e) was approximately equal to C_0 . Table 11 summarizes the results from this study. As shown in Table 11, the order of magnitude difference in flowrate had the most effect on TCB with less effect on DCB and virtually no effect on CB. The number of PV until the compound appeared in the effluent and until breakthrough, increased in the order of increasing K_{ow} for both flow velocities. The earlier

Table 10. Parameters From Packed Column Adsorption Studies.

Size, cm length x i.d.	Flowrate, cm/sec(1)	Diff. noted with increased flowrate	Compound(s) Studied	Concentration, ug/l	Reference
29x1.2	8.7x10 ⁻⁴ 8.0x10 ⁻⁴ 1.0x10 ⁻²	Yes	Chloro- benzenes	40	77
15x7.5	1.21x10 ⁻⁴	(2)	Pesticides	50-5,000	65
30.5x7.6	(3)	(2)	Pesticides	(4)	40
275x10	2.8x10 ⁻⁴ - 4.6x10 ⁻⁴	No	Chloroform 1,1,1-tri- chloroethane tetrachloro- ethylene	1-10	10

Notes: (1) Flowrate is pore water velocity.
 (2) Not discussed.
 (3) No flowrate given.
 (4) Concentration not listed.

Table 11. Summary of Data from Packed Column Study (77).

Parameter	Chemical Compound		
	CB	DCB	TCB
Log K _{ow}	2.71	3.38	4.05
<u>Low Velocity</u>			
PV to appearance in effluent	1.5	4	9
PV to breakthrough	2.5	10	20
<u>High Velocity</u>			
PV to appearance in effluent	1.5	3	5
PV to breakthrough	2.5	7	12

appearance of the compound and earlier breakthrough for high velocities may indicate lack of local equilibrium.

The fact that the compound did not appear in the effluent until after at least one PV indicated that adsorption can retard the movement of an advancing solute concentration front. In this case TCB was retarded the most. This illustrates the relationship between K_p and K_{ow} of Equation 8.

Retardation. Retardation of an advancing solute concentration front has been extensively discussed (65,66,72,74,77,83). If local equilibrium and linear adsorption are assumed,

$$\frac{dS}{dC} = K_p \quad (10)$$

With this relationship, the transport equation (Equation 1) can be used to predict retardation. If dispersion and reaction terms are neglected, Equation 1 becomes:

$$-u \frac{\partial C}{\partial x} = \left[1 + \rho_b K_p / e \right] \frac{\partial C}{\partial t} \quad (11)$$

$$\text{Where } \left[1 + \rho_b K_p / e \right] = t_r$$

The term t_r is defined as the retardation factor which, within a soil column, would theoretically determine the number of pore volumes of water that would pass through before breakthrough. Since the values of ρ_b and e do not vary extensively within a given area, K_p determines the size of the retardation factor. Since K_p can be estimated

according to Equations 8 and 9, the retardation term can also be estimated from knowledge of K_{OW} , f_{OC} , b , and e .

In a similar fashion, if a solute follows a Freundlich isotherm and local equilibrium exists, Equation 3 becomes:

$$X/M = S = K_F C^{1/n} \quad (13)$$

$$\frac{dS}{dC} = K_F^{1/n} C^{1/n-1} \quad (14)$$

and the transport equation becomes:

$$-u \frac{\partial C}{\partial x} = \left[1 + \frac{\rho_b K_F^{1/n} C^{1/n-1}}{e} \right] \frac{\partial C}{\partial t} \quad (15)$$

$$\text{Where } \left[1 + \frac{\rho_b K_F^{1/n} C^{1/n-1}}{e} \right] = t_r \quad (16)$$

The retardation terms of Equations 12 and 16 illustrate that with a solute that obeys a linear adsorption isotherm, retardation is independent of concentration. For a solute that follows a Freundlich isotherm, retardation is dependent upon concentration.

To this point, all discussion has centered upon adsorption of a solute from a solution. Very seldom, though, is an adsorbent challenged by a solution in which the solute maintains a constant concentration. Adsorption is a process of dynamic equilibrium. When the solute concentration in the contacting liquid decreases or is eliminated, there is a corresponding decrease in the adsorptive capacity (X/M) of the adsorbate. This process is desorption.

Desorption. Desorption is commonly studied by batch equilibration in a method similar to adsorption isotherm studies. A portion of soil is equilibrated with a known amount of solute. After equilibrium is established, all or a portion of the solution is removed and replaced with water containing no solute, thus lowering the equilibrium concentration. The container is then re-equilibrated and X/M values are calculated from the resulting equilibrium concentration. Any increase in concentration is assumed due to the mass of solute desorbed from the adsorbent (23,65,66,75,95). This procedure can be repeated as often as necessary to develop a desorption isotherm; however, other experimental losses such as volatilization, degradation, or precipitation must be accounted for so they do not unknowingly lead to an overcalculation of the amount of solute still adsorbed (66,75).

Desorption studies can produce isotherms which do not overlap adsorption isotherms. This noncoincidence of isotherms is known as hysteresis. The usual effect of hysteresis is that desorption isotherms show higher adsorptive capacity at lower equilibrium concentrations when compared to adsorption (23,28,47,77). Apart from unknown experimental losses, hysteresis can be due to nonattainment of equilibrium or to changes in the strength of adsorption during desorption over time (28,47). These

two causes may be interrelated and difficult to separate due to the heterogeneity of soil adsorbents (28).

Organic carbon content is a strong factor in desorption. Felsot and Dahm (23) found evidence of hysteresis in conventional adsorption-desorption studies of five different organophosphorus and carbamate insecticides on five soils with varied organic carbon contents. They found desorption decreased for each of the insecticides as the organic content of the soils increased. Further evidence of this relationship came from additional studies on portions of the high organic soils which were oxidized to reduce the organic content. Oxidized portions showed greater desorption than unoxidized portions for all pesticides tested. Similar results were shown with three isomers of hexachlorocyclohexane (HCH) at adsorption equilibrium concentrations of 20-100 ug/l (95). After adsorption equilibration, each sample was subjected to at least four successive desorptions. The authors found the extent of hysteresis to vary among the different isomers but was consistently greater (less desorption) for the higher organic carbon soils. Neither of these studies, however, accounted for losses due to degradation, nonequilibrium, or volatilization.

One study which did account for such loss is that of Koskinen et al. (47) who characterized hysteresis of 2,4,5-T in desorption from soils at concentrations of

1.5-10 mg/l. They studied the effect of equilibration time on desorption by varying desorption times from 3-48 hours. Their initial studies found greater hysteresis (less desorption) for the longer desorption times which was counter to what was expected. After changing their experimental protocol to account for volatilization and biodegradation losses, actual hysteresis decreased for longer desorption times. This indicated that procedural methodology can significantly influence results.

Successive handling of desorption vials and repeated desorption steps with volatile compounds can introduce volatilization losses which, if not accounted for, can also influence apparent results. Rogers et al. (75) addressed this problem in their study of benzene in the 10-1,000 ug/l concentration range. During one phase of their adsorption-desorption studies their reaction flasks had an unrestricted headspace. In this case, a mass balance for adsorbed benzene, benzene in solution, and loss due to biodegradation accounted for only 1-12% of the mass of benzene applied. As they pointed out, volatilization was then responsible for loss of 88-99% of the benzene.

This type of loss by volatile compounds is the reason Schwarzenbach and Westall (77) did not attempt to determine desorption isotherms for the compounds listed in Table 11. They studied desorption by pumping a solution of the compound through a column until breakthrough occurred. At

this point the feed solution was changed to solute free distilled water which caused the adsorbed compounds to desorb from the soil columns. The combined breakthrough-elution curves produced several points worth comment. From a mass balance on the solute in the effluents, they determined that all the material adsorbed on the columns subsequently desorbed. CLB exhibited breakthrough first, had the steepest breakthrough curve, and had a nearly symmetrical elution curve with very little tailing. DCB exhibited breakthrough second, had moderately sloped breakthrough and elution curves which showed moderate tailing. TCB showed breakthrough last and exhibited breakthrough and elution curves less steep than DCB but with extensive tailing. Viewed with K_{ow} in mind, the slopes of the breakthrough and elution curves decreased and the amount of tailing of the elution curves decreased as the K_{ow} of the compound increased. According to the authors, the tailing could have been due to the hysteretic nature of the adsorption-desorption process, adsorption-desorption kinetics, or the variation in strength of adsorption with different sites (nonequivalency of sites).

In a similar column study, Rao et al. (65,66) determined breakthrough and elution curves for 2,4-D amine (50 and 5,000 mg/l) and atrazine (5 and 50 mg/l) in two soils. Both pesticides exhibited non-linear adsorption with Freundlich $1/n$ values less than one. Consequently,

increased mobility of the pesticides was shown for the higher concentration with both soils. For instance, the 50 mg/l 2,4-D solution exhibited breakthrough at eight pore volumes for the high organic (3.87%) soil and three pore volumes with low organic (0.90%) soil. The 5,000 mg/l 2,4-D solution reached breakthrough at two pore volumes for the high organic soil and one pore volume for the low organic soil. Atrazine showed similar results. The shape of the curves was affected by solution concentration and soil organic content. High solute concentrations and low organic soil content produced steeper breakthrough and elution curves compared to low solute concentrations and high organic soil content. Trailing on the elution curve was much more evident in low concentrations and high organic content soils. The authors pointed out that the shape of the breakthrough and elution curves depended upon adsorption-desorption kinetics. Symmetrical breakthrough curves are normally obtained when local equilibrium exists while nonequilibrium normally produces asymmetrical curves (65). The trailing exhibited in this work was attributed to nonequilibrium.

Other desorption studies have been conducted in a manner described by Hamaker (30) as "one-shot leaching." In this type of study a quantity of chemical is added to a soil column and its movement is traced as a function of water applied. One application of this method studied the

movement of synthetic pyrethroid insecticides in packed columns (40). The authors added a quantity of the chemical to the top of the column, then added one pore volume of water to the column and collected the effluent. No pesticides were detected in the effluent. Analysis of the different depths of the column showed very little penetration of the soil by the compounds. This indicated their immobility in soil. In a similar study, Sharom et al. (79) studied 12 insecticides with four different soils. They found all 12 insecticides were more strongly retained and resisted leaching with the higher organic soils compared to the lower organic soils.

Some possible differences between laboratory studies and actual field leaching were addressed by Hamaker (30). He reported that in chemical leaching in the field, intermittent rainfall can leach or desorb a chemical causing a downward migration of the chemical. However, when the soil dries, capillary action can pull some of the water and chemical back towards the surface. Additionally, the tendency of tailing in one shot leaching is due to the same causes discussed earlier, i.e., difference between adsorption and desorption rates and nonequivalency of adsorption sites. One factor that differentiates one shot leaching from column studies with constant solute concentration is that one shot leaching begins with the compound intimately contacted with the soil. According to

Hamaker (28), this contact can cause higher adsorptive capacity and greater hysteresis than would occur with an equivalent amount of chemical in solution.

Degradation

Chemical Degradation

Studies are inconclusive as to whether direct photolysis is a means by which TCE is degraded. By using a closed system in which no volatilization could occur, Jensen and Rosenberg (34) detected no significant difference in TCE concentration for systems maintained in darkness compared to similar systems exposed to sunlight. Dilling et al. (19) studied the abiotic degradation of TCE exposed to sunlight in sealed ampules of 1.0 mg/l solutions with enough oxygen present to completely oxidize all TCE in the ampule. In this case, sunlight increased the reactivity of TCE to the point that its half-life was about 1.7 times shorter in sunlight than in darkness. The authors suggested the degradation products were dichloroacetic acid and hydrogen chloride from free radical oxidation. Any effect of sunlight on chemical reactions is minimal in soil because the radiant energy is strongly adsorbed by the soil. This reduces the chance for photolytic reactions even at the soil surface (27) and basically eliminates them in the subsurface environment (74).

In their studies, Dilling et al. (19) did not differentiate between oxidation and hydrolysis; therefore, the experimentally determined first order reaction rate, 0.0065/month, is a combined rate due to both oxidation and hydrolysis. Hydrolysis alone, though, may not be a significant factor in degradation of TCE. According to work cited by Dilling et al. (19) TCE in water can resist hydrolysis at 100°C. The EPA reports that under normal conditions, TCE is not hydrolyzed in water (94). Reactions in an aqueous medium may be entirely different from those in a soil medium because soil has catalytic properties. Clays, organic and metallic ions, metal oxides, and various organic functional groups are possible catalysts for chemical reactions (27).

Biodegradation

Since the soil contains a living environment, any foreign substance added to it can be subjected to microbial degradation. Biological degradation of anthropogenic compounds by soil environments has been extensively studied. The overwhelming majority of work in this field has been dedicated to pesticides as illustrated by the extensive review presented by Goring et al. (27). Other compounds such as trichlorobenzene (54) and oil (67) have also been studied.

Any consideration of microbial degradation of organic chemicals added to the soil environment must be reviewed

with an understanding that many factors affect biodegradation. These factors, such as pH, moisture content, and oxygen level were previously discussed. Additionally, sometimes it is difficult to separate biodegradation from chemical degradation (27). One reason generally given for the resistance of anthropogenic compounds to biodegradation is that soil microorganisms lack the enzymes necessary to transform the compound to a degree where it can be metabolized (1,27,46). Some resistant compounds include halogenated organics such as pesticides, trihalomethanes, and organic solvents such as TCE (46).

One biodegradability study of TCE was made by Taybak et al. (82) in their study of priority pollutants in static flask cultures. They tested 5.0 and 10.0 mg/l TCE concentrations in BOD dilution water that contained 5.0 mg/l yeast extract and was inoculated with settled domestic wastewater. After static incubation in the dark at 25°C for one week, a subculture was transferred to fresh medium. This medium was likewise incubated with additional subcultures at the end of the second and third weeks. Blanks accounted for volatilization and chemical degradation. At both test concentrations, TCE showed significant biodegradation after gradual adaptation. After blank corrections, the 5.0 mg/l concentration showed losses of 35%, 44%, 53%, and 50% for each of the succeeding weekly cultures. Likewise, the 10 mg/l concentration showed

losses of 16%, 34%, 54%, and 62%. Conditions of the test indicated these losses were due to biodegradation. Other studies, at much lower concentrations, have not shown such significant biodegradation.

Bouwer et al. (9) studied aerobic and anaerobic degradation of TCE in static flask cultures similar to Taybak et al. (82) with these exceptions: yeast extract was not added; concentrations ranged from 10-200 ug/l; aerobic cultures were incubated at 20°C; weekly subcultures were not used; anaerobic cultures were incubated at 35°C; and anaerobic cultures were seeded with anaerobically digested sludge. All cultures were compared to sterile blanks incubated to account for other losses. Aerobic conditions produced no significant degradation for the concentration range tested for any of the cultures during the 25 week incubation period. Anaerobic conditions showed a very slight degradation compared to sterile controls during the 16 week incubation; however, the authors felt the results were not conclusive.

A field study of groundwater recharge in California presented some evidence of biodegradation of various halogenated organics, including TCE. Roberts et al. (73) studied the decrease in concentration of various compounds in an observation well of an aquifer subjected to groundwater recharge by reclaimed water. When injection was halted, the adsorption capacity of the aquifer was

considered saturated because breakthrough of all compounds had occurred. TCE concentration then declined linearly from 10 ug/l to 2.5 ug/l at a rate of 0.003 ug/l/day when corrected for dilution. The authors considered this evidence of biodegradation. This rate found for TCE, however, was an order of magnitude less than that found for trihalomethanes, which degraded from 20 ug/l to 0.75 ug/l at a rate of 0.03 ug/l/day. The area under study was a silty sand and gravel aquifer 10 to 15 meters below the soil surface.

Wilson et al. (101) conducted a biodegradation study with samples of four different subsurface aquifer materials obtained aseptically and uncontaminated with surface microorganisms. The compounds studied were: 1,1-dichloroethane; chloroform; 1,1,1-trichloroethane; trichloroethylene; tetrachloroethylene; toluene; chlorobenzene; and styrene. Solutions of these compounds at 1.0 mg/l were mixed with slurries of the subsurface materials and incubated in the dark for up to 27 weeks. Periodically, samples were analyzed and compared to sterile controls. They found no evidence of biodegradation for 1,1-dichloroethane, chloroform, or 1,1,1-trichloroethane in any of the samples while toluene and styrene were slowly degraded in all four subsurface slurry systems. Chlorobenzene, tetrachloroethylene, and trichloroethylene showed detectable biodegradation in some but not all of the

subsurface samples. The reported rate for TCE was 1.3 to 2.3% of the initial compound per week.

The variation in biodegradation with variation in location of sample is not unusual. The microbial population varies so considerably with location and depth that Goring et al. (27) consider this variation to be the most unpredictable factor involved in the degradation of pesticides and other chemicals in soils. Additionally, materials that are highly insoluble in water or are highly adsorbed by the soil can resist degradation in soil microcosms to a greater degree than would be shown in other media (27). With the large surface area provided by the fine grained material of the soil, the idea of biodegradation by an attached film, or biofilm, has been proposed for organic substances in a porous medium such as soil (57,74). This film requires three separate but interrelated steps: mass transfer of the organic from the bulk of the solution to the attached film; biodegradation within the film; and film growth and decay. Since a detailed description of fixed film kinetics is not within the scope of this investigation, the reader is referred to McCarty et al. (57) and Rittman et al. (71) for further information.

Regardless of the manner in which biodegradation of TCE occurs, it appears the initial step is usually dehalogenation (46). Goldman (26) presented several

biological mechanisms for dehalogenation of halogenated short chain fatty acids. Dehalogenation is considered a necessary step before beta oxidation of the fatty acids can occur. Neither Goldman (26) nor others, though, reported any particular scheme for dehalogenation of TCE. Kobayashi and Pittman (46) presented a general scheme for reductive dehalogenation by oxidation-reduction as shown in Figure 1. Essentially, this scheme depicts the transfer of electrons from reduced organic substances by microorganisms or abiotic mediators such as NAD, NADP, flavin, flavoproteins, hemoproteins, porphyrins, chlorophyll, cytochromes, and glutathione. The mediators accept the electrons from reduced organic substances and transfer them to the halogenated compound. Free available electrons and direct contact between the donor, mediator, and acceptor of electrons are required for this scheme to function.

Parsons et al. (62) found evidence for this type of dechlorination of TCE in studies with several muck and mud samples. They found the initial chloride ion extracted preferentially formed cis-1,2-dichloroethylene over trans-1,2-dichloroethylene. This preference was attributed to the fact that water, as a polar solvent, prefers the more polar cis-isomer of dichloroethylene.

The literature contains many references to degradative pathways for numerous synthetic organic chemicals (27), including chlorinated aromatics (26,54). No reference,




Figure 1. Possible Routes of Reductive Dechlorination (46).

however, was found to any mechanism or pathway for the degradation of TCE.

Summary

The literature confirms that TCE is present in a significant number of groundwater sources. This is understandable since the production of TCE for 1981 (according to Table 1) was 365,000,000 pounds. If only 0.0001% of this were subsequently lost to groundwater, it could contaminate 8.76×10^{12} gallons of water at 500 ug/l. This volume is equivalent to the lifetime drinking water supply of over 640 million people.

Also widely documented is the correlation between adsorption and the organic content of soil. Little information exists, however, on the effects of flowrate on desorption. Furthermore, information on the adsorption, desorption, and movement of organic chemicals (except for pesticides) in soils at high concentrations is lacking. While some information is available on the movement of trace organics in aquifers (57,72,74), Richter's work (70) with low concentrations of TCE was the only soil adsorption study noted. Even Karickhoff's extensive review (39) of soil-organic chemical adsorption did not contain data for TCE although 13 other chlorinated hydrocarbons were listed. No studies were found which traced the movement of a spill or slug of TCE through soil. Additionally, degradation of

TCE has been studied, but under conditions dissimilar to actual field conditions.

Significant throughout the literature on column studies is the use of pore volume or void volume as a common descriptor for the amount of effluent collected from a column (28,30,33,40,65,66,77). This description is used to provide a common basis on which to correct for differences in bulk densities between soils in column studies.

Factors which should be considered, then, in a study of the movement of TCE in soil are the effects of organic carbon content, role of degradation, and effect of flowrate.

MATERIALS AND METHODS

Description of Soils

The two soils used in this study were Chalmers Silty Clay Loam and Russell Silt Loam, both native to Tippecanoe County, Indiana. These soils were selected for two main reasons: the soils had sufficiently different organic carbon contents to allow comparison based upon this parameter; and they are fairly common type soils to many parts of the country as compared to peat, muck, sediment, or extremely sandy soils. The soils are described in detail by the standard nomenclature as reported by the Soil Conservation Service of the U.S. Department of Agriculture (86).

Chalmers Silty Clay Loam

This is one of the most fertile soils in Tippecanoe County and is found in depressions on broad, gently undulating upland till plains in western Tippecanoe County. The soil profile is described as follows (86):

Depth 0-10 inches: very dark gray to black silty loam; relatively high in organic matter; moderate coarse

granular structure; firm when moist; slightly acid to neutral.

Depth 10-15 inches: very dark gray to black silty clay loam; faint yellowish-brown mottling in lower part; coarse granular structure in upper part grades to moderate medium angular blocky in lower part; firm when moist; slightly acid to neutral.

Depth 15-29 inches: mottled gray and yellowish-brown silty clay loam or clay loam; moderate coarse angular blocky structure; very firm when moist; contains dark-gray organic material along the vertical cracks; slightly acid to neutral.

Depth 29-36 inches: mottled gray and yellowish brown loam; contains sand and gravel which may be in thin, slightly stratified layers; moderate coarse to very coarse angular blocky structure; firm when moist; neutral.

Depth 36 inches + : mottled gray and brown loam glacial till; moderately compact; calcareous.

Russell Silt Loam

This soil is extensively found throughout Tippecanoe County. The Russell soil series are found on low knolls and short ridges that slope to a nearly level till plain. The profile is described as follows (86):

Depth 0-7 inches: brown to grayish brown smooth silt loam; low in organic matter; moderate to weak medium granular structure; friable; medium acid to slightly acid.

Depth 11-18 inches: yellowish-brown to dark brown smooth light silt loam; moderate to strong fine subangular blocky structure; slightly firm when moist; medium acid to strongly acid.

Depth 18-28 inches: dark brown or dark yellowish-brown smooth silty clay loam; moderate to strong medium blocky structure; firm when moist, slightly hard when dry; strongly acid to medium acid.

Depth 28-54 inches: dark yellowish brown to dark brown silty clay loam; moderate coarse subangular blocky structures; firm when moist, hard when dry; contains considerable grit and small rock fragments; medium acid to strongly acid in upper part, grading with depth to slightly acid to neutral in the lower few inches.

Depth 54 inches + : brown or pale brown loam to light clay loam glacial till, calcareous.

Soil Sample Collection

Core samples of the soils were obtained with a stainless steel core sampler four feet long having an inside diameter of three inches at the cutting head. The sampler was driven into and removed from the soil with a hydraulically operated soil sampler manufactured by Giddings Machine Company of Fort Collins, Colorado (serial number GSP-M-5-722) which was mounted on a pickup truck chassis. For illustration of the sampling rig in operation and a view

of the sampling probe, the reader is referred to Emig (100) and Wentink (22).

A procedure was developed to protect the soil cores from fracture or other disturbance during transport to the laboratory. After removing the sampler from the soil, the cores were extruded from the sampler onto one-half of a 42-inch length of three-inch inside diameter PVC pipe which had been cut in half lengthwise. The other half of the PVC pipe was then placed over the exposed portion of the soil core. Plastic bags were used to cover the end of the cores. The ends and open seams of the pipe were then sealed with duct tape to prevent moisture loss. All soil cores were stored in the pilot plant room of the Civil Engineering building until needed.

All sample cores of the Chalmers and Russell soils were obtained from the Purdue University Agronomy Farm in Tippecanoe County, Indiana. For each soil, all cores were obtained from within an area of approximately 120 square feet. Twenty-eight soil cores of each type of soil were taken to ensure enough cores were available for testing.

Soil Analyses

General

A sample of each profile depth for each soil was air dried and crushed or ground fine enough to pass a No. 10 (2 mm opening) sieve. Approximately 300 grams of each of the

sieved samples were submitted to the Purdue University Soil Characterization Laboratory for the analyses indicated in Table 12.

Table 12. Analyses Conducted by the Soil Characterization Laboratory.

Analysis	Method	Reference
Cation Exchange Capacity	Sum of Extractable Cations	(64)
Organic Carbon Content	Meibus	(64)
Particle Size Distribution	Standard	(64)
Soil pH	1:1 Water	(64)

Bulk Density

This test was run in duplicate for each soil profile depth according to the procedures outlined by Black (7) and Purdue University Agronomy Department (64).

Specific Gravity of Soil Particles

Specific gravity was determined on duplicate samples for each soil profile depth according to ASTM method D 854-58 (1) and Black (7). These tests were run on soil samples which passed a No. 10 sieve.

Chemical Analyses

pH and Effluent Volume

The pH of the column effluents from the water application phase of the research studies was measured with a Corning Model 125 pH meter which was calibrated each time it was used with a standard pH 7.0 phosphate buffer solution. Effluent volumes were measured and recorded to the nearest milliliter (ml) with a 100 ml graduated cylinder.

Nitrogen

Ammonia nitrogen was determined according to the Phenate Method of Standard Methods (3). This method had a sensitivity of 10 micrograms (ug) ammonia nitrogen/l and was applicable up to 0.5 mg/l. Samples with concentrations greater than 0.5 mg/l were quantitatively diluted prior to analysis. Nitrate nitrogen was measured by the Cadmium Reduction Method of Standard Methods (3). Nitrite nitrogen was determined according to Section 419 of Standard Methods (3).

Chlorides

Chlorides were determined with an Orion Model 96-17 chloride electrode operated from a Model 90 pH/mV meter made by Markson Science, Incorporated. The low level measurement procedure from Orion was used with a low level calibration curve (1.0-48 mg/l) prepared for each sampling run.

Suspended Solids

Suspended solids were determined with Gelman Metrical Membrane Filters (GA-6), 0.45 micron pore size, according to the following procedure:

1. Filters were dried in a 103°C oven for two hours, cooled in a dessicator, and weighed.

2. A 100-300 ml volume of filtrate was produced by vacuum filtration.

3. Filters and residue were dried for at least two hours in a 103°C oven, cooled in a dessicator, and reweighed.

4. A blank filter was processed in the same manner using deionized (DI) water as the filtering solution to correct for any weight gain or loss due to the filter alone.

5. Suspended solids were calculated by:

$$\text{Concentration (mg/l)} = \frac{\text{Weight gain in filter in mg}}{\text{Volume of filtrate in liters}} \quad (17)$$

Trichloroethylene Analyses

Column Effluent Analysis

Determination of the TCE concentration in the column effluents resulting from the water application phase of the research studies had to be accomplished by a procedure which met the following criteria:

1. The procedure had to be readily accomplishable due to the expected number of samples and availability of analytical equipment.

2. The procedure had to be able to measure concentrations of TCE in the high mg/l range.

The procedures available for analysis by gas chromatography (GC) included liquid:liquid extraction (LLE), purge and trap, and headspace gas chromatography. LLE using pentane is an accepted, accurate method to quantify TCE in water at the ug/l level (25,32,69,90). It was, however, time consuming and not recommended for levels over 50 ug/l (90). The purge and trap method can be used for TCE (12,42,68,84), but the equipment necessary for this analysis was not available.

Because of the limitations of LLE and purge and trap, headspace gas chromatography (or static headspace analysis) was the method chosen.

Principle: Static headspace analysis is based on the distribution of volatile organics between liquid and gaseous phases. When volatile organics are allowed to come to equilibrium with the vapor headspace in a sealed container, the concentration in the headspace is proportional to the concentration in the water (14,18,44,58,84). The distribution of the organic compounds between the two phases depends upon the effects of vapor pressure, temperature, and ratio of headspace to liquid volume in the container. By keeping

these factors constant, the concentration of the compound in the vapor phase then depends only upon the concentration in the liquid phase (14,18).

Analysis of the headspace gas of the sealed container can allow determination of the aqueous TCE concentration with four major advantages: (1) only relatively volatile compounds readily distribute into the headspace, thereby providing a form of sample cleanup (18); (2) many column and detector contamination problems are eliminated since only gaseous samples are analyzed (14,18); (3) the method can be used for concentrations that vary from the ug/l to the mg/l range; and (4) the method is less time consuming than LLE or purge and trap (18).

GC Operating Conditions. The specific analytical procedure used was modeled after that used successfully by Richter (70) which was adapted from that reported by Dietz and Singley (18). Headspace analyses were conducted using a Varian Model 3700 gas chromatograph with a flame ionization detector (FID) and a CDS 111 data system. Specific GC operating conditions were:

Column Temperature: 90°C

Injector Temperature: 140°C

Detector Temperature: 280°C

Carrier gas flowrate (Nitrogen): 30 ml/min

FID gas flowrate: Hydrogen - 30 ml/min

Air - 300 ml/min

Column: glass 10 ft x 1/4 inch outside diameter x 2 mm inside diameter (Supelco No. 2-3738).

Column packing: 10% SP-1000 on 100/120 Supelcoport as supplied by Supelco.

Retention time of TCE on Column: 2.1 - 2.2 minutes (depending upon condition of column).

All glassware used in the analysis of samples or preparation of standards was cleaned according to the following sequence: detergent wash, tap water rinse, dichromic acid wash, tap water rinse, methanol rinse, DI water rinse, followed by drying at 260°C for at least four hours. Samples were collected in 125 ml (actual capacity 160 ml) serum bottles sealed with Teflon faced septa and aluminum crimp caps. The actual sampling procedure will be discussed in Preliminary Investigations.

Standards. Standard solutions were prepared by dilution of TCE saturated water which had a TCE concentration of 1,100 mg/l. TCE saturated water was prepared by adding approximately 10 ml of TCE (reagent grade as supplied by Aldrich Chemical Co.) to 2.5 liters of DI water in an amber glass container and stirring with a magnetic stirrer for two hours. The saturated concentrations were periodically compared with standards made by diluting a stock solution of two grams (precise amount determined by weight) of TCE dissolved in 100 ml of methanol. Standard solutions were transferred to 125 ml serum bottles which were sealed with Teflon faced septa and aluminum crimp caps. Throughout the research, 25 and 50 ml sample volumes were used but the

samples and the standards to which the samples were compared always had the same volume. For each series of analytical determinations a blank of DI water was treated in the same manner as the samples to check the quality of DI water and adequacy of glassware cleaning.

Equilibration: All samples, standards, and blanks were placed on a gyrorotary shaker platform and agitated for 30 minutes prior to analysis. This was determined to be sufficient time for equilibration by tests that were made at five minute intervals during shaking until a stable value was obtained. Others (18,70) used shorter equilibration times, but 30 minutes provided a convenient and satisfactory equilibration period for this research.

Injection: After equilibration, headspace samples were injected into the GC with gastight syringes (Hamilton 1000 series, 0.25 or 0.5 ml capacity). The usual injection volume was 0.25 - 0.50 ml with the 0.5 ml syringe reserved for low concentrations and the 0.25 ml syringe reserved for high concentrations. TCE concentrations were calculated by comparing the GC response for the sample to that of the standard with the following equation:

TCE concentration =

$$F \times \text{TCE conc. in std.} \times \frac{(\text{mean peak area of sample})}{(\text{mean peak area of std.})} \quad (18)$$

$$\text{Where } F = \frac{\text{injection volume of standard}}{\text{injection volume of sample}}$$

The mean peak area was the mean of peak areas from three injections in which the largest response was less than 10% greater than the smallest response.

Between injections, the needle and plunger were removed from the syringe. The barrel was attached to a vacuum pump and purged for approximately two minutes. Periodically, an aliquot of room air was injected to check syringe cleanliness.

Two or three standards were used for each analysis run as a check on linearity and to ensure that the range of sample concentrations was within those of the test samples being measured. The procedure gave a linear response up to 880 mg/l as shown by Table 13 and the example calibration curves of Figure 2. Consequently, for sample concentrations greater than 800 mg/l, the samples were diluted prior to analysis.

Temperature effects were minimized by keeping all samples and standards in the same location (approximately 18-22°C) during GC injection.

The possible loss of TCE through pierced septa was of concern although Dietz and Singley (18) found such loss insignificant. This investigation found no discernible loss from standards injected at the beginning of a series of analyses compared to injection of the same standards at the end of the same series of analyses. This was true even though, during the three to four hour elapsed time, the

Table 13. GC Linearity Data for Headspace Analysis.

TCE Conc., mg/l	Mean Peak Area, units	r^2	Sample Volume, ml	Injection Volume, ml	Range
0.011	6,309	0.983	50	0.50	10^{-12}
0.055	22,465				
0.110	57,621				
0.220	119,862				
0.440	221,312				
0.660	310,861				
0.880	419,754				
1.100	578,605*				
1.1	456	0.988	50	0.25	10^{-9}
11	4,510				
55	21,695				
110	44,383				
220	86,041				
440	168,781				
660	259,668				
880	336,135				
1100	566,152*				
55	14,698	0.996	25	0.25	10^{-9}
110	29,101				
220	61,965				
440	118,757				
660	179,414				
880	242,412				
1100	392,145*				

Note: Values marked with * not included in regression to determine r^2 .




Figure 2. GC Response for Different Sample Volumes.

septum may have been pierced up to five times. Regardless, to minimize any such loss, each sample was injected as soon after equilibration as possible. Usually, analyses were complete within four hours after sample collection.

The effects of sample matrix and variation of sample volume will be discussed in Preliminary Investigations.

Soil Sample Analysis

This procedure was adopted from an article by DeLeon et al. (16) using the operating conditions reported by the U.S. Environmental Protection Agency (90).

Sample Collection. The glass column and the soil core it contained were placed in a refrigerated room maintained at 4°C. The top stopper was removed from the column and an airline was connected to the glass tube that pierced the bottom stopper in the column. Using a slight air pressure, the soil core was extruded from the column onto a 42-inch section of 3-inch inside diameter PVC pipe cut in half lengthwise. The half section of pipe had been previously lined with aluminum foil. Samples of the soil were taken from several different locations within a particular profile depth. The individual samples were mixed together on an aluminum foil covered base to form a composite sample for that depth.

Extraction. Approximately two grams of the composite soil sample were transferred to a tared 60 ml Hypovial (actual capacity 11 ml; Pierce Chemical Co.) and weighed. Six ml of

n-pentane (reagent grade redistilled in glass) were added to the vial which was then sealed with a Teflon faced septum and aluminum crimp cap. The exact amount of pentane added was determined by weight. The sealed vial was then placed on a vortex mixer for 60 seconds and stored in a freezer at -15°C until analyzed. In no case was the sample held for longer than 10 days prior to analysis.

Dry Weight Determinations. A 20-25 gram portion of each soil sample was placed in a tared aluminum weighing boat and weighed. The sample was then dried in a 103°C oven for 24 hours, cooled in a dessicator, and weighed to determine weight loss due to water content. The percent water content was used to correct the extracted soil samples to a dry weight basis.

GC Operating Conditions. Analysis was conducted with a Varian model 3700 gas chromatograph with a ^{63}Ni foil electron capture detector (ECD) and a CDS 111 data system. Specific GC operating conditions were:

Column Temperature: 65°C

Injector Temperature: 110°C

Detector Temperature: 240°C

Carrier Gas Flow Rate (N_2): 30 ml/min

Column: Glass, 6.0 ft x 1/4 inch outside diameter
x 2.0 mm inside diameter (Supelco No. 2-1721).

Column Packing: 10% Squalene on 80/100 Chromosorb
WAW as supplied by Supelco.

Sample Size: 2-6 microliters.

A D-A147 918


FATE AND DISPOSITION OF TRICHLOROETHYLENE IN SURFACE
SOILS(U) AIR FORCE INST OF TECH WRIGHT-PATTERSON AF OH
T J WALKER11984 AFIT/CI/NR-84-92D


2/4

UNCLASSIFIED

F/G 13/2

NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

Retention Time of TCE on Column: 1.9 minutes

Detector Sensitivity: 10^{-11} or 10^{-12} amp/mV (ECD 10 or 1).

Between injections, the microsyringe was flushed with pentane. Periodically, pure pentane was injected to ascertain syringe cleanliness.

Sample Recovery and Calculation. Based upon absolute standards of TCE in pentane, a series of spiked soil samples was used to test the recovery of the method. For each soil type, a composite soil mixture was made by mixing quantities of dry soil from each profile in proportion to the dry weight of the soil profile. Two grams of the composite sample were placed in a tared Hypovial, weighed, and sealed. The water content of the soil was adjusted to 20% by injecting the appropriate quantity of DI water through the septum, weighing to verify the amount of water, and mixing on a vortex mixer. The soil was spiked by injecting TCE with a microliter syringe. The vial was then reweighed to determine the amount of TCE injected. Pentane was injected into the vial, the vial was reweighed, and the spiked samples analyzed as regular samples. Table 14 lists the recoveries for various concentrations of spiked samples.

Table 14. TCE Recovery from Composite Soil Samples.

<u>Chalmers Composite Soil</u>		<u>Russell Composite Soil</u>	
TCE Conc. (ug/g)	% Recovery	TCE Conc.(ug/g)	% Recovery
190	60.3	233	63.2
254	68.2	309	71.6
580	86.6	726	73.8
807	82.1	806	80.1
929	74.2	1007	69.9
1155	70.3	1170	82.2

Generally, the lower concentrations had lower recoveries. To minimize error introduced by poor recoveries, unknown samples were compared to spiked standards instead of to absolute standards. Concentrations were calculated on a soil dry weight basis by:

$$\begin{aligned} \text{Concentration (ug TCE/g Soil)} &= \frac{\text{Peak area of sample}}{\text{Peak area of std.}} \\ &\times F \times \frac{M_{\text{std}}}{M_{\text{smp}}} \times \text{Conc. Std (ug/g)} \end{aligned} \quad (19)$$

Where $F = \frac{\text{Injection volume of standard}}{\text{Injection volume of sample}}$

$M = \frac{\text{Dry mass of soil used in extraction, g}}{\text{Mass of pentane used in extraction, g}}$

Peak Area = Mean peak area of three injections with the largest no more than 10% greater than the smallest.

Adsorption Isotherms

Soil

Isotherms were developed for coarse and fine particle sizes of soil. To obtain the coarse particle size soil, a

quantity of soil was ground with a mortar and pestle until all of that quantity of soil passed a No. 10 sieve (<2 mm). To obtain the fine particle size soil, a quantity of coarse particle size soil was ground in an electric carbon grinder, then further ground with a mortar and pestle until all of the soil passed a No. 100 sieve (0.150 mm opening). All soil was autoclaved for two hours to minimize any possible biodegradation losses during testing. All soil was dried at 103°C for four hours and cooled in a dessicator prior to weighing the aliquots of 10 g. The basic procedure was based upon methods used in the literature (4,7,32,69,100). The following specific steps were followed with initial TCE concentrations of 110 - 1,100 mg/l:

1. Pour approximately 10 ml of TCE solution into a glass liquid scintillation vial (actual capacity 25 ml) from a full 25 ml graduated cylinder.
2. Immediately, add the preweighed aliquot of 10 grams of soil to the vial.
3. Place a Teflon faced septum on the vial, hold in place by hand, and gently tap and invert the vial several times to release entrained air.
4. Fill the vial with solution and record the total volume of solution used.
5. Immediately replace the septum to eliminate headspace and tightly seal the vial with an open screw cap.

6. Seal all vials in a carton to minimize exposure to light and equilibrate on a shaker table at 20°C for 48 hours.

7. After 48 hours, remove vials and centrifuge at 8,000 rpm for 20 minutes in a refrigerated room (4°C).

8. Withdraw an aliquot of clarified solution through the septum with a syringe and dilute to 25 ml in the syringe.

9. Inject sample into a sealed serum bottle for GC analysis.

During the equilibration period, the vials were inverted on the shaker table six times daily to provide additional mixing. For each different initial TCE concentration, duplicate adsorption vials were used. The results were calculated from the averages of the mass of soil, volume of solution, and final TCE concentration within the two vials. To correct for volatilization losses, duplicate blanks (scintillation vials without soil added) were processed in the same manner except step 2 was eliminated. Results were calculated as follows:

1. Volatilization loss, VL, %

$$VL = \frac{C_i - C_b}{C_i} \times 100\% \quad (20)$$

Where C_i = initial TCE concentration.

C_b = average TCE concentration in blank after equilibration.

2. TCE adsorbed, X

$$X = (C_b - C_f) \times V \quad (21)$$

Where C_f = Final average TCE concentration in adsorption vials after equilibration.

V = Average volume of TCE solution used in adsorption vials.

3. Adsorptive capacity, q.

$$q = X/M \quad (22)$$

Where M = Average mass of soil in adsorption vials.

Glass and Gravel

The adsorptive effects of glass and gravel were studied in separate experiments with initial TCE concentrations of 110-1,100 mg/l. Glass adsorption tests used four mm diameter glass beads which had been acid washed, rinsed, and dried at 260°C for 24 hours. Gravel adsorption tests used 1/4 - 3/8 inch gravel which had been washed to remove silt and dried at 260°C for 24 hours. The procedure was as follows:

1. Pour approximately 50 ml of TCE solution from a full 250 ml graduated cylinder into a 125 ml serum bottle.
2. Immediately, add the preweighed sample of 75 grams of glass or 70 grams of gravel to the bottle.
3. Place a Teflon faced septum on the bottle, hold in place by hand, and gently tap and invert the bottle several times to release entrained air.
4. Fill the bottle with solution and record the total volume of solution used.

5. Immediately replace the septum so as to eliminate headspace, then seal with an aluminum crimp cap.

6. Seal all bottles in a carton to minimize exposure to light and place in a 20°C laboratory area for 72 hours.

7. After 72 hours invert the bottle several times to mix. Withdraw an aliquot of solution of 25 ml or less through the septum with a syringe. For aliquots less than 25 ml, dilute to 25 ml in the syringe with DI water.

8. Inject 25 ml sample into a sealed serum bottle for GC analysis.

During the equilibration period, the bottles were inverted three times daily to provide mixing. For each initial TCE concentration tested, a blank without glass or gravel was processed in the same manner except step 2 was eliminated. X/M values were calculated in the same manner as those for soil adsorption. Adsorptive capacity based on glass surface area was as calculated in Appendix A.

Warburg Respirometry Studies

These studies were conducted to determine the relative rates of aerobic biodegradation of TCE by various soil profiles. The respirometric technique is based on the principle that oxygen consumption in a closed system is indicated by a pressure change which can be measured by micromanometers. This pressure change can then be converted into a volumetric determination of oxygen consumed when the

corresponding carbon dioxide produced is absorbed by a solution of KOH.

The Warburg Respirometer is commonly used to measure oxygen consumption in aerobic liquid cultures. Its use in these studies was adapted from accepted methods for liquid cultures based upon Umbreit et al. (85). The specific procedure was:

1. Add 0.2 ml of 10% KOH solution to the center well of a flask and insert a fluted filter paper wick.
2. Add 2.0 ml of air dried, coarse particle size soil (pass No. 10 sieve). (The 2.0 ml was determined by weight based upon the specific gravity of soil particles for that profile).
3. Attach flask to the proper matched manometer.
4. Equilibrate flask at 25°C for 10 minutes with manometer vents open.
5. Add 1.0 ml of substrate to sidearm of flask and close stopcock.
6. In five minutes, adjust level of manometer fluid in closed end of manometer to 250 mm and read level of fluid in open end. Use this reading as zero time reading.
7. Tip in substrate from sidearm.
8. At appropriate time intervals, read pressure change on manometer by readjusting level in closed end to 250 mm and recording the level in the open end.

The temperature of the water bath was held constant at 25°C during the studies. The change in barometric pressure was accounted for with a blank flask called a thermobarometer. Glucose solution, TCE solution and TCE solution with added ammonia were used as substrates. DI water was used as an endogenous control substrate. All solutions were adjusted to pH 6-7 before use. Each different substrate and concentration of substrate was run in either duplicate or triplicate.

Individual manometer readings were corrected for atmospheric pressure changes then converted to oxygen uptake by the following relationship:

$$\text{O}_2 \text{ uptake, ul} = k \times h \quad (23)$$

Where k = flask constant, ul/mm manometer solution, specifically determined for each flask and corresponding manometer.

h = corrected change in manometer fluid height from previous reading.

The individual oxygen uptake calculations were summed to provide a total cumulative oxygen uptake over the duration of the test. The total cumulative oxygen uptake quantities were then averaged for the duplicate or triplicate measurements. An average exogenous uptake was then calculated by subtracting the average endogenous uptake from the average total cumulative oxygen uptake for each test.

PRELIMINARY INVESTIGATIONS

Prior to initiation of column studies, various techniques, procedures, and methods were investigated to develop a satisfactory experimental protocol for the studies. Included in these investigations were soil analyses, column setup, methods and rates of water application, methods of effluent collection, sample extraction, effects of sampling on GC analysis for TCE, and TCE application to the soil columns.

Soil Analyses

The results of initial soil analyses are presented in Tables 15 and 16. Tables 16 and 17 also contain some soil parameters calculated according to Appendix A.

General observations showed that the bulk density of the soil and the specific gravity of the soil particles increased with depth while the porosity and organic carbon content decreased with depth. This is typical of most soils because the organic matter is generally associated with porous structures which are less dense than discrete particles of silt or clay (2). Additionally, the burden of overlying soil generally compacts the deeper subsurface

Table 15. CEC, Organic Carbon, Particle Size Distribution, and pH of Soils.

Soil Depth, Inches	CEC, meq/100g	% Organic Carbon	Particle Size Dist. %			Textural Class	pH
			Clay	Silt	Sand		
<u>Chalmers Soil</u>							
0-10	26.4	3.03	25.8	57.6	16.6	SiL	6.1
10-15	26.1	1.33	21.6	67.9	10.5	SiL	6.2
15-29	28.4	0.59	30.9	60.9	8.2	SiCL	6.5
29-33	18.1	0.32	35.0	62.4	2.6	SiCL	7.2
<u>Russell Soil</u>							
0-7	12.2	1.22	23.6	67.0	9.4	SiL	6.5
7-11	20.0	0.49	13.2	78.6	8.2	SiL	6.4
11-18	19.5	0.41	22.2	73.5	4.3	SiL	5.4
18-28	16.5	0.36	27.4	72.0	0.6	SiCL	7.0
28-33	18.3	0.23	29.3	67.1	3.6	SiCL	5.0

Table 16. Physical Parameters of Soils.

Soil Depth, inches	Bulk Density, g/cm ³	ρ	n	Calculated Bulk Volume, cm ³	Calculated Pore Volume, cm ³
<u>Chalmers Soil</u>					
0-10	1.31	2.50	0.476	1,158	553
10-15	1.44	2.54	0.434	579	252
15-29	1.46	2.57	0.433	1,620	703
29-33	<u>1.48</u>	2.58	<u>0.425</u>	<u>463</u>	<u>198</u>
Total	1.41		0.446	3,820	1,706
<u>Russell Soil</u>					
0-7	1.37	2.53	0.458	810	371
7-11	1.40	2.55	0.451	463	209
11-18	1.50	2.58	0.418	810	339
18-28	1.54	2.59	0.405	1,158	469
28-33	<u>1.56</u>	2.58	<u>0.396</u>	<u>579</u>	<u>229</u>
Total	1.48		0.423	3,820	1,617

- Notes: 1. ρ = Specific gravity of soil solids (unitless).
 2. n = Calculated porosity (unitless).
 3. Calculations made according to Appendix A.

Table 17. Calculated Soil and Organic Carbon Mass.

Soil Depth, inches	Calculated Soil Mass, g	% of Total Mass	% Organic Carbon	Calculated Organic Carbon Mass, g
<u>Chalmers Soil</u>				
0-10	1,517	28.1	3.03	46.0
10-15	834	15.4	1.33	11.1
15-29	2,365	43.8	0.59	14.0
29-33	<u>685</u>	<u>12.7</u>	<u>0.32</u>	<u>2.2</u>
Total	5,401	100.0	1.4	73.3
<u>Russell Soil</u>				
0-7	1,110	19.6	1.22	13.6
7-11	648	11.5	0.49	3.2
11-18	1,215	21.5	0.41	5.0
18-28	1,783	31.4	0.36	6.4
28-33	<u>903</u>	<u>16.0</u>	<u>0.23</u>	<u>2.1</u>
Total	5,659	100.0	0.53	30.3

- Notes: 1. Calculations made according to Appendix A.
 2. Percent organic carbon measured by Soils Characterization Laboratory.

soils causing the porosity to decrease with depth (7). Compared to the Russell soil, the Chalmers soil showed a higher organic carbon content and slightly lower bulk density for corresponding profile depths. There appeared to be no discernible correlation between neither CEC and organic carbon content nor CEC and clay content for either soil.

Soil Column Setup

The technique used by Wentink (100) and Emig (22) for operation of their soil columns was the basis for the leaching method developed for these investigations. Since Wentink and Emig both studied nonvolatile compounds, their setup was modified for use with TCE as shown in Figure 3. The columns were assembled in the following manner:

1. Place a 38-inch length of glass tubing (Corning No. 234850-7740 Pyrex Standard Wall Tubing; 80mm inside diameter; 85mm outside diameter) in a horizontal V-shaped trough eight feet long.
2. Remove half of the PVC pipe soil core container and strip away all tape and plastic bags. Crop the grass and vegetation closely to the soil surface.
3. Place the soil core container on the trough with the surface end of the core butted snugly against the glass tubing.




Figure 3. Diagram of Soil Column.

4. Gently push the soil core into the tubing while carefully monitoring the integrity of the core (see Figure 4).

5. When 33 inches of soil are in the tubing, trim the core squarely with the end of the tubing, then gently push the core three inches farther into the tubing.

6. Insert a three inch thick spacer (to hold column in place) into the top end of the tubing, turn the column upside down into a vertical position and place two inches of 1/4-3/8 inch gravel in the bottom of the column.

7. Tightly seal the column bottom with a No. 14 rubber stopper prepared for sample collection.

8. Turn the column upright, remove the plug and place column in the support rack. Tightly seal the top with a No. 14 one hole rubber stopper which has been wrapped with aluminum foil and non-reactive Teflon tape to minimize adsorption onto the stopper.

The stopper used to seal the bottom of the column was assembled to provide for sample collection. A No. 14 one hole rubber stopper was wrapped with aluminum foil and non-reactive Teflon® tape. A 5-3/4 inch disposable glass pipette with the fine tip removed by grinding was inserted through the stopper hole as shown in Figure 3.



Figure 4. Extrusion of Soil Core into Column.

Approximately 1/8 inch of the pipette extended into the gravel bed with the stopper in place. With the column in the rack, an 18 gauge, two-inch steel syringe needle was used to cover the tapered end of the pipette. The needle was held in place with a 1/2 inch collar of surgical tubing as detailed in Figure 3.

Preliminary studies conducted with test columns assembled without a gravel bed proved unsatisfactory because the columns drained poorly, the needle frequently clogged, and cloudy effluents with 6.0-10.0 mg/l suspended solids were produced. Since there was concern the solids could interfere with TCE analysis, gravel was added to the column to serve as a porous base to improve drainage as recommended by Hamaker (30). With gravel, test columns produced clear effluents with suspended solids less than 1.0 mg/l.

Column headspace was limited to approximately two inches. This depth was large enough to allow visual inspection of water application but not too large to allow excessive TCE volatilization.

The 33 inch length of soil was chosen based on several factors. This length spanned the upper soil profiles with varied physical and chemical parameters. Below 33 inches, the characteristics of the soil changed only slightly. Additionally, below 33 inches, the soil cores were fragile and easily split or broke, thus disturbing their integrity.

Effluent Collection

Procedure

All water leached through the columns was collected and is hereafter referred to as column effluent. The way in which the effluent was collected depended upon whether or not the TCE concentration was to be determined for that particular sample. For samples in which TCE was not determined, effluent was collected by placing a serum bottle beneath the column as shown in Figure 5. All analyses other than TCE used effluent collected in this way.

Samples for TCE analysis had to be collected in a manner which would eliminate or, at least, minimize TCE loss by volatilization. Schwarzenbach and Westall (77) used an evacuated syringe to collect column effluent for volatile organic analysis. A modification of this approach was tried with some preliminary test columns by attaching a glass syringe to the effluent drain. A sample was withdrawn with the syringe but the vacuum was enough to produce a cloudy effluent. Also, unless the effluent drain were restricted, insufficient sample accumulated in the gravel bed to collect the needed sample volume. Consequently, this method was unsatisfactory.

The method developed for use was similar to that of Schwarzenbach and Westall (77) except an evacuated 125 ml serum bottle was used instead of an evacuated syringe. A serum bottle was sealed with a Teflon faced septum and



Figure 5. Collection of Sample without TCE Analysis.




Figure 6. Collection of Sample with TCE Analysis.

aluminum crimp cap. The bottle was then partially evacuated through a syringe needle which pierced the septum and was connected to a vacuum pump. The approximate vacuum was determined by a gauge in the vacuum line. The necessary vacuum was determined in a series of tests in which serum bottles were evacuated to different absolute pressures. The septa of these bottles were then pierced with a needle attached to a 50 ml syringe barrel filled with water. Based upon the amount of water which was sucked into the bottle, the degree of vacuum was chosen which would collect the desired sample volume. This vacuum was then used to prepare subsequent sample bottles.

After the serum bottle was evacuated, it was attached to the effluent drain line by piercing the septum as shown in Figure 6. Effluent was slowly collected in the bottle as it reached the bottom of the column. Effluent was generally collected overnight.

All serum bottles used for TCE analysis were permanently marked at the 25 and 50 ml levels so sample volumes could be easily identified. If the volume of the sample was greater or less than the volume desired, the sample volume was adjusted in the following manner:

1. If the sample volume was greater than 25 ml and the expected sample concentration was greater than 800 mg/l, the sample was diluted to the 50 ml mark by injecting DI water with a graduated syringe and needle into the bottle through the septum.

2. If the volume collected was greater than 25 ml, but the sample concentration was expected to be less than 800 mg/l, the sample was withdrawn with a syringe and needle until the liquid level reached the 25 ml mark. During sample withdrawal, an empty needle was inserted through the septum and extended to about 0.5 inches below the liquid level in the bottle. This needle allowed an equal volume of air to replace the volume of liquid withdrawn, since the pressure in the headspace was able to stay at a constant level because of the balance between liquid levels and pressures in the bottle. If analysis proved the concentration was greater than 800 mg/l, the sample was diluted to 50 ml as in Step 1.

3. If the volume of sample collected was less than 25 ml and sample concentration was expected to be less than 800 mg/l, the sample was diluted to 25 ml as in Step 1.

4. In all cases, the amount of sample withdrawn or the amount of dilution water added was recorded. In this way the exact amount of the effluent was determined by the volume differential in the sample collection bottle.

Regardless of the manner in which samples were collected, or diluted for analysis, all effluent from the

columns was collected and accounted for except that possibly lost to evaporation. To estimate evaporative loss, 100.0 ml of DI water were poured into an open serum bottle and placed in the 20°C room where the columns were housed (hereafter referred to as the column room). After 24 hours, the water was poured into a graduated cylinder and the volume was measured as 99.6 ml. This slight loss was considered negligible and, consequently, evaporative loss of effluent from unsealed serum bottles was not further considered.

TCE Volatilization Loss During Sample Collection

In Materials and Methods, the possible loss of TCE through pierced septa during analysis was discussed and reported to be an insignificant factor. Another source of anticipated volatilization loss was leakage around the column needle piercing the bottle septum during sample collection. To investigate this loss, a series of standards with TCE concentrations of 110-880 mg/l was analyzed in the following manner:

1. Prepare a set of four identical standards in serum bottles for each concentration. Place two of the bottles from each set in the column room.
2. To simulate the hole used for evacuating the sample bottle, pierce the septa of the remaining two bottles of each set with an empty syringe needle. Then, insert into each of the septa an 18 gauge, 2-inch syringe needle which is fitted with a

glass rod, held in place with a collar of surgical tubing. This simulates the column needle which pierces the septa during sample collection.

3. Place the pierced bottles in the column room and ensure the needles remain upright.

4. After 24 hours, remove needles and analyze all four bottles of each set for TCE as compared to freshly prepared standards.

The results of this test are shown in Table 18. There appears to have been a slight loss of TCE from both the pierced and unpierced septa when considering the entire concentration range tested. However, the maximum loss was 5.3%, with some test concentrations greater than corresponding fresh standards. This indicated there could have been some variation due strictly to experimental error and slight differences in preparing standards. Additionally, the test was run for 24 hours while the sample bottles were to be connected for only 12-16 hours. The levels of volatilization loss were considered negligible and not accounted for in subsequent testing.

Variation in GC Response

Effects of Sample Matrix

The accuracy of TCE analyses was of some concern since the GC response of the effluents was compared with GC response of standards prepared in DI water. To study the

Table 18. Loss of TCE through Pierced Septa.

Standard	Unpierced Septa		Pierced Septa	
TCE Conc., mg/l	TCE Conc., mg/l	% of Std.	TCE Conc., mg/l	% of Std.
110	106	96.4	113	102.7
220	213	97.0	208	94.7
440	452	102.7	443	100.7
660	628	95.2	637	96.5
880	897	101.9	856	97.3
Mean		98.64		98.38
Standard Deviation		3.415		3.251

Sample Volume = 25 ml; Injection Volume = 0.25ml; Range = 10^{-9} .

Table 19. Variation in FID Response Due to Sample Matrix.

Mean Peak Area					
TCE Concentration, mg/l	DI Water	Chalmers Effluent	% of DI Response	Russell Effluent	% of DI Response
110	27,519	26,418	96.0	28,537	103.7
220	61,099	59,938	98.1	61,649	100.9
440	122,461	124,665	101.8	119,644	97.7
660	169,472	164,727	97.2	172,353	101.7
880	254,543	246,652	96.9	253,016	99.4
r ²	0.990	0.983		0.978	
Mean			98.0		100.68
Standard Deviation			2.253		2.276

Sample Volume = 25 ml; Injection Volume = 0.25ml; Range = 10^{-9} .

effects of sample matrix, effluent from several uncontaminated test columns of both soil types was collected. A portion of each type of effluent was saturated with TCE. TCE saturated effluent was then diluted with uncontaminated effluent to provide standard concentrations in the range of 110-880 mg/l. These standards were analyzed and compared to standards made with DI water. Results of the comparison are shown in Table 19.

Dietz and Singley (18) had found that salt concentrations up to 1.0% significantly increased the GC response of TCE concentrations in the few ug/l range. In this study, there were only slight variations in response to sample matrix. The responses of the effluent standards were all within $\pm 4.0\%$ of the corresponding DI standards. This level of variation was considered less than necessary to justify preparation of standards with column effluents. Consequently, all further analyses were conducted and quantified with standards prepared with DI water.

Effects of Sample Volume

Since the liquid volume in the serum bottles was to be determined from permanent side markings, there was some concern that the accuracy of determining the liquid volume could affect the accuracy of the analysis. Determination of the sample volume by the meniscus of the liquid level in the bottle at the marking was accurate to within ± 0.5 ml. To determine the GC response with slight variations in sample

volume, a series of standards from 110-880 mg/l TCE were analyzed with volumes of 24, 25, and 26 ml. The results are shown in Table 20 and Figure 7. As expected, the 24 ml sample volume generally produced a lower GC response than did the corresponding 25 ml sample volume. Conversely, the 26 ml volume generally produced a higher response than the 25 ml volume. In all cases, however, the responses were within $\pm 3.0\%$ of the responses for the 25 ml sample volume. Consequently, the effect of sample volume was considered no further.

Application of Water To Columns

Water was applied to the columns with the same application scheme used by Wentink (100) and Emig (22) which was shown in Figure 3. Deionized water, with the pH adjusted to 5.5-6.0 with 0.1N sulfuric acid when necessary, was placed in a 1,000 ml intravenous (IV) feed bottle to which IV tubing with a screw clamp was attached. The delivery end of the tubing was connected to a two-inch 18 gauge steel syringe needle which was then inserted into the hole in the top stopper of the column. The screw clamp and needle sufficiently restricted flow through the tubing to allow the desired daily application rates. Flowrate was adjusted by tightening or loosening the screw clamp.

Application rates were determined on the basis of the quantity of water which could be applied to the columns on a

Table 20. Variation in FID Response with Sample Volume.

TCE Conc., mg/l	24 ml Volume		25 ml	26 ml Volume	
	MPA	% of 25 ml MPA	MPA	MPA	% of 25 ml MPA
110	24,866	97.6	25,473	25,229	99.1
220	58,962	97.8	60,302	60,994	101.1
440	119,021	97.1	122,563	123,947	101.2
660	169,974	97.3	174,690	178,941	102.4
880	249,334	99.2	251,345	255,367	101.6
r^2	0.981		0.982	0.978	
Mean		97.8			101.1
Standard Deviation		0.851			1.22

Note: 1. MPA = Mean Peak Area




Figure 7. Variation in FID Response with Different Sample Volumes.

daily basis and not cause ponding on the top of the columns. Ponding was undesirable because it could clog surface pores, cause anaerobic conditions within the soil columns, and upset the leaching conditions desired in the study. To determine the maximum application rates, a set of test columns of each soil were leached with DI water at rates of 50-200 ml/day. From these tests, it was found that water applied at 125 ml/day or more caused ponding. Consequently, the maximum daily water application rate was chosen as 100 ml/day with a secondary rate of 50 ml/day. In terms of rainfall, these application rates for a three-inch diameter soil core were:

$$50 \text{ ml/day} = 1.10 \text{ cm/day} = 0.43 \text{ inches/day}$$

$$100 \text{ ml/day} = 2.20 \text{ cm/day} = 0.86 \text{ inches/day}$$

Flowrate was adjusted daily, based upon amount of effluent collected.

Application of TCE to Soil

Since the purpose of this study was to investigate the movement of TCE through soil as a result of a spill, it was necessary to make a reasonable estimate of the quantity of TCE to apply to soil columns. As a basis for this estimate, the K_p for TCE was calculated from Equation 8:

$$\begin{aligned} K_p &= (0.63)(195)(f_{OC}) \\ &= 123 \times f_{OC} \text{ (on a gram/gram basis)} \end{aligned}$$

Assuming a linear adsorption isotherm of Equation 4,

$$X/M = (123) (f_{OC})(C)$$

When X/M is expressed in mg/g and C is in mg/l, K_p becomes:

$$\begin{aligned} K_p &= (123 \text{ g/g})(f_{OC})(1 \text{ liter}/1000\text{g}) \\ &= (0.123 \text{ l/g})f_{OC} \end{aligned}$$

Then,

$$X/M = 0.123 \times f_{OC} \times C \quad (22)$$

This equation was used to calculate the values shown in Table 21. Since at this point in the research the organic carbon content of the soils had not yet been determined, f_{OC} was estimated based upon similar soils. It was also assumed that water leaching through the columns would reach a concentration of 1,100 mg/l, the maximum solubility of TCE. Based upon these calculations, the maximum amount of TCE that would be adsorbed on the columns was 7.31 g (5.0 ml) on Chalmers soil and 3.83 g (2.62 ml) on Russell soil.

Table 21. Calculated TCE Adsorption.

Parameter	Chalmers Soil	Russell Soil
Estimated f_{OC}	0.01	0.005
Total Soil Mass, M	5,401 g	5,659 g
X/M , mg/g at $C = 1,100 \text{ mg/l}$	1.353	0.677
TCE Adsorbed, X	7.31 g	3.83 g
TCE Adsorbed, X	5.01 ml	2.52 ml

These calculated values were gross estimates since the valid range for Equations 4 and 8 were greatly exceeded.

Additionally, it was recognized that portions of the TCE applied to the columns might be lost due to degradation and volatilization, thus increasing the amount which could be applied without exceeding the adsorptive capacity of the soil. However, since the TCE was to be applied directly to the soil instead of in solution, the adsorptive capacity of the soil was expected to be higher than that calculated in Table 21. Considering these factors, the TCE loadings chosen for study were 5.0 ml and 10.0 ml on each soil column. Comparative loadings are indicated below:

5 ml/col = 7.3g/col = 0.054 gal/ft^2 = 0.043 inches/column

10 ml/col = 14.6g/col = 0.108 gal/ft^2 = 0.086 inches/column

For ease of analysis, and to eliminate interference due to impurities, reagent grade TCE, which had been redistilled in glass, was used to dose the columns.

Initiation of Column Studies

Thirteen soil columns of each soil type were assembled, placed in support racks, and plumbed to ensure the columns were vertical. The columns were located in a 20°C temperature controlled room (column room) as shown in Figure 8. All columns were saturated with DI water then allowed to drain until no further drainage occurred (all columns ceased draining after 48 hours). To apply TCE, the top stopper of the column was removed and 5.0 or 10.0 ml of TCE (according to Table 22) were applied to the surface of the soil core with a volumetric pipette. The stopper was immediately




Figure 8. Column Study Assembly.

replaced to tightly seal the column. To maximize adsorption of the TCE, no water was applied for 24 hours. After 24 hours, water was applied according to the schedule of Table 22. The day water application began was logged as Day 0, with the first attempt to collect effluent listed as Day 1, according to Appendix B.

One soil column of each soil type was not dosed with TCE but was leached with water as a control column. All conditions were run with triplicate columns so that any fluctuations due to a particular column could be compensated for by the response of other similar columns.

For convenience of discussion and as a basis for comparison, the typical laboratory day during the column studies was conducted according to the following approximate time schedule, beginning with Day 1:

1. 6-7:30 A.M.: Removed sample bottles from columns scheduled for TCE analysis and replaced evacuated bottles with open serum bottles to collect any additional effluent during the day. Prepared samples for analysis and recorded sample volumes as well as all effluent volumes collected. To be consistent, all effluent collected during the previous 24 hours (including sample) was recorded as of the morning the volume was determined. Any additional effluent or sample collected later during the day was recorded for the following day.

Table 22. Operating Conditions for Column Soil Studies.

Column Number	TCE Applied, ml	Water Application Rate, ml/day
<u>Chalmers Soil</u>		
C1	5.0	50
C2	5.0	50
C3	5.0	50
C4	5.0	100
C5	5.0	100
C6	5.0	100
C7	10.0	50
C8	10.0	50
C9	10.0	50
C10	10.0	100
C11	10.0	100
C12	10.0	100
CC (Control)	0.0	100
<u>Russell Soil</u>		
R1	5.0	50
R2	5.0	50
R3	5.0	100
R4	5.0	100
R5	5.0	100
R6	5.0	50
R7	10.0	50
R8	10.0	50
R9	10.0	100
R10	10.0	100
R11	10.0	100
R12	10.0	100
RC (Control)	0.0	

2. 7:30 A.M.-4:00 P.M.: Conducted necessary analyses.

3. 4:00-7:00 P.M.: Prepared and attached sample bottles to columns. Added DI water to IV bottles and adjusted flow rates as needed.

The times indicated were the approximate times during which the tasks were begun and do not indicate the time necessary for completion of a particular task.

RESULTS AND DISCUSSION

The column studies discussed in Preliminary Investigations were operated continuously for 132 consecutive days. During this same time span, additional studies and tests were also conducted as part of the overall research program. These concurrent studies included determination of adsorption isotherms; elution of TCE from soil columns; effect of nutrient addition to the soil columns on the fate of TCE; TCE degradation studies; and analysis of the soil from the test columns to determine the amount of TCE that remained at the end of the column studies. To achieve an overall accounting for the TCE applied to each column, all results from the various means by which TCE was retained or eluted from the soil columns were pooled in a mass balance.

Batch Adsorption Studies

Soil Adsorption Isotherms

Equilibrium adsorption isotherms were determined for composite mixtures of each of the Chalmers and Russell soils. For each soil, the effect of particle size on adsorption was studied with soil mixtures of coarse particle size and fine particle size as discussed in Materials and

Methods. Experimental results used to determine the isotherms are listed in Table 23 and Table C1 of Appendix C. All adsorption isotherms were best described by the Freundlich theory as shown by Equation 3. The values of the Freundlich equation constants K_F and $1/n$ were determined from a least squares fit of the data in Table 23. The Freundlich constants are summarized in Table 24 based upon an equilibrium TCE concentration in mg/l and X/M expressed as ug of TCE adsorbed/g of soil.

Several observations can be drawn from the data of Table 24. Since $1/n$ values were not equal to unity, adsorption could not be considered linear over the range of TCE concentrations used to determine the isotherms. However, the $1/n$ values were close to unity and evaluation of the data portrayed in Figures 9 and 10 indicated a slight increase in adsorption at higher TCE equilibrium concentrations. There appeared to be no observable difference between the $1/n$ values for coarse particle soil and fine particle soil. Rather, the differences in $1/n$ values for the different particle sizes of a particular soil were probably due to experimental error inherent in the analysis procedure and the method used to generate the isotherms. It did appear, however, that both particle sizes of Chalmers soil had $1/n$ values slightly greater than the corresponding $1/n$ values for each of the particle sizes of Russell soils. The difference, however, was not great and no significance should be attached to this difference.

Table 23. Summary of Experimental Values Used to Determine Soil Adsorption Isotherms for TCE.

C_i , mg/l	C_b , mg/l	% Loss	* C_e , mg/l	+X/M, ug/l
<u>Chalmers Soil, coarse particle size</u>				
110	85	22.7	64	42
220	167	24.0	130	73
440	354	19.5	273	164
660	493	25.3	349	294
880	717	18.5	564	307
1100	968	12.0	772	399
<u>Chalmers Soil, fine particle size</u>				
220	205	6.8	130	153
440	364	17.3	250	232
660	631	4.9	424	428
880	747	15.1	503	491
1100	987	10.3	627	727
<u>Russell Soil, coarse particle size</u>				
110	90	18.2	74	33
220	175	20.5	159	32
440	371	15.7	331	81
660	491	25.6	429	125
880	720	18.2	631	182
1100	896	18.5	772	242
<u>Russell Soil, fine particle size</u>				
110	91	17.3	68	47
220	172	21.8	142	61
440	370	15.9	302	139
660	516	21.8	426	178
880	756	14.1	628	261
1100	920	16.4	701	442

* Average of two values.

+ Calculated from average values.

Table 24. Freundlich Constants Determined from Equilibrium Adsorption Isotherms for TCE Applied to Soils.

Parameter	Chalmers Soil		Russell Soil	
	Coarse	Fine	Coarse	Fine
^+K_F	0.813	1.250	0.443	0.826
$^+1/n$	0.949	0.972	0.926	0.910
r^2	0.941	0.962	0.901	0.922
% organic carbon	1.4	1.4	0.53	0.53
$^*K_{OCF}$	58.1	89.3	83.6	155.8

* Calculated from Eq. 6

+ Based upon TCE equilibrium concentration in mg/l and X/M in ug/g

Table 25. Calculated X/M Values for Various TCE Concentrations.

Soil Type	X/M (ug/g) or X(g)	TCE Equilibrium Conc., mg/l			
		100*	500*	1100*	1100**
Chalmers (coarse)	X/M	64	296	626	1,894
	X	0.346	1.599	3.381	10.229
Chalmers (fine)	X/M	110	525	1,130	1,894
	X	0.594	2.836	6.103	10.229
Russell (coarse)	X/M	32	140	290	717
	X	0.181	0.792	1.641	4.05
Russell (fine)	X/M	55	236	484	717
	X	0.311	1.336	2.739	4.05

* Calculated from Freundlich isotherm constants.

** Calculated from Karickhoff's relationship, Eq. 8




Figure 9. TCE Adsorption Isotherm for Composite Mixture of Chalmers Soil.




Figure 10. TCE Adsorption Isotherm for Composite Mixture of Russell Soil.

The values determined for K_F differed depending upon soil type and particle size. As shown in Table 24, for both particle sizes, the Chalmers soil exhibited higher K_F values than the Russell soil which had the lower organic carbon content of the two soils. Additionally, for both soils, the K_F determined on fine particle soil was greater than that determined for coarse particle soil. While the increase in K_F from coarse to fine particle size for Chalmers soil was only 52.6%, the increase for Russell soil was 86.5%. This increase in K_F , with decrease in particle size, would seem to indicate that adsorption capacity depended upon surface area. Since both soils were composited, ground, and sieved in the same manner, it was unlikely that the different values for K_F were due solely to difference in handling. Considering that Karickhoff (38) found that most organic carbon in soil is associated with the fine particles (<50 microns), grinding of the coarse particles into the smaller particles probably exposed very little additional organic surface area sites for adsorption. However, the same grinding could have exposed additional inorganic surface area adsorption sites thereby increasing K_F . The numerical increases in K_F from coarse to fine particle size soil isotherms (0.437 for Chalmers and 0.383 for Russell) are comparable. Consequently, if all the organic carbon was in the fines fraction it would have passed through the No. 100 sieve even without grinding. Therefore, the grinding would

seem to have increased the inorganic surface area approximately equally for each soil.

A further indication of adsorption onto inorganic surface areas was shown by the K_{OC} 's calculated for the soils. If it is assumed that only organic carbon controls adsorption, the K_{OC} 's for each of the soils should have been reasonably similar. As shown in Table 24, however, the K_{OCF} 's differed. For the coarse particle sizes, the Russell K_{OCF} was 53.7% greater than that for Chalmers soil, while for the fine particle size, the Russell K_{OCF} was 86.4% greater. This comparison is important for it indicated that in this study organic carbon content alone did not solely control the adsorptive capacity of the soils tested.

Calculated values of adsorptive capacity based upon the Freundlich isotherms are shown in Table 25. As a comparison, X/M values calculated according to Karickhoff's relationship (38) of Equation 8 are also listed. It should be noted that the values calculated with a TCE concentration of 1,100 mg/l (maximum solubility of TCE) were extrapolated values since none of the isotherm tests used a TCE equilibrium concentration greater than 772 mg/l (Table 23).

Generally, Karickhoff's relationship (38) estimated X/M values 1.5 times higher than those predicted by the isotherms for the fine particle soil and 2.5-3.0 times higher than X/M values predicted by isotherms from coarse particle soil. While the difference was large, it must be

remembered that Karickhoff (38) expected his equation to have an accuracy only within a factor of two. Additionally, Equation 8 is a linear adsorption relationship based solely on organic carbon content with no consideration for inorganic surface adsorption and particle size effects. The isotherms determined in this study did account for particle size effects. As shown by the results of Table 24 and Figures 9 and 10, the particle size of the soil used to determine the isotherm had a measurable effect on the K_p values.

Adsorption Equilibrium Study

As discussed in the Literature Review, various equilibrium times have been used for batch determination of soil adsorption isotherms. The equilibrium times used in this study were based upon the 18-hour times used by Richter (70) but lengthened to 48 hours. This increase was used because of the approximately 1,000 fold increase in initial TCE concentrations used.

After determination of the adsorption isotherms, it was desired to determine if equilibrium had, in fact, been reached during the 48 hour contact period. Consequently, a simple experiment was conducted to determine the time necessary for adsorption to reach equilibrium for both particle sizes of each soil type. A number of vials with soil were prepared for isotherm studies (as discussed in Materials and Methods) at TCE concentrations of 220 and 880

mg/l. These concentrations were chosen to represent the low and high TCE levels used in the isotherm determinations. An equal number of blanks were prepared that corresponded to the number of soil adsorption vials. All vials were incubated on an operating shaker table at 20°C. Approximately ten times per day all vials were inverted to maximize mixing. At intervals during the 48 hours, one adsorption vial and one corresponding blank were removed and analyzed for TCE solution concentration as discussed in Materials and Methods. The results of this experiment are shown in Tables 26 and 27 with liquid volumes and soil masses used shown in Table C2 of Appendix C.

The degree of attainment of equilibrium was based on the ratio of X/M determined from the time of adsorption experiment to X/M calculated from the appropriate adsorption isotherm for the C_e value determined for the particular time of adsorption. With this procedure, if the ratio was less than 1.0, then maximum adsorption had not been achieved up to that particular time. An assumption made in using this approach was that equilibrium would, in fact, be attained during the 48-hour contact period. This assumption proved correct as shown by the X/M ratios listed in Tables 26 and 27 and graphically illustrated in Figures 11, 12, 13, and 14.

In all cases, equilibrium appeared to have been reached after 20 hours of agitating and mixing the adsorbent (soil) and adsorbate (TCE in solution). More specifically, the

Table 26. Data from Time of Adsorption Experiment for Chalmers Soil Subjected to TCE Application.

Time, hours	C _b , mg/l	% Loss	C _e , mg/l	* (X/M) _t , ug/g	+ (X/M) _i , ug/g	X/M ratio (X/M) _t /(X/M) _i
Coarse particle size, C _i = 220 mg/l.						
2	184	16.4	175	18	109	0.17
4	173	21.4	165	16	103	0.15
6	186	15.5	163	47	102	0.46
9	169	23.2	138	62	87	0.71
13	174	20.9	136	76	86	0.88
23	172	21.8	132	79	84	0.94
33	183	16.8	127	73	80	0.91
48	173	21.4	130	81	82	0.99
Coarse particle size, C _i = 880 mg/l.						
2	744	15.4	722	46	419	0.11
4	749	14.9	721	57	419	0.14
6	737	16.2	656	162	383	0.42
9	721	18.1	610	225	357	0.63
13	703	20.1	560	293	330	0.89
23	729	17.2	573	314	337	0.93
33	758	13.9	591	338	347	0.97
48	697	20.8	541	324	319	1.02

Table 26. Continued.

Time, hours	C _b , mg/l	% Loss	C _e , mg/l	* (X/M) _t , ug/g	+(X/M) _i , ug/g	X/M ratio (X/M) _t /(X/M) _i
Fine particle size, C _i = 220 mg/l.						
2	192	12.7	168	49	182	0.27
4	199	9.5	152	95	165	0.58
6	191	13.2	141	99	153	0.65
9.5	188	14.5	127	128	139	0.92
13	183	16.8	121	125	132	0.95
16	189	14.1	124	132	135	0.98
24	185	15.9	118	137	129	1.06
36	187	15.0	123	134	134	0.98
48	174	20.9	116	121	127	0.95
Fine particle size, C _i = 880 mg/l.						
2	769	12.6	691	157	719	0.22
4	757	14.0	608	303	635	0.48
6	748	15.0	573	364	600	0.61
9.5	787	10.6	542	493	568	0.87
13	753	14.4	501	515	526	0.98
16	755	14.2	489	529	514	1.03
24	764	13.2	496	545	521	1.05
36	756	14.1	479	548	504	1.09
48	763	13.3	507	517	532	0.97

* (X/M)_t = X/M value determined from time of adsorption experiment.

+(X/M)_i = X/M value calculated from isotherm for C_e value listed.

Table 27. Data from Time of Adsorption Experiment for Russell Soil Subjected to TCE Application.

Time, hours	C _b , mg/l	% Loss	C _e , mg/l	* (X/M) _t , ug/g	+ (X/M) _i , ug/g	X/M ratio (X/M) _t /(X/M) _i
Coarse particle size, C _i = 220 mg/l.						
2	181	17.7	177	8	53	0.15
4	173	21.3	166	14	50	0.28
6	174	20.9	162	24	49	0.49
9	177	19.5	166	22	50	0.44
14	169	23.2	152	36	46	0.78
18	182	17.3	154	56	47	1.19
24	173	21.3	149	48	46	1.05
38	170	22.7	147	46	45	1.02
48	176	20.0	150	51	46	1.11
Coarse particle size, C _i = 880 mg/l.						
2	742	15.7	727	30	198	0.15
4	736	16.3	718	36	196	0.18
6	744	15.4	700	88	191	0.46
9	730	17.0	668	124	183	0.68
14	723	17.8	638	175	175	1.00
18	737	16.3	643	186	176	1.05
24	707	19.6	618	179	170	1.05
38	714	18.9	622	184	171	1.07
48	726	17.5	630	190	173	1.10

Table 27. Continued.

Time, hours	C _b , mg/l	% Loss	C _e , mg/l	* (X/M) _t , ug/g	+ (X/M) _i , ug/g	X/M ratio (X/M) _t /(X/M) _i
Fine particle size, C _i = 220 mg/l.						
2	178	19.1	170	16	88	0.18
4	174	20.9	161	26	84	0.31
6	176	20.0	152	48	80	0.60
10	172	21.8	140	66	74	0.89
15	180	18.2	144	72	76	0.95
24	176	20.0	139	74	74	1.00
33	170	22.7	134	73	71	1.03
37	169	23.2	135	69	72	0.96
48	179	18.6	141	79	75	1.05
Fine particle size, C _i = 880 mg/l.						
2	758	13.9	723	70	330	0.21
4	740	15.9	702	78	321	0.24
6	800	9.1	693	219	318	0.69
10	761	13.5	644	232	297	0.78
15	757	14.0	626	273	290	0.94
24	780	11.4	638	289	295	0.98
33	766	13.0	619	293	287	1.02
37	741	15.8	608	269	282	0.95
48	782	11.1	636	290	294	0.99

* (X/M)_t = X/M value determined from time of adsorption experiment.
 + (X/M)_i = X/M value calculated from isotherm for C_e value listed.




Figure 11. Adsorption Equilibration for Coarse Particle Soil with TCE Concentration of 220 mg/l.




Figure 12. Adsorption Equilibration for Coarse Particle Soil with TCE Concentration of 880 mg/l.




Figure 13. Adsorption Equilibration for Fine Particle Soil with TCE Concentration of 220 mg/l.




Figure 14. Adsorption Equilibration for Fine Particle Soil with TCE Concentration of 880 mg/l.

fine particle soil reached equilibrium by 15 hours. This slightly faster approach to equilibrium by fine particle soil was not unexpected since the smaller particle size can allow more rapid diffusion into the pores of the adsorbent (98). As shown in Figures 11-14, there appeared to be little difference between the Chalmers and Russell soils in the attainment of equilibrium for both particle sizes and TCE concentrations studied. Except for the combination of coarse particle size and 880 mg/l TCE concentration, the Chalmers soil appeared to approach equilibrium more rapidly. For the combination of coarse particle size and 880 mg/l TCE concentration, the Russell soil appeared to approach equilibrium more rapidly.

This experiment indicated that maximum adsorption by the soils occurred by at least 20 hours. Consequently, the 48-hour contact period was sufficient to allow the adsorbents and adsorbates to reach equilibrium, therefore establishing the validity of the isotherms.

Adsorption by Glass and Gravel

Within the soil columns, the glass surface of the tubing and the gravel at the bottom of the column were also possible adsorbents for TCE during the studies. To assess the adsorptive capacity of glass and gravel, separate adsorptive studies were conducted according to procedures described in Materials and Methods. The results of these studies are shown in Tables 28 and 29 with liquid volumes

Table 28. Summary of Data from Glass Adsorption Study with TCE.

C_i , mg/l	C_b , mg/l	% Loss	C_e , mg/l	X/M, ug/g	*X/A, ug/cm ²
220	196	10.9	191	8.0	1.20
440	401	8.9	398	5.0	0.73
660	572	13.3	580	-13.2	-1.91
880	743	15.6	756	-21.4	-3.12
1100	894	18.7	893	1.6	0.24

* X/A = ug TCE adsorbed/cm² of glass surface area
(Calculated in Appendix C)

Table 29. Summary of Data from Gravel Adsorption Study with TCE.

C_i , mg/l	C_b , mg/l	% Loss	C_e , mg/l	X/M, ug/g
110	89	19.1	88	2
220	187	15.0	193	-12
440	372	15.5	369	5
550	479	12.9	481	-4
660	593	10.2	586	12
880	774	12.0	772	3
1100	939	14.6	935	7

and adsorbent masses used in the experiments listed in Tables C3 and C4 of Appendix C.

For both gravel and glass, adsorption appeared to be minimal, erratic, and not to fit any standard isotherm relationship. In fact, several "negative" X/M values were obtained, presumably due to a higher volatile loss from the blanks than adsorption plus volatile loss from adsorption bottles. Because of the randomness of the data, no plots to establish isotherms were made. It was apparent, though, that the glass and gravel provided negligible adsorption compared to soil.

The gravel surfaces, for all practical purposes, could be considered inorganic. Additionally, the surface area per unit weight of the 1/4"-3/8" gravel was exceedingly small, on weight basis, compared to that of the soil particles. The largest X/M value found in Table 29 was 12 ug/g. When this value was used to determine the adsorptive capacity of 369 g of gravel (the average amount of gravel in the 2-inch deep column well), it indicated only 4.428 mg of TCE could have been adsorbed by the gravel. For this reason, TCE adsorption by the gravel was neglected at the TCE concentrations exhibited during the course of this study.

Similarly, the glass surfaces of the column were also inorganic with 2,234 cm² of glass area exposed to TCE solution on the interior of the glass tubing. Since, from Table 28, the largest X/A (ug TCE adsorbed/cm² of glass

surface area) was 1.20, the maximum amount of TCE adsorbed by the glass could have been 2.6 mg. Because this calculated amount was small, TCE adsorption by glass was neglected.

Other small amounts of the TCE could have possibly been adsorbed by the effluent needle, collector tube, and rubber collar shown in Figure 3. While not quantitatively determined during the study, TCE adsorption by these items was neglected due to their exceedingly small surface contact area and based upon results of the gravel and glass adsorption tests. Consequently, adsorption by materials other than the soil of the column was considered negligible and was not accounted for during the course of the column studies.

Volatilization Losses

One problem associated with working with volatile compounds such as TCE is their disappearance from solution via volatilization. Richter (70) and Rogers et al. (75) reported volatilization losses in their studies but did not analytically quantify the losses. As indicated by Tables 23, 26, 27 and 28, all blank adsorption vials used for the various experiments of this study showed loss of TCE. There appeared to be no particular pattern to the percentage of TCE lost from the adsorption blanks based upon initial TCE concentration, soil type, or particle size. Additionally, there appeared to be no major difference in percentage lost

between the 25 ml soil adsorption vials (which used screw caps and septa) and the 125 ml serum bottles (which used crimp caps and septa) used for glass and gravel adsorption.

The time of adsorption study (Tables 26 and 27) did not generally indicate an increased volatilization loss with increased time of equilibrium. Rather, the loss appeared to be randomly distributed throughout the sampling periods, and largely, within a range of 10-20% of the amount of TCE present. These facts seemed to indicate that loss of TCE while determining adsorption isotherms occurred during sample preparation and retrieval rather than during sample equilibrium. Since the adsorption blanks were treated exactly as adsorption vials, differences in volatilization losses due to handling were minimized. Additionally, since the soils used in these batch adsorption studies were sterilized, the loss of TCE from solution in the adsorption vials was solely due to volatilization and adsorption and not biological degradation. Since volatilization was accounted for with the blanks, adsorption was determined in a valid manner.

Column Elution Studies

General

The column elution studies comprised the bulk of the research effort of this investigation. Twenty-four hours after the TCE was applied to the soil columns, water was

applied for 132 consecutive days at the rates shown in Table 22. The purpose in applying the water was to determine the amount and pattern of TCE that could be eluted from the soil. The elution patterns were determined for the effluent TCE concentrations which were measured on each column effluent two to four times per week. Prior to discussion of effluent TCE concentrations, however, it is necessary to enumerate several methodology problems that arose early in the studies.

Daily effluent volumes collected were quite erratic during the early days of the investigation as shown by the daily data listed in Tables B2-B11 of Appendix B. A summary of the data for each column is listed in Tables 30 and 31. The initial erratic effluent volumes were caused by two factors. Occasionally, various effluent needles became obstructed or clogged from bits of septum which were gouged from the sample collection bottles. This was only a minor problem which was corrected by Day 20, but it prompted a routine check of each needle for bits of septum to prevent further problems.

The major cause of erratic water application rates was the problems associated with the IV tubing and screw clamps used to control the water flow from the IV reservoir to the delivery needle at the top of the column. As described in Preliminary Investigations, the IV bottle was to be filled with DI water which would slowly drip onto the column at the

Table 30. Mean, Standard Deviation, and Range of Daily Volume of Effluent Collected from Chalmers Soil Columns.

Column	Daily Volume of Effluent Collected , ml					
	Mean	SD	Range	Mean	SD	Range
	<u>Day 0 - Day 70</u>			<u>Day 0 - Day 132</u>		
						<u>Day 71 - Day 132</u>
C1	52.9	12.64	0-79	51.4	9.55	0-79 49.7 3.09 45-46
C2	53.8	17.03	0-123	52.1	12.66	0-123 50.2 3.01 41-55
C3	52.9	13.82	0-181	51.7	10.27	0-81 50.3 2.63 42-55
C7 ¹	55.2	14.83	0-85	53.1	11.61	0-85 50.1 2.16 46-54
C8	52.7	16.06	0-89	51.7	11.83	0-89 50.6 2.53 46-56
C9	52.3	15.01	0-89	51.2	1.07	0-89 50.0 2.38 45-55

Table 30. Continued.

Column	Daily Volume of Effluent Collected, ml									
	Day 0 - Day 55		Day 0 - Day 132		Day 56 - Day 132					
	Mean	SD	Range	Mean	SD	Range	Mean	SD	Range	
C4	97.7	24.50	0-147	98.3	16.19	0-147	99.0	4.29		81-106
C5	95.8	23.09	0-142	97.7	15.26	0-142	99.1	4.26		87-107
C6	97.3	29.04	0-175	98.9	18.87	0-175	100.1	3.36		93-109
C10 ²	99.7	27.08	0-136	-	-	-	-	-		-
C11	93.9	24.74	0-138	97.0	16.34	0-138	99.3	3.63		92-107
C12	99.0	25.75	0-139	98.8	16.91	0-139	99.7	4.70		81-108
Control	103.5	24.79	0-144	101.2	16.52	0-144	99.5	5.19		80-112

Note: 1. C7 removed on Day 121
 2. C10 removed on Day 44

Table 31. Mean, Standard Deviation, and Range of Daily Volume of Effluent Collected from Russell Soil Columns.

Column	Daily Volume of Effluent Collected , ml					
	Mean	SD	Range	Mean	SD	Range
	<u>Day 0 - Day 70</u>		<u>Day 0 - Day 132</u>		<u>Day 71 - Day 132</u>	
R1	54.3	15.74	0-101	52.3	11.73	0-101 50.1 2.41 45-53
R2	55.5	14.25	0-84	52.7	10.89	0-84 49.5 2.19 45-54
R3	54.8	15.52	0-75	53.6	13.71	0-75 50.0 3.07 39-61
R7 ¹	51.6	22.10	0-90	-	-	- -
R8	53.0	13.71	0-91	51.6	10.20	0-91 50.0 2.52 44-54
R9	54.9	15.73	0-87	52.7	11.76	0-87 50.2 2.19 46-54

Table 31. Continued.

Column	Daily Volume of Effluent Collected , ml									
	Mean	SD	Range	Mean	SD	Range	Mean	SD	Range	
	<u>Day 0 - Day 55</u>			<u>Day 0 - Day 132</u>			<u>Day 56 - Day 132</u>			
R4	99.2	22.99	0-143	99.5	15.01	0-143	99.7	3.53	94-106	
R5	94.7	23.66	0-139	97.6	15.66	0-139	99.8	3.82	93-109	
R6	91.1	20.07	0-130	96.1	13.95	0-130	99.6	4.28	92-117	
R10	99.4	24.65	0-137	99.9	16.14	0-137	100.2	4.15	88-106	
R11	98.1	22.12	0-142	98.8	14.48	0-142	99.3	3.61	88-109	
R12 ²	96.9	24.33	0-132	-	-	-	-	-	-	
Control	103.5	24.79	0-144	101.2	16.52	0-144	99.5	5.19	80-112	

Note: 1. R7 removed on Day 44.
 2. R12 removed on Day 45.

prescribed rate until the IV bottle needed to be refilled. During column setup in preliminary experiments, all delivery systems were calibrated for the proper rates. Once the studies began, daily adjustments in flow rates were made. Eventually, these adjustments began to restrict the tubing and to produce permanent crimps which severely restricted the flow. Efforts to relieve the crimps and errors in adjusting the screw clamps allowed some excessive water applications. Consequently, to reduce the excessive amount of time spent adjusting the tubing, a different application method was instituted on Day 40.

The new method, similar to that used by Emig (22) and Wentink (100), consisted of placing the daily volume of DI water into the appropriate IV bottles on a daily basis. This volume was then allowed to drip onto the columns at a controlled rate. In most cases, the volume of water was applied to the column over a 10-12 hour period.

This method vastly improved the delivery rate as evidenced by the data on effluent volumes in Tables 30 and 31. These tables show the mean, standard deviation, and range for effluent volumes for the initial stage, latter stage, and complete duration of the study. The division between the initial stage and latter stage was determined from a residence time estimated from the application rate and the calculated pore volume of the columns. The calculated pore volume of the Chalmers column was 1,706 ml

while that for the Russell column was 1,617 ml. Thus, for 50 ml/day application rate, the calculated residence time for the Chalmers column was 34.1 days and 32.3 days for the Russell column. Since, as discussed in Literature Review, the actual residence time would be less than that calculated, 30 days was used as an estimate of residence time for both soil columns for 50 ml/day. Similarly, for 100 ml/day, 15 days was used as an estimate for residence time for both soil columns. The initial stage listed in Tables 30 and 31 encompasses the time period up to the change in application method (Day 40) plus one residence time (15 or 30 days).

As shown in Tables 30 and 31, control of the flow rate improved over the latter stage of the study as compared to the initial stage. Evidence to this are mean values of flow rates that are closer to the desired flow rates, smaller standard deviations, and smaller ranges of flow rates. While overall in the initial stage the mean values of effluent volumes were close to the desired rate, there were wide fluctuations as shown by the wide range and high standard deviations. Some flow variations did exist in the latter stage, however, most of this was accounted for by the one to four hour variation in time on a daily basis in which samples were collected or delivery bottles replenished.

It was initially planned to periodically sacrifice or take apart selected columns during the study to determine

the location and magnitude of TCE movement through the soil. However, the glass tubing of columns C10 and R12 were found broken on Days 44 and 45, respectively. Since the breaks were located at the bottom of the column, it was speculated that the weight of the soil column caused the bottom stopper to act like a wedge and to fracture the glass. Regardless of the cause, the idea of periodically sacrificing columns was discarded to prevent unnecessary reduction in the triplicate columns in each column grouping.

TCE Elution

To graphically illustrate the TCE elution patterns for the different soils, water application rates, and TCE mass loadings, the TCE concentrations listed in the daily data of Appendix B were plotted for each specific test column loading and operating condition. These plots, using effluent volume as the common basis of comparison, are shown in Figures 15-22. In the figures, a composite elution curve was drawn through all data points for the specific column tests. This approach was used because on a day to day basis the cumulative effluent volumes differed and never matched well enough to allow for calculation of a mean value.

As anticipated, the use of triplicate columns allowed the fluctuation of any particular column to be compensated for by the response of similar columns. This was evident in all of the composite elution curves of Figures 15-22. For




Figure 15. Composite TCE Elution Curve: Chalmers Soil Columns C1, C2, and C3.




Figure 16. Composite TCE Elution Curve: Chalmers Soil Columns C4, C5, and C6.




Figure 17. Composite TCE Elution Curve: Chalmers Soil Columns C7, C8, and C9.




Figure 18. Composite TCE Elution Curve: Chalmers Soil Columns C10, C11, and C12.




Figure 19. Composite TCE Elution Curve: Russell Soil Columns R1, R2, and R3.




Figure 20. Composite TCE Elution Curve: Russell Soil Columns R4, R5, and R6.




Figure 21. Composite TCE Elution Curve: Russell Soil Columns R7, R8, and R9.




Figure 22. Composite TCE Elution Curve: Russell Soil Columns R10, R11, and R12.

each specific column test, the composite plot allowed a smooth curve to be drawn. On the other hand, if one followed the periodic fluctuations of TCE concentrations for any one specific column, the TCE elution pattern may be somewhat different from the composite elution patterns. Before comparing the composite elution curves on the basis of organic carbon, TCE loading, and water application rate, the elution curve for each specific column test group (identified in Table 22) will be discussed separately.

Columns C1-C3 (Figure 15, Table B2). TCE was initially detected in these effluents at 0.18 Calculated Pore Volumes (CPV) of cumulative effluent. Concentrations gradually increased to the mg/l range by 0.5 CPV. At 1.0 CPV, the composite elution curve indicated an effluent concentration of approximately 220 mg/l. From an effluent volume of approximately 1.3 l to 4.0 l, the TCE concentration increased to approximately 810 mg/l in an apparent linear manner. From 810 mg/l, the concentration gradually increased to a maximum of 840 mg/l at 4.5 l. Beyond this, there was a gradual, then almost linear, decrease in TCE concentration. The elution curve was slightly asymmetrical and exhibited some tailing on the descending portion.

Columns C4-C6 (Figure 16, Table B3). TCE was initially detected at 0.23 CPV. Concentrations in the mg/l range appeared by 0.47 CPV with a TCE concentration of 140 mg/l at 1.0 CPV on the composite elution curve. This concentration

increased linearly to 820 mg/l at 4.0 l of effluent volume then to a maximum of 880 mg/l. The TCE concentration then declined in a linear fashion for approximately 0.5 l, at which point the rate changed from linear to a decreasing rate of decrease. The elution curve was asymmetrical and exhibited tailing on its descending concentration portion.

Columns C7-C9 (Figure 17, Table B4). By 0.16 CPV, TCE was detected in the effluents with mg/l concentrations by 0.27 CPV. At 1.0 CPV the TCE concentration was 320 mg/l on the composite elution curve. Concentrations on the composite curve reached a maximum of 1,050 mg/l at 5.25 l and stayed constant through the final effluent value of 6.7 l. Since the final concentration did not decrease from the maximum, it could not be determined whether the elution curve was symmetrical or asymmetrical. Column C7 was removed from service on Day 122 when the bottom of the glass tubing was found to be broken.

Columns C10-C12 (Figure 18, Table B5). TCE was initially detected at 0.19 CPV and by 0.43 CPV had reached the mg/l concentration. By 1.0 CPV on the composite elution curve, the concentration was 365 mg/l. The concentration increased at a decreasing rate to 1,020 mg/l on the composite curve, slightly decreased to 980 mg/l then increased to 1,000 mg/l. At this point the TCE began to decrease until the final concentration was 340 mg/l at 13 l final volume. The elution curve was asymmetrical and exhibited slight tailing

toward the final stages of elution. As discussed previously, column C10 was removed from service on Day 44 because of a break in the glass tubing.

Columns R1-R3 (Figure 19, Table B7). TCE was initially detected at 0.25 CPV with concentrations in the mg/l range by 0.43 CPV. By 1.0 CPV on the composite elution curve, the concentration had reached 280 mg/l and climbed to a maximum of 1,050 mg/l at 5.0 l cumulative effluent volume. From this point, the TCE concentration decreased to 655 mg/l at the final effluent volume of 7.0 l. No tailing was noted; however, the elution curve appeared to be slightly asymmetrical.

Columns R4-R6 (Figure 20, Table B8). Initial detection of TCE came at 0.32 CPV. By 1.0 CPV the composite elution curve indicated a concentration of 200 mg/l. This concentration increased linearly to a broad peak with a maximum concentration of 980 mg/l. This broad peak initially decreased at an increasing rate until approximately 3.0 l of effluent volume. At this point, the rate of decrease slowed until the concentration was 40 mg/l at the final effluent volume of 12.7 l. This elution curve was asymmetrical with extensive tailing compared to the other column elution patterns.

Columns R7-R9 (Figure 21, Table B9). TCE was initially detected at 0.17 CPV with mg/l concentrations appearing by 0.38 CPV. By 1.0 CPV the concentration on the composite

elution curve was 440 mg/l. Beginning at approximately 1.0 l effluent volume (0.62 CPV), the TCE concentration increased linearly to 850 mg/l then tapered off to a maximum of 1,040 mg/l at the final effluent volume of 7.0 l. Since the concentration had not begun to decrease by the end of the investigation, it could not be determined if the elution curve would exhibit tailing or asymmetry. Column R7 was removed from service on Day 45 due to the appearance of free or undissolved TCE in the sample collection bottle as discussed later in this section of the thesis.

Columns R10-R12 (Figure 22, Table B10). TCE was detected by 0.25 CPV with mg/l levels by 0.30 CPV which showed a rapid increase by 0.65 CPV. At 1.0 CPV, the TCE concentration on the composite elution curve was 480 mg/l. The concentration increased to a maximum of 1,040 mg/l at 3.4 l then stayed constant until approximately 10 l of effluent volume. At this point the TCE concentration rapidly decreased in an apparently linear fashion. While no tailing was exhibited, the curve appeared to be asymmetrical. On Day 45 Column R12 was removed from service because of a break in the glass tubing.

General Information On All Columns. The erratic water application rate during the initial 40 days of the study presented two problems to all the column groups. One problem was that preliminary investigations determined the maximum water application rate for the soils to be 125 ml/

day. Although several daily applications exceeded this, no ponding was ever noted on the top of any columns. Another problem involved small effluent volumes collected for analysis. To ensure accuracy, 15 ml was the minimum effluent volume used for analysis. Consequently, during the initial 40 days of study, several small samples were not analyzed. Their volume, however, was logged into the daily cumulative effluent volume. This lack of data was most apparent in columns with the 100 ml/day water application rate.

None of the samples from the control columns indicated any detectable TCE in the effluent. This was expected because there was no history of any TCE spill or application on the site from which the soil cores were obtained. These negative results also indicated glassware was adequately cleaned. Since no blanks showed any detectable levels of TCE, the syringe cleaning procedures and quality of DI water used for dilution were also adequate.

At least one suspended solids analysis was run on each column during the period of Day 12 through Day 30. Since all results were less than 1.0 mg/l, there was no concern over a solids mediated effect on the head space analysis procedure. No further solids analyses were conducted. The clarity of the effluent was visually inspected daily; however, no turbid effluents were noted.

In all columns, TCE was detected at various levels before 1.0 CPV of effluent had passed through the soil column. There were several reasons for this occurrence with one of the most obvious being short-circuiting between the soil core and glass tubing of the column. It appeared, however, that no free or undissolved TCE initially short-circuited the entire length of the column because the early phases of elution show no immediate increase before 1.0 CPV. Since TCE is more dense than water, free TCE could have traveled faster than water before adsorbing onto soil or dissolving in the water, thus advancing the concentration front. Another reason for the early appearance of TCE was that the soil was not a homogeneous medium but contained tortuous passageways. Some fractions of the effluent may have traveled shorter passageways than other fractions and exited before than 1.0 CPV. Additionally, since the pore volumes were not quantitatively measured, they could have actually been less than that calculated because of immobile regions of the pore volume (74). Since the pore volume was used only as a basis for comparison, the CPV was accepted as a valid parameter.

Only one column, R7, showed evidence of free or undissolved TCE in the effluent. On Day 44 several globules of liquid, a total estimated less than 0.1 ml, were noticed in the bottom of the sample collection bottle. After 1:1 and 4:1 dilutions with DI water, the headspace analysis

still showed TCE concentration at or over the maximum solubility of 1,100 mg/l. Subsequent to the dilution, 10 ml of methanol were added to the serum bottle and shaken. After this, the globules were no longer evident, indicating they were free TCE. In view of this finding, Column R7 was removed from service.

Other columns also showed effluent concentrations slightly greater than the maximum solubility of 1,100 mg/l. Figures 17,19,21, and 22 show those columns were C7,C8, R3, and R7-12. With only one dilution (as discussed in Materials and Methods), though, the highest concentration found was 1,193 mg/l. In this sample, as well as all others initially determined to be over 1,100 mg/l, subsequent dilution lowered the concentration in proportion to the dilution ratio. Additionally, no globules of TCE were visually noted in any sample bottle before or after dilution. Consequently, the dilution method used to maintain linearity also served as a check on the presence of free or undissolved TCE. The TCE concentrations over 1,100 mg/l may have been due to additive errors in determining sample volume, dilution water volume, and GC sample injection volume. Conversely, for the same reasons, some concentrations were probably calculated to be less than actual as evidenced by the fluctuation of concentrations on a day-to-day basis. This was especially evident for those columns charged with 10 ml of TCE.

Concern developed over the constant high concentrations of TCE in several of the column effluents. It was considered possible that these saturated or nearly saturated TCE concentrations could have been due to free TCE which migrated through the soil and coated the gravel or stayed as a pool on the bottom stopper. To check this possible cause, the gravel and stopper assemblies were removed and replaced with new gravel and stopper assemblies for the following columns on the indicated days and cumulative effluent volumes: C7, Day 80, 4.363 l; C8, Day 80, 4.208 l; C11, Day 55, 5.165 l; C12, Day 55, 5.446 l; R8, Day 78, 4.111 l; R9, Day 78, 4.240 l; R10, Day 78, 7.790 l; R11, Day 78 7.655 l. All of these columns had been loaded with 10 ml TCE. As shown in Figures 17,18,21, and 22, changing the gravel and stopper assemblies had no effect on the effluent concentrations. This reinforced the finding that, except for column R7, no free TCE was transported through the soil columns during the course of the investigation. The saturated or nearly saturated effluent concentrations observed were consequently considered to be due to the TCE present in the soil.

Time of Saturation Study. As indicated in the discussion of specific column groups and as shown in Figures 15-22 and Tables B2-B11, TCE concentrations from some, but not all columns approached or exceeded 1,100 mg/l, the maximum solubility of TCE in water (45,51). The question arose as

to whether this finding was relevant in adsorption:desorption phenomena or whether it simply pertained to the time required for TCE dissolution. To answer this question, an experiment was conducted to determine the time required for a given volume of water to become saturated with TCE when TCE was present in excess of its maximum solubility.

The experiment was conducted as follows:

1. A number of 125 ml serum bottles were completely filled with DI water. Two ml (approximately 2.9 g) of TCE were pipetted into the mouth of the bottle so that the TCE settled through the water the entire depth of the bottle and the water displaced was allowed to overflow. The bottles were sealed with Teflon® faced septa and aluminum crimp caps and inverted three times to provide mixing. The bottles were allowed to remain quiescent at 20°C.
2. Periodically, one of the bottles was removed. A sample of TCE solution was withdrawn via a syringe needle through the septum with the end of the needle approximately mid-depth of the bottle.
3. The TCE concentration of the sample was determined according to the procedure listed in Materials and Methods.

Results of TCE concentrations determined during the study are listed in Table B12 of Appendix B and plotted in

Figure 23. As shown from the figure, the TCE concentration reached 90% of maximum by 25 hours, 95% by 30 hours, and 100% by 45 hours. This experiment was solely intended to indicate the magnitude of time required for maximum TCE dissolution. It was not intended as an accurate measure of dissolution kinetics.

Since the dissolution experiment was conducted with quiescent conditions, one must consider how this would compare to conditions within the soil column. Water was applied to the column drop-by-drop, so some mixing occurred at the point of soil:water contact. Since the pore volume of the soil contains a degree of tortuosity, additional mixing and contact was assured between the water and any adsorbed or free TCE. It was assumed that this degree of mixing would allow faster TCE dissolution than quiescent conditions would allow. Consequently, TCE dissolution within the soil column probably proceeded at a faster rate than that indicated in the experiment. It is probable that the rate of TCE dissolution within the column was not the major factor in the movement of TCE through the columns, since the previously estimated residence times for the columns were 15 and 30 days for 100 and 50 ml/day water application rates, respectively.

Effluent pH Values. Effluent pH was measured on all columns on an approximately weekly basis with results listed in Tables B13 and B14. Table 32 summarizes the pH range and




Figure 23. Time of Saturation for TCE and Water.

Table 32. Maximum, Minimum, and Mean pH for Soil Column Effluents.

Column	pH			No. of Measurements
	Maximum	Minimum	Mean	
<u>Chalmers Soil</u>				
C1	6.91	5.52	6.25	18
C2	6.72	5.32	6.20	18
C3	6.74	5.70	6.28	18
C4	6.72	5.83	6.23	18
C5	7.19	5.62	6.41	18
C6	7.08	5.82	6.40	18
C7	7.49	6.19	6.72	16
C8	7.21	5.85	6.48	18
C9	7.30	6.12	6.67	18
C10	7.11	5.90	6.37	6
C11	7.39	5.80	6.58	18
C12	7.59	5.76	6.50	18
Control	7.33	5.92	6.34	18
<u>Russell Soil</u>				
R1	7.23	5.62	6.39	18
R2	6.81	5.41	6.23	18
R3	7.37	5.74	6.35	18
R4	7.16	5.81	6.44	18
R5	7.23	5.71	6.33	18
R6	6.83	6.16	6.40	18
R7	6.30	6.08	6.18	5
R8	7.16	5.83	6.30	18
R9	7.25	5.97	6.50	18
R10	6.67	5.84	6.19	18
R11	7.21	5.90	6.35	18
R12	6.82	5.95	6.31	5
Control	6.72	5.87	6.28	18

- Notes:
1. Columns R7 and C10 removed from service on day 44.
 2. Column R12 removed from service on day 45.
 3. Column C7 removed from service on day 122.

mean for each of the columns over the entire study. A review of the individual measurements indicates no particular trend; however, all mean pH values were higher than that of the applied water (pH 5.5-6.0). In addition, there was no particular trend for pH values among columns within a specific group. Since the soil pH values listed in Table 15 are all slightly acid or just slightly basic, it was probable the pH of the effluents was largely affected by the complex soil:water interactions as discussed in the Literature Review.

Comparison of TCE Elution Patterns

The factors which varied between the columns in the elution studies were soil type, water application rate, and mass of TCE applied. Effects of these factors are compared in Figures 24-29. To construct these figures, the composite elution curves for the specific column groups of Figures 15-22 were replotted onto collective plots based upon soil type, water application rate, and TCE loading. Therefore, to assess the effects of one factor, such as TCE loading, one must study the collective plots based upon the other two factors, soil type and water application rate. Each of these factors will be discussed separately, based upon the column conditions of Table 22 of the Preliminary Investigations.




Figure 24. Composite TCE Elution Curves for 5 ml TCE Application to Soil Columns.




Figure 25. Composite TCE Elution Curves for 10 ml TCE Application to Soil Columns.




Figure 26. Composite TCE Elution Curves for 50 ml/day Water Application Rate to Soil Columns.




Figure 27. Composite TCE Elution Curves for 100 ml/day Water Application Rate to Soil Columns.




Figure 28. Composite TCE Elution Curves for Chalmers Soil Columns.




Figure 29. Composite TCE Elution Curves for Russell Soil Columns.

Soil Type

Table 17 lists the calculated composite organic carbon content of Chalmers soil as 1.4% and that of Russell soil as 0.53%. Other soil parameters are listed in Tables 15 and 16.

The elution curves show the Chalmers soil initially retarded the movement of TCE more significantly than did the Russell soil. This result was more pronounced with the 5 ml TCE loading than with the 10 ml TCE loading. For instance, in Figure 24, the initial stages of the elution curves show lower effluent concentrations for Chalmers soils than for Russell soils at corresponding effluent volumes for 50 ml/day and 100 ml/day application rates. For the latter stages of the 100 ml/day application rate curve, however, the Chalmers soil exhibited higher TCE concentrations. These same results were also indicated by Figures 27 and 28.

Elution curves for the 10 ml TCE loading show slightly less difference between the soils than did the 5 ml TCE loading curve. As shown in Figure 25, the initial appearance of TCE in the effluent came at approximately the same effluent volumes for the different column groups. Both soils exhibited quite similar rates of increase in effluent TCE concentration. These rates of increase are greater than those exhibited by the 5 ml loading. The Russell effluent reached an almost constant effluent TCE concentration which

only decreased from 1,040 to 1,030 mg/l over 6.3 l of effluent. The Chalmers soil exhibited a slight drop in its broad peak or hump which lasted over only 4.0 l of effluent. Concentration levels on the broad peak of the Chalmers elution curve varied from 970-1,020 mg/l. Additionally, the concentration levels of the Chalmers curve (for 100 ml/day) began to decline at a lower effluent volume with an apparent smaller rate of decline when compared to Russell soils.

Figures 26 and 27 also indicate the greater retardation of TCE by Chalmers soil. In these figures, for corresponding soil and water application rates, the elution curves for 5 ml loading show lower TCE concentrations at all points than do the 10 ml loadings. However, in the early stages of both figures, the elution curves for the Russell 5 ml TCE loading closely compared with the curves for the Chalmers 10 ml TCE loading.

From the adsorption isotherms, the adsorptive capacity of the Chalmers soil was found to be greater than that of the Russell soil for both particle sizes studied. In the column studies, the effect of particle size was not considered although soil analyses of Table 15 indicated comparable size distributions of the sand, silt, and clay fractions of the two soils. Consequently, it was consistent with the findings of others (38,55,65,77,79) that the organic carbon content of the two soils was responsible for

the difference in TCE elution through the columns. In this case, the Chalmers soil exhibited greater retardation of TCE movement.

Water Application Rate

The effects of water application rate are graphically shown in Figures 24, 25, 28, and 29. For the 5 ml TCE loading of Figure 24, the initial stages of elution to maximum TCE concentrations were similar for both application rates (50 and 100 ml/day) for the two soils. Once the elution curves reached maximum concentration, the similarity slightly deviated in the latter stages of elution.

For columns R1-3 (50 ml/day), the maximum concentration reached 1,050 mg/l. This was greater than that for R4 (100 ml/day) which reached 970 mg/l. The converse was true for the Chalmers soil; columns C4-6 (100 ml/day) exhibited a maximum TCE concentration of 880 mg/l while the maximum for columns C1-3 was lower at 840 mg/l. Both of the curves declined at approximately the same rates, separated only by the difference in maximum concentration. Conversely, the elution curve of columns R1-3 declined more rapidly than that for columns R4-6 which showed a broader peak than did columns R1-3.

The differences shown by the 5 ml TCE loading were not apparent in the curves of Figure 25 for the 10 ml TCE loading. There was little variation in elution between the 50 and 100 ml/day water application rates for either soil.

However, the elution curves for the 50 ml/day rates had not yet begun to decline when the study was terminated, so the shape or pattern of the curves in decline could not be determined.

The data shown in Figures 24,25,28, and 29 are graphical indications that the water application rates of this study did not affect the elution of TCE from the soil columns for either soil or TCE loading studied. As discussed in the Literature Review, Schwarzenbach and Westall (77) found significant differences between pore water velocities of 8.7×10^{-4} cm/sec and 1.0×10^{-2} cm/sec for adsorption: desorption studies in columns.

Pore water velocities for the 50 and 100 ml/day application rates of this study were calculated according to Schwarzenbach and Westall (77) as shown in Appendix A. For the Chalmers columns, the calculated average pore water velocities were 2.8×10^{-5} cm/sec and 5.7×10^{-5} cm/sec for 50 and 100 ml/day application rates, respectively. For the Russell columns, the calculated average pore water velocities were 3.0×10^{-5} cm/sec and 6.0×10^{-5} cm/sec for 50 and 100 ml/day, respectively. Since the pore water velocities were calculated, not measured, they were approximate values only. In addition, since the water application and effluent collection did not always take the full 24 hours of each day, the actual pore water velocities probably varied during the course of the day. Regardless,

the calculated velocities can be used as a basis for comparison to the work of others.

In this study, the pore water velocities varied only by a factor of two while those of Schwarzenbach and Westall (77) varied by a factor of 11.4. In addition, their lower velocity was 14.7 times greater than the high velocity of this study. Consequently, while comparison between the two studies was not applicable, it is apparent that higher velocities than those of this study are necessary to effect a difference in adsorption due to water application rate.

The water application rates of 50 ml/day and 100 ml/day represent 0.43 and 0.86 inches of rainfall per day. Consequently, the pore water velocities shown in this study are closer to that for natural conditions than that shown by Schwarzenbach and Westall (77). Rainfall, then, should cause no effect due to pore water velocity. However, when considering the time of adsorption previously discussed and the lack of effect of flow rate, it is probable that local equilibrium (as defined in the Literature Review) was reached in all soil columns.

Amount of TCE Applied

As expected, the elution of TCE was more pronounced for the columns loaded with 10 ml of TCE than for those loaded with 5 ml of TCE. This effect was found for both soils as best shown by Figures 28 and 29. Of the two soils, the Russell columns exhibited less difference in elution for the

AD-A147 918


FATE AND DISPOSITION OF TRICHLOROETHYLENE IN SURFACE
SOILS(U) AIR FORCE INST OF TECH WRIGHT-PATTERSON AFB OH
T J WALKER 1984 AFIT/CI/NR-84-92D


3/4

UNCLASSIFIED

F/G 13/2

NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

two different TCE loadings. This was shown by the fact that for both loadings on Russell soils, the maximum TCE concentrations differed only by 70 mg/l whereas the maximum concentrations for Chalmers soil differed by 210 mg/l. In addition, as previously discussed, free or undissolved TCE was found in the effluent of column R7 but was not found in any other effluents. This point was significant because during a large portion of the study, the columns loaded with 10 ml TCE had constant maximum TCE concentrations only slightly less than 1,100 mg/l, the maximum solubility of TCE in water.

A plausible explanation for the high constant effluent concentrations can be drawn from results of tests previously discussed. The adsorption isotherms indicated increasing adsorption at high concentrations. Hamaker (30) indicated adsorption at chemicals applied directly to the soil can be significantly higher than adsorption of chemicals from solution. This aspect was especially apparent from calculated X/M and X values of Table 25 which indicated the maximum adsorptive capacities for the columns at various TCE concentrations. For instance, in extrapolating the isotherm to a TCE concentration of 1,100 mg/l (maximum solubility of TCE), Table 25 indicates the maximum TCE which could be adsorbed by one of the columns was 6.103 g (4.2 ml). Since the TCE loadings were 5 ml (7.3 g) and 10 ml (14.6 g), free

or undissolved TCE should have been detected in the effluents of columns other than R7.

The increased mobility of TCE at the higher loadings can be theorized as due to several factors. In one respect, it was possible that the upper layers of soil strongly adsorbed much of the applied TCE with subsequent elution by the applied water at a constant rate near the maximum solubility of TCE. As the initially free TCE and subsequent TCE solution traveled through the soil, the TCE may have further adsorbed onto the soil until all adsorption sites were saturated. Once the adsorption sites were saturated, the TCE in solution could have moved through the soil with no further adsorption occurring. In the case of the higher TCE loadings, the adsorption sites throughout the columns became saturated more quickly and the higher TCE concentrations appeared in the effluent at smaller effluent volumes. Then, as the upper levels of adsorbed TCE gradually desorbed, equilibrium concentrations decreased at points throughout the columns, thus effectively lowering effluent TCE concentrations.

Cumulative TCE Elution

A comparison of the cumulative TCE elution patterns for the soil columns provided additional evidence that adsorption of TCE had occurred within the soil columns. The cumulative elution curves of Figures 30 and 31 were constructed in the following manner:

1. The effluent TCE concentrations from the composite elution curves of Figures 15-22 were recorded at 0.33 l increments of cumulative effluent volume (Table B15, Appendix B).

2. The area under the composite elution curves represented the amount of TCE eluted. Those areas were determined by use of Simpson's Approximation to the data of Table B15. The corresponding incremental cumulative mass of TCE eluted for each composite column group determined in this manner is listed in Tables B16 and B17.

3. The percent TCE eluted in the column groups (Tables B16 and B17) was determined on the basis of the cumulative mass of TCE eluted and the corresponding mass of TCE applied to each particular column group. This information was plotted in Figures 30 and 31.

Figure 30 illustrates several findings previously discussed. No difference in elution based solely upon water application rate was shown for any of the corresponding column groups. Additionally, the higher organic soil (Chalmers) showed a higher retardation capacity than did the lower organic carbon soil (Russell). Also, the initial cumulative elution of TCE from Russell soil loaded with 5 ml TCE was nearly identical to that of the Chalmers loaded with 10 ml TCE. These findings indicate the Chalmers soil had a




Figure 30. Cumulative Mass Elution of TCE from Soil Columns.




Figure 31. Cumulative Percentage Elution of TCE from Soil Columns.

greater capacity than the Russell soil to retain the TCE at both 5.0 and 10.0 ml TCE loadings.

Figure 31 illustrates the same findings of Figure 30. It also compares the percentage elution to that which could be expected from non-adsorption of TCE in a plug flow reactor (PFR) of volume equal to the approximate pore volume of the two different type soil columns. Data used to plot the experimentally determined curves of Figure 31 are contained in Table B18.

The PFR curve was determined in the following manner. No elution of TCE was considered until one approximate pore volume, 1.66 l (average of pore volumes for Russell and Chalmers soil). After one pore volume, the TCE effluent concentration was considered saturated at 1100 mg/l. This concentration was considered to continue until all TCE applied (either 5 or 10 ml) had eluted from the column. Consequently, TCE was considered eluted at the rate of 1100 mg/l in the effluent (1.1 g/l) or 0.75 ml/l. For the 5 ml TCE loading, the percentage elution rate was 15% TCE applied/l effluent. For the 10 ml TCE loading, the % elution rate was considered 7.5% TCE applied/l effluent after 1 pore volume. Consequently, Figure 31 shows the cumulative percentage elution rate of TCE from the soil columns as considered for both the 5 and 10 ml TCE loadings.

For the 5 ml TCE loading, 100% of the TCE would be eluted by 8.28 l effluent for a PFR. For the 10 ml loading, 100% of

the effluent would be eluted by 14.9 l for a PFR. Theoretically, no TCE would have appeared in the effluent before 1 calculated pore volume because of the definition of a plug flow reactor.

Comparing theoretical PRF elution curves with the experimentally determined elution curves, one sees that the steps are quite similar. However, the experimentally determined curves were dissimilar to the theoretical curves in that the theoretical curves indicate a higher percentage TCE elution than do the experimental curves for the same effluent volumes. Since the theoretical curves assumed a non-reactive species, this dissimilarity is not surprising because the batch isotherms had shown that TCE was, in fact, adsorbed from solution and was not a non-reactive species as assumed with a PFR.

Biodegradation Studies

As discussed in the Literature Review, TCE has been shown to be biodegradable. Within this investigation, several different studies and analytical tests were conducted to determine if biodegradation was a major factor in the fate of TCE within the soil columns.

Nutrient Addition

Alexander (1) states that nitrogen is the key nutrient required for biological degradation of organic compounds in soil environments. To determine if TCE biodegradation could be enhanced with nutrient addition, a dilute solution of ammonium hydroxide was added to one column of each column

group beginning on Day 75. The concentration of ammonia as nitrogen was 10 mg/l. This concentration was chosen based upon the theoretical Chemical Oxygen Demand (COD) of TCE, 0.54 mg COD/mg TCE (calculated in Appendix A). With an approximate theoretical COD:N requirement of 40:1 (1,27,29), the 10 mg/l ammonia nitrogen would satisfy the nitrogen requirement of 761 mg/l TCE. From Figures 15-22, the effluent TCE concentrations ranged from 500-900 mg/l at the start of nutrient addition (Day 75). Ammonia addition to selected columns (C1,C5,C7,C11,R1,R4,R8, and R10) was continued through Day 100. During this period and the subsequent 15 or 30 day residence time after nutrients were discontinued, no evidence was apparent in Figures 15-22 to indicate the effluent TCE concentrations in enhanced columns were significantly lower than TCE concentrations from the other columns within the groupings.

The ammonia nitrogen concentrations in the effluent from Day 71 through Day 122 are listed in Table B19 of Appendix B. These results indicate the nutrient enhanced columns generally passed the ammonia through the soil with very little depletion as shown by the maximum effluent values of 8.0-12.0 mg/l for the enhanced columns. The corresponding non-enhanced columns maintained generally constant ammonia nitrogen concentrations of approximately 0.3-0.7 mg/l during the same period with no particular pattern or trend for

effluent concentration. Generally, the ammonia concentration in the effluent of non-enhanced columns was higher than that for the control columns. No attempt was made to determine mean ammonia concentrations or to compare maximum or minimum concentrations because: (1) the ammonia concentrations were not determined for every effluent on each sampling run; and (2) since ammonia was added to the column with a lag time before it appeared in the effluent, a mean concentration would have no significance for comparison to non-enhanced columns.

During the nutrient addition, nitrate nitrogen concentrations were also determined on the column effluents. Results are shown in Table B20 of Appendix B. Generally, the non-enhanced columns showed effluent levels of 0.2-0.5 mg/l nitrate nitrogen. The nitrate levels of the enhanced column effluents were higher, having increased approximately 0.5 mg/l by the end of the enhancement period, Day 100, to approximately 0.7-1.0 mg/l. The control columns (to which no TCE had been applied) had nitrate nitrogen levels of 0.42-0.90 mg/l. These levels were higher than those of the non-enhanced columns. For the same reason stated for the ammonia concentrations, no attempt was made to compute a mean or to compare maximum and minimum values.

Nitrite nitrogen was measured on the control columns on Day 64 and on all columns on Days 73 and 78. Nitrite was

not detected in any of the effluents on these days and no further analyses were conducted.

TCE requires initial dechlorination of the molecule (releasing chloride ions) before it can be biologically degraded (26,46). Complementary to the ammonia and nitrate analytical tests, the chloride levels of the effluents were determined during the period Day 66-Day 127. Table 33 summarizes these measurements as contained in Table B21. Compared to the control columns, all TCE laden soil columns had higher effluent chloride levels over the analytical period. Except for column C1, all nutrient enhanced columns showed mean chloride concentrations 2.0-6.0 mg/l higher than non-enhanced columns. This indicated that some form of TCE degradation had probably occurred within the columns.

The theoretical amount of TCE that would have to be degraded to produce the chloride levels found could be calculated. Since chlorine represents 80.95% of the the molecular weight of TCE (15,45,76), complete dechlorination and degradation of 1.0 mg of TCE would result in 0.81 mg of chloride. Conversely, 1.0 mg of chloride would represent complete dechlorination and degradation of 1.24 mg TCE. Consequently, the 2.0-6.0 mg/l difference in chloride level between enhanced and non-enhanced columns would indicate only a 2.5-7.4 mg/l difference in effluent TCE concentrations. This slight difference was not significant and could neither be accounted for in composite

Table 33. Summary of Soil Column Effluent Chloride Measurements.

Column	Chlorides, mg/l				
	Max.	Min.	Mean	Std. Dev.	**Corr. Mean
<u>Chalmers Soil</u>					
*C1	9.6	1.9	5.3	2.32	3.3
C2	6.3	3.7	5.1	0.90	3.1
C3	5.7	2.4	4.0	1.02	2.0
C4	4.8	2.2	3.4	0.96	1.4
*C5	8.5	2.8	6.0	2.08	4.0
C6	4.2	<1.0	2.9	1.15	0.9
*C7	12.2	4.1	8.6	2.60	6.6
C8	3.5	1.1	2.5	0.71	0.5
C9	4.1	1.0	2.2	1.13	0.2
C10	Removed from service on Day 44.				
*C11	12.1	3.8	8.3	2.36	6.3
C12	4.8	1.4	3.1	1.16	1.1
Control	3.2	1.0	2.0	0.71	-
<u>Russell Soil</u>					
*R1	10.8	4.8	7.5	1.96	5.9
R2	4.6	1.3	2.7	1.02	1.1
R3	3.2	<1.0	2.3	0.76	0.7
*R4	10.2	3.6	6.0	1.96	4.4
R5	4.6	1.6	3.2	0.98	1.6
R6	4.4	<1.0	2.7	1.24	1.1
R7	Removed from service on Day 44.				
*R8	10.6	2.8	6.4	2.21	4.8
R9	5.3	1.8	3.2	1.14	1.6
*R10	8.5	1.4	6.0	2.44	4.4
R11	4.2	1.2	2.5	1.02	0.9
R12	Removed from service on Day 45.				
Control	3.1	<1.0	1.6	0.66	-

*Indicates columns to which 10 mg/l ammonia - N added to elution water.

**Corr. Mean = Corrected Mean = Mean of Column - Mean of Control.

elution curves of Figures 15-22 nor differentiated in individual analyses due to the random error of the analytical tests. The effect of less than complete dechlorination will be discussed later.

During the 26 days of nutrient enhancement, either 50 ml/day or 100 ml/day of 10 mg/l solution of ammonia nitrogen were added to the soil columns. In terms of total ammonia added to the columns, this equated to either 13 mg (50 ml/day) or 26 mg (100 ml/day). As previously discussed, 10 mg of ammonia nitrogen would theoretically satisfy the nutrient requirements of 761 mg of TCE. Consequently, 13 mg would theoretically satisfy 989.3 mg of TCE while 26 mg would theoretically satisfy 1,987.5 mg of TCE. If these amounts of TCE were to be considered completely dechlorinated and degraded, then the respective amounts of chloride released would be 800 and 1,600 mg. These chloride amounts can be correlated to the flow rates. During the enhancement period, either 1.3 l (50 ml/day) or 2.6 l (100 ml/day) of water were applied to the columns. Therefore, the theoretical chloride concentration (if all available added nitrogen was used) should have reached 615 mg/l. At least 800 mg (500 ml/day) or 1,600 mg (100 ml/day) of chloride would then have eluted during the enhancement period plus one residence time. Chloride measurements during this time period did not indicate levels or quantities of chlorides of this magnitude. Nutrient

enhancement, then, provided very little additional biological degradation of TCE within the soil columns. Because of this and findings from Warburg studies discussed later, nutrient enhancement was stopped at Day 100.

Warburg Respirometer Studies

Aerobic biodegradation studies using Warburg respirometry were conducted concurrently with the column elution studies and nutrient enhancement of selected soil columns. The purpose of the respirometry studies, as discussed in Materials and Methods, was to determine relative rates of aerobic TCE degradation by various profile depths of the soils under study. These studies were not intended to determine the exact amount of TCE degradation. After a testing protocol was developed using a glucose solution as substrate, actual work using a TCE solution with an uncontaminated soil sample was attempted according to the procedure described in Materials and Methods.

The initial respirometric study used soil from a 2.5 inch depth of an extra Chalmers column which had not been used in the column elution studies. This soil sample had never had TCE applied to it and was considered "unacclimated". Glucose, an easily degradable material, was used as a substrate to indicate biological activity. TCE solutions ranging from 55-1,100 mg/l were used as test substrates. The results of the test are plotted in Figure 32 for results shown in Table D1 of Appendix D. The table




Figure 32. Warburg Oxygen Uptake for Unacclimated Chalmers Soil supplemented with TCE for 2.5 Inch Depth.

and figure show the cumulative oxygen utilization in microliters (ul) to be negative when corrected for endogenous utilization for all TCE solutions tested. The glucose showed a positive oxygen utilization, so the test was considered to have been run under satisfactory conditions. Additionally, the total cumulative endogenous oxygen utilization was 171.51 ul in an approximate linear fashion. Divided over the period of the test 36 hours, and the mass of soil used in the test, 2.70 g, the endogenous rate was approximately 1.76 ul/g soil/hr. Converting this oxygen utilization to carbon dioxide production. then 1.76 ul/g soil/hr of carbon dioxide was produced. On a mass basis, this converts to 3.46 ug/g soil/hr or 83 ug/g/day of carbon dioxide. This production rate closely approximated that reported by Alexander (1). He found typical carbon dioxide production for mineral soils in the field commonly ranged from 5.0-50 ug/g soil/day. Consequently, because of this and the degree of glucose respired by the soil, the test was considered to have been representative of normally expected conditions.

From this initial test with unacclimated soil, it was determined that the levels of TCE tested were inhibitory to degradation over the time period used. Even nutrient enhancement of a 55 mg/l TCE concentration showed no evidence of oxygen utilization. Since degradation of anthropogenic compounds such as TCE may require induction of

enzymes before the compound can be biodegraded (1,27,46), additional testing was conducted with "acclimated" soil.

Acclimated soil was obtained from two soil columns which had been removed from the elution studies because of breakage of the glass tubing. These columns were C10 for Chalmers soil and R12 for Russell soil. During the initial two weeks after being removed from service, the columns had been maintained in the column room. After this period, the columns were extruded, sectioned, wrapped in aluminum foil, and refrigerated at 4°C. Soil from these sections was used in the acclimated studies.

The first test with acclimated soil was conducted with Chalmers soil from a 2.5 inch depth. Results are shown in Table D2 and Figures 33 and 34. This test appeared successful so subsequent tests were run with other acclimated soils. Since these tests were to be used on a comparative basis, the total oxygen uptake for each solution tested was determined when possible. This was determined by intersecting the linear portion of the uptake curve with the upper portion of the same curve as it approached the endogenous rate. This total oxygen uptake was converted to a percentage of substrate respired with the theoretical TCE:oxygen relationship calculated in Appendix A. This same relationship was used to convert the rate of oxygen uptake to a rate of TCE respiration. The rate of oxygen uptake was determined from the initial linear portion of the




Figure 33. Warburg Oxygen Uptake for Acclimated Chalmers Soil Supplemented with TCE for 2.5 Inch Depth.




Figure 34. Warburg Oxygen Uptake for Acclimated Chalmers Soil Supplemented with a Glucose Substrate.

cumulative oxygen uptake curve. The total oxygen uptake and percentage respired were similarly determined for glucose according to the glucose:oxygen relationship calculated in Appendix A. These data are contained in Tables 34, 35, and 36.

For the 2.5 and 15 inch depth acclimated samples, the Chalmers soil (1.4% organic carbon) showed a greater total oxygen uptake and percentage respired for the glucose substrate than shown by the Russell soil (0.53% organic carbon). For the same parameters at the 31 inch depth, the Russell soil showed higher results. However, at none of the depths tested was the corresponding difference between values for the two different soils great. For Chalmers soil, the glucose degradation required no lag time and was complete (rate returned to endogenous) within two to four hours. The Russell soils required a lag time of approximately two hours with degradation complete in six to ten hours.

In all soils, the 110 mg/l TCE solution and the 550 mg/l TCE solution (Russell, 2.5 inch depth) produced negative cumulative oxygen utilization. Since this indicated an inhibitory effect, no total uptake or rate of respiration could be determined. These same parameters also could not be determined for any of the TCE solutions tested with the soils from 31 inch depths. Testing with soils from these depths proved to be too sensitive for the degree of accuracy

Table 34. Total Oxygen Uptake from Acclimated Soil Warburg Studies When Supplemented with TCE or Glucose.

Soil Type and Depth, Inches	Total Oxygen Uptake, ul				
	Glucose, 500 mg/l	TCE, 110 mg/l	TCE, 55 mg/l	TCE, ^a 55 mg/l	TCE, ^b 55 mg/l
<u>Chalmers Soil</u>					
2.5	91	nd	3.6	4.8	5.6
15.0	69	nd	2.2	2.2	2.2
31.0	16	nd	nd	nd	nd
<u>Russell Soil</u>					
2.5	79	nd ^c	3.4	3.6	4.1
15.0	53	nd	2.2	2.6	2.4
31.0	21	nd	nd	nd	nd

Notes: ^aSolution contained 1 mg/l ammonia nitrogen.

^bSolution contained 2 mg/l ammonia nitrogen.

^cTCE solution = 550 mg/l.

nd - Unable to be determined.

Table 35. Percent Substrate Respired from Acclimated Soil Warburg Studies When Supplemented with TCE or Glucose.

Soil Type and Depth, Inches	Percent Substrate Respired				
	Glucose, 500 mg/l	TCE, 110 mg/l	TCE, 55 mg/l	TCE, ^a 55 mg/l	TCE, ^b 55 mg/l
<u>Chalmers Soil</u>					
2.5	24.5	nd	17.3	23.1	26.9
15.0	18.6	nd	10.4	10.4	10.4
31.0	4.3	nd	nd	nd	nd
<u>Russell Soil</u>					
2.5	21.3	nd ^c	16.4	17.3	19.7
15.0	14.3	nd	10.8	12.5	11.8
31.0	5.6	nd	nd	nd	nd

Notes: ^aSolution contained 1 mg/l ammonia nitrogen.

^bSolution contained 2 mg/l ammonia nitrogen.

^cTCE solution = 550 mg/l.

nd - Unable to be determined.

Table 36. Rate of TCE Respiration from Acclimated Soil Warburg Studies When Supplemented with TCE.

Soil Type and Depth, Inches	Rate of TCE Respiration, ug TCE/g soil/hr			
	TCE, 110 mg/l	TCE, 55 mg/l	TCE, ^a 55 mg/l	TCE, ^b 55 mg/l
<u>Chalmers Soil</u>				
2.5	nd	0.39	0.39	0.39
15.0	nd	0.26	0.26	0.26
31.0	nd	nd	nd	nd
<u>Russell Soil</u>				
2.5	nd ^c	0.39	0.39	0.39
15.0	nd	0.26	0.26	0.26
31.0	nd	nd	nd	nd

Notes: ^aSolution contained 1 mg/l ammonia nitrogen.

^bSolution contained 2 mg/l ammonia nitrogen.

^cTCE solution = 550 mg/l.

nd - Unable to be determined.

afforded by the Warburg micromanometers. The endogenous rates for the 31 inch depth samples, and their corresponding carbon dioxide production rates appear to fall within the order of magnitude suggested by Alexander (1); however, biological activity of these samples apparently was not enough to provide a significantly different oxygen uptake with the TCE solution to accurately measure the respiration of TCE.

For the 55 mg/l TCE solutions, both soils exhibited higher total oxygen uptake and percentage respired at the 2.5 inch depth than at the 15 inch depth. This decrease with depth was expected since according to Table 7 (1) the concentration of microorganisms decreased with depth. When compared between soils, however, the Chalmers 2.5 inch depth exhibited a higher uptake and percentage of TCE respired than did the Russell 2.5 inch depth. The opposite was true at the 15 inch depth. One possible explanation for this was that the concentration of microorganisms is often proportional to the organic carbon content of the soil (1,27). According to Table 15, the percentage of carbon at the 2.5 inch depth of the Chalmers soil was 3.03% while for Russell soil it was 1.22%. This was a much greater difference than that at 15 inches where the percentage of organic carbon for Chalmers was 0.59% and 0.41% for Russell soil. Consequently, the concentration of microorganisms in the Chalmers soil at 2.5 inches may have been significantly




Figure 35. Warburg Oxygen Uptake for Acclimated Chalmers Soil Supplemented with TCE for 15 Inch Depth.




Figure 36. Warburg Oxygen Uptake for Acclimated Chalmers Soil Supplemented with TCE for 31 Inch Depth.




Figure 37. Warburg Oxygen Uptake for Acclimated Russell Soil Supplemented with TCE for 2.5 Inch Depth.




Figure 38. Warburg Oxygen Uptake for Acclimated Russell Soil Supplemented with TCE for 15 Inch Depth.




Figure 39. Warburg Oxygen Uptake for Acclimated Russell Soil Supplemented with TCE for 31 Inch Depth.




Figure 40. Warburg Oxygen Uptake for Acclimated Russell Soil Supplemented with a Glucose Substrate.

greater than that at the corresponding depth for Russell soil. However, with only a slight difference in organic carbon content at 15 inches, there may have been no significant difference in the number of microorganisms at that depth. Additionally, since the types of microorganisms may have varied between the types of soils and depths (1,27,29), no particular significance can be attached to differences between the soils.

The 55 mg/l TCE substrates enhanced with ammonia nitrogen showed slightly higher percentage substrate respired and corresponding total oxygen uptake compared to the non-enhanced 55 mg/l TCE solution. This was evident for the 2.5 and 15 inch depths for each soil. The difference between the 1 mg/l ammonia and 2 mg/l ammonia enhancement was slightly apparent for the 2.5 inch depth but not apparent for the 15 inch depth. Additionally, the ammonia did not enhance the rate of degradation. Based upon this and the results of the ongoing column nutrient enhancement studies, it appeared this type of nutrient addition did not increase TCE degradation. Consequently, the nutrient enhancement column studies were terminated on Day 100.

As a measure of the validity of the Warburg tests as run in this investigation, the rates of endogenous respiration and the associated carbon dioxide production were calculated for each soil and depth tested. These values are shown in Table 37. As previously discussed, Alexander (1) reported

Table 37. Rate of Endogenous Respiration and Carbon Dioxide Production for Soil Samples from Columns at Various Depths.

Soil Type and Depth, Inches	Rate of Endogenous Respiration, ul O ₂ /g soil/hr	Rate of Carbon Dioxide Production, ug CO ₂ /g soil/day
<u>Chalmers Soil</u>		
2.5 ^a	1.8	83
2.5	1.4	66
15.0	0.9	42
31.0	0.7	33
<u>Russell Soil</u>		
2.5	1.0	47
15.0	0.6	28
31.0	0.5	24

Note: ^aUnacclimated soil. All other soils were acclimated.

the typical mineral soil in the field produces 5.0-50 ug carbon dioxide/g soil/day. The production rates shown in Table 37 closely approach this order of magnitude. Additionally, since field soil would probably be of a lower temperature than the 25°C conditions of the Warburg studies, the values calculated for Table 37 are probably higher than would be expected for the same soils in the field.

Summary

These studies were intended to determine if biodegradation was a major factor in the fate of TCE within the soil columns. It was not intended to be an attempt to determine kinetics or mechanisms of TCE biodegradation. However, several points from the studies were worth discussion.

The pH of the column effluents fell within the range for satisfactory growth conditions as previously discussed. Consequently, pH could not have been an inhibitory factor in the degradation studies.

In neither the column enhancement nor the Warburg studies did nitrogen addition significantly increase TCE degradation. The glucose substrates in the Warburg studies were degraded without added nutrients. This indicated that nutrients were probably not a limiting factor in degradation. There was no concern that other nutrients such as phosphorus could have been limiting since glucose substrates showed significant degradation over the course of the studies for all soils tested.

While the nitrate levels increased in all effluents of nutrient enhanced columns, this was probably because of nitrification of some of the available ammonia. Since the ammonia levels of the nitrogen-enhanced columns eventually reached the approximate influent levels, extensive nitrification did not take place. This could have possibly been due to a lack of oxygen in the soil which would have inhibited nitrification. The soil columns were in a saturated or nearly saturated state for most of the study so they were quite possibly in an anaerobic or oxygen limited condition (1,2). This would explain the slightly elevated nitrate levels in the test columns over those for the control columns. Additionally, in the Warburg studies, oxygen was not a limiting factor since the soil:substrate mixture was constantly shaken to provide sufficient oxygen transfer.

Regardless of whether oxygen was a limiting factor in the column studies, the Warburg studies indicated TCE levels of 110 and 550 mg/l inhibited oxygen utilization even in acclimated soils. Since the effluent TCE concentrations during the column studies reached levels over 550 mg/l, it is probable that very little aerobic TCE degradation took place within the columns. However, as illustrated by the low chloride concentration in the effluents, very little anaerobic degradation could have occurred either, although no anaerobic studies were conducted to confirm this.

Consequently, biodegradation was not considered a major factor in the fate of TCE in this investigation.

Abiotic Degradation

As discussed previously in Biodegradation Studies, effluents from the nutrient enhanced columns generally contained higher chloride levels than effluents from the non-enhanced columns (Table 33). This higher level could have been due not only to biological degradation, but also to abiotic degradation.

In the Literature Review, photodegradation of TCE was discussed. This specific method of abiotic degradation was not accounted for but was considered with other abiotic degradation. Photodegradation of TCE was not considered to be enhanced by the presence of light in the column room for several reasons. First, the lights were on for only two to three hours/day. Secondly, less than half of the column soil surface area was directly exposed to the light since the support rack was mounted directly next to a wall. Consequently, photodegradation of TCE as a specific form of degradation was disregarded.

Two of the initial degradation products of TCE would be cis-1,2-dichlorethylene (cis-1,2-DCE) and trans-1,2-dichlorethylene (trans-1,2-DCE) (62). While these are not the only possible degradation products, these are the ones which would be readily apparent. To determine the possible presence of DCE in the column effluents, the

retention time of the compounds was determined for the GC column, operating conditions, and procedures for TCE headspace analysis discussed in Materials and Methods.

Solutions of cis-1,2-DCE and trans-1,2-DCE were made from reagent grade chemicals from Eastman Chemical Company that had been redistilled in an all glass distillation system. Based upon headspace analysis, the retention times were 1.22 minutes for trans-1,2-DCE and 1.97 minutes for cis-1,2-DCE. These retention times provided enough separation from the TCE peak of interest (2.2 minutes) so that even in the presence of 880 mg/l TCE, both the cis and trans isomers of DCE in prepared solutions could be detected to a minimum level of 2.0 mg/l. A review of the GC chromatograms indicated no peaks at the retention times for cis-and trans-1,2-DCE. This indicated these compounds were present at less than 2.0 mg/l throughout the column studies if they were present at all.

Removal of one chlorine from TCE would form one chloride ion plus either trans or cis-1,2-DCE. This reaction shows that for each 1.0 mg/l chloride ion formed from TCE, 2.7 mg/l DCE would be formed. The corrected mean chloride concentrations (Table 33) of the column effluents were generally greater than 1.0 mg/l. Since no DCE was indicated above the 2.0 mg/l detection level, abiotic degradation of TCE to DCE was minimal. If present, though, this degradation would have accounted for less than 1.0 mg/l

chloride in the column effluents. Consequently, biological degradation of TCE, rather than abiotic degradation, was the probable major cause of the additional chlorides found in the TCE test columns compared to the control columns.

TCE Mass Balance

The overall fate and disposition of TCE in the column studies included that which was eluted in the effluents, remained adsorbed on the columns, degraded (biologically and abiotically), and volatilized. Except for volatilization, these fates have been discussed but the total quantities of TCE associated with them have not been presented. This section quantifies the TCE associated with each of these fates and estimates the amount of TCE that volatilized.

TCE Eluted in Column Effluents

The incremental TCE elution was illustrated in Figures 30 and 31 from the data of Tables B16 and B17. Table 38 summarizes the TCE elution for each column group for both water application rates and corresponding final effluent volumes. As discussed previously, these data on elution volumes indicate there was no difference in elution based on flow rate.

TCE Remaining on Soil

The column elution studies were discontinued after 132 days. Soil samples from one column of each column group were then extracted according to procedures listed in

Table 38. TCE Eluted in Soil Column Effluents.

Column Group	Mass of TCE Applied ^a , g	Water Application Rate, ml/day	TCE Eluted in Effluent			
			CEV = 6.67 l ^b		CEV = 13.0 l	
			Mass, g	% ^c	Mass, g	%
C1-3	7.30	50	2.94	40.3	-	-
C4-6	7.30	100	3.10	42.5	4.84	66.3
C7-9	14.60	50	4.38	30.0	-	-
C10-12	14.60	100	4.32	29.6	9.34	64.0
R1-3	7.30	50	4.04	55.3	-	-
R4-6	7.30	100	3.99	54.7	5.66	77.5
R7-9	14.60	50	4.92	33.7	-	-
R10-12	14.60	100	5.08	34.8	10.47	72.5

Notes: ^aMass based on TCE specific gravity = 1.46.

^bCEV = Cumulative Effluent Volume.

^c% = % of TCE applied.

Materials and Methods. This extraction determined the mass of TCE that remained on the soil. Samples were taken from 2.5, 15, and 30 inch depths which closely corresponded to sampling depths used for the Warburg experiments. Table 39 presents results of the TCE analysis on the depth samples. For all corresponding column conditions, the Chalmers soil retained more TCE than did the Russell soil. This was expected since Table 38 and Figures 30 and 31 had indicated more TCE eluted from the Russell columns than from the Chalmers columns.

The TCE extracted from the soil also included that TCE in solution in the water present as soil moisture. To eliminate the moisture would have required drying the soil samples. This would have resulted in TCE volatilization losses from the soil. No attempt was made to account for this soil moisture TCE content since the liquid TCE concentration was not known at the exact point from which the samples were collected. In this way, the soil moisture TCE was included in the mass balance. Consequently, no attempt was made to differentiate between TCE adsorbed to the soil and TCE present in the soil moisture.

When all columns were disassembled, the base stopper assemblies were checked to determine the integrity of the aluminum foil liners. All liners were intact except for those on columns C4, C6, and R11, which were slightly torn. These tears could have allowed TCE to adsorb to the

stoppers; however, this was not anticipated to be significant since there was no major difference in effluent concentrations between these columns and others of the corresponding column groups tested.

Table 39 indicates the pattern of how TCE was eluted from the upper soil levels through the column by the water applied. Except for column C4, the upper soil layers retained more TCE than the lower soil layers. In all cases, the columns loaded with 10.0 ml TCE showed higher TCE soil concentrations than corresponding columns loaded with 5.0 ml TCE. This could possibly have been due to a higher adsorptive capacity at higher TCE loadings as indicated by the slight upturn of adsorption isotherms at higher TCE concentrations. Additionally, except for the 30 inch depth sample, all Chalmers soils retained more TCE than the corresponding samples of Russell soils. This was expected since the Chalmers soils showed a higher adsorptive capacity based on the batch isotherm studies.

Another indication of increased adsorptive capacity at high TCE loading was the comparison between actual and predicted capacity of the soil columns for TCE. Table 39 lists the calculated mass of TCE that remained on the columns after elution, while Table 40 lists the sum of TCE that was either eluted or retained. A comparison of these values with the predicted maximum adsorptive values, or X values, of Table 25, showed the columns were able to adsorb and retain more than that predicted by the isotherms.

Table 39. Concentration and Mass of TCE Remaining on Soil Columns after Elution.

Column	Depth of Sample			^a Calculated Mass of TCE on Column, g	
	2.5 Inches	15 Inches	30 Inches		
<u>Chalmers Soil</u>					
C1	mg/g ^b	0.663	0.346	0.114	1.94
	g	0.83	0.95	0.16	
C4	mg/g	0.142	0.180	0.086	0.79
	g	0.18	0.49	0.12	
C9	mg/g	1.70	1.23	0.261	5.85
	g	2.13	3.37	0.36	
C12	mg/g	0.490	0.281	0.163	1.61
	g	0.61	0.77	0.23	
<u>Russell Soil</u>					
R2	mg/g	0.327	0.265	0.156	1.42
	g	0.43	0.76	0.23	
R6	mg/g	0.106	0.080	0.074	0.48
	g	0.14	0.23	0.11	
R9	mg/g	1.29	0.81	0.178	4.96
	g	1.79	2.81	0.36	
R11	mg/g	0.227	0.205	0.109	1.05
	g	0.30	0.59	0.16	

Notes: ^aCalculated from sum of g's for column.

^bmg/g = mg TCE/g soil (dry weight basis).

^cg = Calculated mass, in grams, of TCE on segment of soil column as calculated in Appendix A.

TCE Degraded

Previous discussion indicated that the primary chemical degradation products of TCE (cis and trans-1,2-DCE) were not detected at the detection limit of 2.0 mg/l. Accordingly, for the purpose of the mass balance, the chlorides associated with the TCE laden columns are attributed to biological degradation. Consequently, to determine the amount of TCE attributed to degradation, the average of the corrected mean chloride concentrations of Table 33 were determined for the non-enhanced columns of each column group. As discussed in Biodegradation Studies, 1.0 mg of chloride represents complete dechlorination and degradation of 1.24 mg TCE. This factor was applied to the average corrected mean chloride concentration and total effluent volume for the appropriate column groups. It was used to determine the mass of TCE degraded as reported in Table 40.

Volatilization

Table 40 contains the mass balance as determined from the quantities of TCE associated with the previously discussed fates. The loss of TCE due to volatilization was attributed to that which could not be quantified by elution, soil retention, and degradation. While other factors such as glass and gravel adsorption could account for some loss of TCE, these factors were previously found to be

Table 40. TCE Mass Balance for Soil Columns Operated Continuously with Water Application for 132 Consecutive Days.

Column Group	Mass of TCE Associated with Fate				Eluted + Retained, g	
	Eluted	Retained	Degraded	^a Volatilized		
<u>Chalmers Soil</u>						
C1-3	g ^b	2.94	1.94	0.02	2.4	4.88
	% ^c	40.3	26.6	0.3	32.8	66.9
C4-6	g	4.84	0.79	0.02	1.65	5.63
	%	66.3	10.8	0.3	22.6	77.1
C7-9	g	4.38	5.85	0.01	4.36	10.23
	%	30.0	40.1	0.1	29.8	70.1
C10- 12	g	9.34	1.61	0.02	3.63	10.95
	%	64.0	11.0	0.2	24.8	75.0
<u>Russell Soil</u>						
R1-3	g	4.04	1.42	0.01	1.83	5.46
	%	55.3	19.5	0.2	25.0	74.8
R4-6	g	5.66	0.48	0.02	1.14	6.14
	%	77.5	6.6	0.3	15.6	84.1
R7-9	g	4.92	4.96	0.02	4.7	9.88
	%	33.7	34.0	0.2	32.1	62.7
R10- 12	g	10.47	1.05	0.02	3.06	11.52
	%	72.5	7.2	0.2	20.1	79.7

Notes: ^aVolatilization attributed to that not accounted for by other fates.

^bmass, in grams.

^c% of applied TCE.

^d Sum of mass of TCE which was eluted and retained on soil, grams.

negligible. Consequently, volatilization was determined to be the major fate of the unaccounted for TCE.

Summary

Elution was the major route by which TCE was removed from the columns for the 100 ml/day water application rates. Despite having a restricted headspace, calculated volatilization losses for the columns ranged from 15.6-32.8%. Volatilization of TCE from columns with water application rates of 100 ml/day was less than that from 50 ml/day columns. The reason for this difference was not investigated but it is possible the elution of TCE at 50 ml/day allowed the TCE to remain at the top of the soil column longer. This could have provided less of a barrier to volatilization than the 100 ml/day which translocated the TCE deeper into the soil column where volatilization would have been minimized.

Findings as Applied to an Actual Release to the Environment

This study has shown that high concentrations of TCE can be eluted through 33 inches of soil. However, during the course of this investigation, the equivalent rainfall applied was 0.43 inches/day (50 ml/day) and 0.86 inches/day (100 ml/day) for respective totals of 56.8 and 113.6 inches. These volumes are high for a 132 day period but do indicate the necessity for early discovery and remedial action at TCE release sites.

TCE was shown to be inhibitory to biological activity in unacclimated soil at levels down to at least 55 mg/l. Consequently, biodegradation as a means to restore early detected spill sites may not be feasible but may apply to dilute, aged, or "acclimated" spill sites.

If a release is detected immediately and the soil contains a high level of organic carbon, the TCE may be highly adsorbed and its movement retarded. In this case, consideration could be given to ways to increase the volatilization of TCE. One such method would be to plow or till the site to increase the surface area of soil exposed to the atmosphere. Depending upon weather conditions such as precipitation, temperature, and sunlight, the volatilization for a volatile compound such as TCE may be the major route of disappearance from the soil. Plowing or tilling to increase volatilization may also increase aerobic degradation and photodegradation.

SUMMARY

The fate of trichloroethylene in two different soils under conditions of a simulated spill or discharge was studied by continuous elution of soil columns with water for 132 consecutive days. The soils, Chalmers Silty Clay Loam and Russell Silt Loam, were common soils with similar particle size composition but different organic carbon contents. The Chalmers Silty Clay Loam had a composite organic carbon content of 1.4% while that of the Russell Silt Loam was 0.53%.

TCE was initially applied to the surface of each of twelve columns of each type soil. An additional column of each soil was used as a control. Triplicate columns of each soil were used for four different test conditions: (1) 5 ml TCE, 50 ml water/day; (2) 5 ml TCE, 100 ml water/day; (3) 10 ml TCE, 50 ml water/day; (4) 10 ml TCE, 100 ml water/day. Control columns had no TCE applied but were only eluted with 100 ml water/day. The equivalent rainfall for the water application rates was 0.43 inches/day (50 ml/day) and 0.86 inches/day (100 ml/day). Soil columns consisted of 33 inch long, three inch diameter soil cores extruded into

Pyrex glass tubing. Water was applied by intravenous sets which allowed for drop by drop feed. A minimal headspace was used to minimize volatilization of the TCE.

Equilibrium adsorption isotherms were determined for composite mixtures of each of the Chalmers and Russell soils for two different particle sizes, coarse (< 2 mm) and fine (< 0.150 mm). All adsorption isotherms were best described by the Freundlich theory with the following relationships: (1) Chalmers, fine: $X/M = 1.250C^{0.972}$; (2) Chalmers, coarse: $X/M = 0.813C^{0.949}$; (3) Russell, fine: $X/M = 0.826C^{0.910}$; (4) Russell, coarse: $X/M = 0.443C^{0.926}$ (X/M expressed in ug TCE adsorbed/g soil; C expressed as TCE equilibrium concentration in mg/l). These isotherms indicated the higher organic carbon content soil had the higher adsorptive capacity for TCE for both particle sizes tested. However, when normalized for the organic carbon content, the K_F indicated a dependence upon inorganic surface area adsorption.

TCE and soil adsorption equilibration time studies determined that adsorption equilibrium was reached within 15 hours for fine particle soil and within 20 hours for coarse particle soil. These studies were conducted for TCE concentrations of 220 and 880 mg/l for both soils. Glass and gravel adsorption studies indicated negligible adsorption. Based upon water application rates, the calculated residence

times of water within the columns (for both soils) were 30 days for 50 ml/day and 15 days for 100 ml/day. Soil column effluents were tested two to four times weekly for TCE concentration.

In all columns, TCE appeared in the effluent before one pore volume of water had been applied. This was believed to be due to both short-circuiting and TCE's specific gravity which is greater than that of water. The TCE concentrations in the effluents increased more rapidly for the low organic soil (Russell) than for the high organic soil (Chalmers) for both water application rates and TCE loadings used. The columns charged with 5 ml TCE showed a greater retardation of TCE through the column than did the columns charged with 10 ml TCE. This difference was less pronounced in the Russell soil than in the Chalmers soil.

Water application rates used in this study had no measurable effect on the elution of TCE from either type of soil or TCE loading studied. TCE concentration in the soil column effluents reached maximum values of 840-1,100 mg/l. TCE concentrations in Chalmers effluents were consistently lower than equivalent conditions for the Russell soil at the 5 ml TCE loading. For 10 ml TCE loadings, maximum concentrations for all columns rapidly reached and remained constant at approximately 1,100 mg/l, the maximum solubility of TCE. For this loading, the effluent TCE concentrations

from columns to which 100 ml/day of water was applied began to decrease after 5.3-5.9 pore volumes.

In only one column (Russell soil, 5 ml TCE, 50 ml water/day), was any free or undissolved TCE found in the effluent. Effluent from all other columns contained only TCE in solution as substantiated by dilution of samples before headspace analysis to quantify TCE. Comparison of actual TCE elution with theoretical TCE elution based upon TCE as a nonreactive substance indicated TCE was adsorbed and retarded in its movement through the soil. However, the continued water application eventually desorbed TCE with Russell soil showing greater TCE elution than the Chalmer's soil for similar conditions and total column effluent volume.

Column effluent pH was measured at approximately weekly intervals. For all columns, effluent pH was consistently greater than that of the water applied (pH 5.5-6.0). The mean pH for the columns ranged from 6.19-6.72. No difference in pH was noted for difference in soils, TCE loadings, or water application rates.

TCE biodegradation studies were conducted both in column elution and batch Warburg respirometric tests. To determine if nutrient addition would enhance biodegradation of TCE, water to one column of each column test group was supplemented with 10 mg/l ammonia nitrogen for days 75-100. During this period, measurement of effluent ammonia,

nitrate, chlorides, and TCE indicated no measurable enhancement of TCE degradation. Furthermore, nutrient addition showed no measurable depletion of ammonia nitrogen as evidenced by maximum effluent values of 8.0-12.0 mg/l of ammonia. Nitrate nitrogen levels in effluents of enhanced columns were approximately 0.5 mg/l higher than non-enhanced columns. Nitrite nitrogen was not detected in any of the column effluents.

Effluents from nutrient enhanced columns had mean chloride concentrations 2.0-6.0 mg/l higher than effluents from non-enhanced columns. This represented evidence of some form of degradation since degradation of TCE requires an initial dechlorination step that produces chloride ions. This increase in chloride concentration for the enhanced columns was not significant and the corresponding amount of TCE degradation it could represent was not measurably accounted for in the column effluents. Enhancement with ammonia was therefore discontinued due to its non-measurable effect on TCE degradation.

Concurrent with the column studies, aerobic biodegradation studies using Warburg respirometry were conducted. Initial respirometric studies used soil from a 2.5 inch depth of a Chalmers soil core which had not been used in column elution studies. TCE solutions ranging from 55-1,100 mg/l were used as test substrates with a glucose solution of

1,000 mg/l used as a biological activity indicator substrate. No oxygen uptake was measured for TCE while glucose showed evidence of oxygen uptake. All TCE solutions tested were inhibitory to biological activity as shown by oxygen uptakes that were less than control or endogenous uptakes. Further testing with acclimated soil showed oxygen uptake for TCE solutions of 55 mg/l but inhibition for 110 and 550 mg/l. Biological degradation of TCE was greater for both soils with samples at the 2.5 inch depth exhibiting greater degradation than samples from the 15 inch depth. Degradation was not demonstrated for either soil at the 31 inch depth. Biodegradation was not considered to have been inhibited by pH because the pH of the column effluents fell within the range for satisfactory biological growth.

As a measure of the validity of the Warburg test, the endogenous respiration and associated carbon dioxide productions were calculated for each soil and sample depth tested. Endogenous respiration rates ranged from 0.5-1.8 ul oxygen/g soil/hr with the corresponding carbon dioxide production of 24-83 ug carbon dioxide/g soil/day. These values compared favorably with the 5-50 ug carbon dioxide/g soil/day reported in the literature (1).

Abiotic degradation was evaluated by screening soil column effluents for cis-1,2-dichloroethylene and trans-1,

2-dichloroethylene. These compounds, the primary degradation products of TCE, were not detected in any of the column effluents at a minimum detection limit of 2 mg/l.

At the end of the column elution studies, soil samples, at various depths, were taken from one column of each column group. These samples were analyzed to determine the mass of TCE remaining on the soil. TCE soil concentrations were generally proportional to the organic carbon content of the sample depth. A comparison of the TCE remaining on the column with that predicted by the isotherms indicated the isotherms underestimated the TCE adsorptive capacity of the soil. Consequently, it was concluded that isotherms developed with aqueous solutions of TCE cannot accurately predict the adsorptive capacity and retardation of TCE applied to soil in a non-solution form.

Volatilization was calculated based upon the quantification of the fate of TCE from elution, degradation, and that remaining on the soil. The amount of TCE that eluted depended upon the total amount of water applied; however, elution was greater for the Russell soil than for the Chalmers soil at both TCE loadings and both water application rates. Degradation (both abiotic and biological) was calculated to have accounted for no more than 0.3% of the TCE applied to the columns. Volatilization, however, was calculated to account for 15.6-32.8% of the applied TCE despite the restrictive headspace used. Volatilization was

less from columns with water application rates of 100 ml/day than from those with 50 ml/day.

This research indicated that TCE spilled or discharged onto the soil in a non-solution form would neither be subject to immediate biological degradation nor would much degradation likely take place with time. Volatilization would be a likely route of major loss. The amount of TCE that would be eluted through the soil as a result of rainfall would not likely be affected by rainfall amounts. This was shown in these studies by the lack of effect of water application rates at equivalent rainfall rates of 0.43 and 0.86 inches/day.

CONCLUSIONS AND RECOMMENDATIONS

Conclusions

From the research studies on the disposition and fate of TCE when applied to soil columns, the following conclusions could be drawn:

1. Adsorption isotherms developed in batch studies followed a Freundlich relationship for the soils and TCE concentration ranges tested.

2. Adsorption of TCE from solution in batch studies increased as the particle size of the soil decreased.

3. Adsorption of TCE from solution in batch studies was greater for the soil with the higher fraction of organic carbon.

4. Adsorption of TCE from solution in batch studies was due to both the organic carbon content and inorganic surface areas as shown in K_{ocF} of the soils tested.

5. Adsorption equilibrium between the TCE solutions (220 and 880 mg/l) and soil particles in batch studies was attained within 15 hours by the fine particle size (<0.150 mm) and within 20 hours by the coarse particle size soil (<2 mm) for both soils tested.

6. Adsorption of TCE onto glass and gravel surfaces was negligible at the concentration levels tested.

7. Adsorption and desorption of TCE for the soil within the columns was demonstrated.

8. Adsorption isotherms developed from batch studies with composite soil samples underestimated maximum adsorptive capacity for TCE directly applied to the column.

9. TCE eluted more rapidly from the soil with the lower fraction of organic carbon.

10. Elution was not affected by the rate of water application used.

11. Biological degradation of TCE within the soil columns was not measurably enhanced by application of ammonia nitrogen.

12. Aerobic biological degradation of TCE by unacclimated soils was not possible at TCE concentrations of 55-1,100 mg/l.

13. Aerobic biological degradation of TCE by acclimated soils was inhibited by TCE concentrations of 110 mg/l and higher.

14. Biological degradation of TCE was higher at 2.5 inch depth than at 15 inch depth for both soils.

15. Nutrient enhancement of aerobic degradation did not alter the rate of degradation but did increase the percentage of TCE respired at 55 mg/l.

16. Abiotic degradation of TCE within the soil columns was insignificant.

17. Degradation accounted for 0.3% or less of the TCE in the column studies.

18. Volatilization was a significant route of loss for TCE in the soil column studies and was calculated to range from 15.6-32.8%.

Recommendations for Future Research

This research focused on one particular chemical, TCE, and two representative soils in assessing the fate of a spill. This research did show that TCE would be eluted through the soil; however, other chemicals and other soil conditions are worth investigating.

Additional research should be focused on the effects of ageing upon the desorptibility of an organic chemical from the soil. Varying the time of contact for a chemical upon the soil before elution is worth study.

Further studies should be conducted with cycles of water application followed by no water application to assess the effect of wetting/drying cycles upon the movement of TCE or other chemicals.

Volatilization was calculated to be a major route of loss in these investigations even though the columns contained a restrictive headspace. Comprehensive studies, tied in with wetting/drying cycles, could include actually capturing the volatilized chemical to quantify such losses.

Use of radiolabeled compounds would increase the ability to account for all forms of chemical fates.

Consideration should be given to bench scale or field tests wherein a quantity of chemical is applied to a soil, then the soil plowed or tilled to promote volatilization. Results could be quantified over time by actual extraction of soil samples.

LIST OF REFERENCES

LIST OF REFERENCES

1. Alexander, M., Introduction to Soil Microbiology. 2nd Edition, John Wiley and Sons, New York (1977).
2. Alrichs, J.L., "The Soil Environment." in Organic Chemicals in the Soil Environment: Vol. 1, ed. by C.A. Goring and J.W. Hamaker, Marcel Dekker, Inc., New York (1972).
3. American Public Health Association, American Water Works Association, Water Pollution Control Federation, Standard Methods for the Examination of Water and Wastewater. 15th Ed., (1981).
4. American Society of Testing and Materials, 1982 Annual Book of ASTM Standards. Part 19: ASTM D 854-58, Philadelphia (1982).
5. Baselt, R.C., Biological Monitoring Methods for Industrial Chemicals. Biomedical Publications, New York (1980).
6. Bear, J., Hydraulics of Groundwater. McGraw-Hill, Inc., New York (1979).
7. Black, C.A., Methods of Soil Analysis: Part 1. American Society of Agronomy, Madison, Wisconsin (1965).
8. Bohn, H.L., et al., Soil Chemistry. John Wiley and Sons, New York (1979).
9. Bower, E.J., et al., "Anaerobic Degradation of Halogenated 1 and 2 Carbon Organic Compounds." Environ. Sci Tech. 15, 596 (1981).
10. Bower, E.J., et al., "Trace Organic Behavior in Soil Columns During Rapid Infiltration of Secondary Wastewater." Water Res., 15, 151 (1981).
11. Bower, H., Groundwater Hydrology. McGraw-Hill, Inc., New York (1978).

12. Brass, H.J., "Procedures for Analyzing Organic Contaminants in Drinking Water". J Am Water Works Assoc, 74, 107 (1982).
13. Carlson, G.P., "Enhancement of the Hepatotoxicity of Trichloroethylene by Inducers of Drug Metabolism." Res Comm Chem Pathol Pharmacol, 7, 637 (1974).
14. Castello, G., et al., "Gas Chromatographic Analysis of Halocarbons in Drinking Water by Headspace Extraction and Mixed Column Separation." J Chromatogr, 247, 263 (1982).
15. Clayton, G.D., and F.E. Clayton, editors, Patty's Industrial Hygiene and Toxicology: Vol 2B, Toxicology. 3rd Edition, John Wiley and Sons, New York (1981).
16. DeLeon, I.R., et al., "Rapid Gas Chromatographic Method for the Determination of Volatile and Semivolatile Organochlorine Compounds in Soil and Chemical Waste Disposal Site Samples." Chromat Science, 18, 83 (1980).
17. DeWalle, F.B., and E.S.K. Chian, "Detection of Trace Organics in Well Water Near a Solid Waste Landfill." J Am Water Works Assoc, 73, 206 (1981).
18. Dietz, E.A., and K.F. Singley, "Determination of Chlorinated Hydrocarbons in Water by Headspace Gas Chromatography." Anal Chem, 51, 1809 (1979).
19. Dilling, W.L., et al., "Evaporation Rates and Reactivities of Methylene Chloride, Chloroform, 1,1,1-Trichloroethane, Trichloroethylene, Tetrachloroethylene, and Other Chlorinated Compounds in Dilute Aqueous Solutions." Environ Sci Techn, 9, 833 (1975).
20. Dyksen, J.E., and A. F. Hess, "Alternatives for Controlling Organics in Groundwater Supplies." J Am Water Works Assoc, 74, 394 (1982).
21. Editorial Staff, "Organic Contaminants in Groundwater." J Am Water Works Assoc, 74, 381 (1982).
22. Emig, D.K., "Removal of Heavy Metals From Acid Bath Plating Wastes by Soil." Ph.D. Thesis, School of Civil Engineering, Purdue University (1973).
23. Felsot, A. and P.A. Dahm, "Sorption of Organophosphorous and Carbamate Insecticides by Soil." J Agric Food Chem, 27, 557 (1979).

13. Carlson, G.P., "Enhancement of the Hepatotoxicity of Trichloroethylene by Inducers of Drug Metabolism." Res Comm Chem Pathol Pharmacol, 7, 637 (1974).
14. Castello, G., et al., "Gas Chromatographic Analysis of Halocarbons in Drinking Water by Headspace Extraction and Mixed Column Separation." J Chromatogr, 247, 263 (1982).
15. Clayton, G.D., and F.E. Clayton, editors, Patty's Industrial Hygiene and Toxicology: Vol 2B, Toxicology. 3rd Edition, John Wiley and Sons, New York (1981).
16. DeLeon, I.R., et al., "Rapid Gas Chromatographic Method for the Determination of Volatile and Semivolatile Organochlorine Compounds in Soil and Chemical Waste Disposal Site Samples." Chromat Science, 18, 83 (1980).
17. DeWalle, F.B., and E.S.K. Chian, "Detection of Trace Organics in Well Water Near a Solid Waste Landfill." J Am Water Works Assoc, 73, 206 (1981).
18. Dietz, E.A., and K.F. Singley, "Determination of Chlorinated Hydrocarbons in Water by Headspace Gas Chromatography." Anal Chem, 51, 1809 (1979).
19. Dilling, W.L., et al., "Evaporation Rates and Reactivities of Methylene Chloride, Chloroform, 1,1,1-Trichloroethane, Trichloroethylene, Tetrachloroethylene, and Other Chlorinated Compounds in Dilute Aqueous Solutions." Environ Sci Techn, 9, 833 (1975).
20. Dyksen, J.E., and A. F. Hess, "Alternatives for Controlling Organics in Groundwater Supplies." J Am Water Works Assoc, 74, 394 (1982).
21. Editorial Staff, "Organic Contaminants in Groundwater." J Am Water Works Assoc, 74, 381 (1982).
22. Emig, D.K., "Removal of Heavy Metals From Acid Bath Plating Wastes by Soil." Ph.D. Thesis, School of Civil Engineering, Purdue University (1973).
23. Felsot, A. and P.A. Dahm, "Sorption of Organophosphorous and Carbamate Insecticides by Soil." J Agric Food Chem, 27, 557 (1979).

24. Freeze, R.A., and J.A. Cherry, Groundwater. Prentice-Hall, Inc., Englewood Cliffs, New Jersey (1979).
25. Glaser, J.A., et.al., "Trace Analysis for Wastewaters." Environ Sci Techn, 15, 1426 (1981).
26. Goldman, P., "Enzymology of Carbon-Halogen Bonds." in Degradation of Synthetic Organic Molecules in the Biosphere, National Academy of Sciences, Washington, D.C. (1972).
27. Goring, C.A.I., et al., "Principles of Pesticide Degradation in Soil." in Environmental Dynamics of Pesticides, ed. by R. Hague and V.H. Freed, Plenum Press, New York (1974).
28. Hamaker, J.W. and J.M. Thompson, "Adsorption." in Organic Chemicals in the Soil Environment: Vol 1. ed. by C.A. Goring and J.W. Hamaker, Marcel Deker, Inc., New York (1972).
29. Hamaker, J.W., "Decomposition: Quantitative Aspects." in Organic Chemicals in the Soil Environment: Vol 1. ed. by C.A. Goring and H.W. Hamaker, Marcel Deker, Inc., New York (1972).
30. Hamaker, J.W., "The Interpretation of Soil Leaching Experiments." in Environmental Dynamics of Pesticides. ed. by R. Hague and V.H. Freed, Plenum Press, New York (1974).
31. Hedly, W.H., et al., Potential Pollutants from Petrochemical Processes. Monsanto Research Corp. (1975).
32. Henderson, J.E., et al., "A Convenient Liquid-Liquid Extraction Method for the Determination of Halomethanes in Water at the Parts Per Billion Level." in Identification and Analysis of Organic Pollutants In Water, ed. b L.H. Keith, Ann Arbor Science Publishers, Inc. (1976).
33. Houle, M.J. and D.E. Long, "Accelerated Testing of Waste Leachability and Contaminant Movement in Soils." Land Disposal of Hazardous Wastes: Proceedings of the 4th Annual Research Symposium, U.S. EPA, EPA-600/9-78-016 (1978).
34. Jensen, S. and R. Rosenberg, "Degradability of Some Chlorinated Aliphatic Hydrocarbons in Seawater and Sterilized Water." Water Res, 9, 659 (1975).

35. Josephson, J., "Protecting Public Groundwater Supplies." Environ Sci Techn, 16, 502 (1982).
36. Josephson, J., "Safeguards for Groundwater." Environ Sci Tech, 14, 38 (1980).
37. Josephson, J., "Water Research Needs and Trends." Environ Sci Techn, 17, 69 (1983).
38. Karickhoff, S.W., et al., "Sorption of Hydrophobic Pollutants on Natural Sediments." Water Res, 13, 241 (1979).
39. Karickhoff, S.W., "Semi Empirical Estimation of Sorption of Hydrophobic Pollutants on Natural Sediments and Soils." Chemosphere 10, 833 (1981).
40. Kaufman, D.D. et al., "Movement of Cypermethrin, Decamethrin, Permethrin, and Their Degradation Products in Soil." J Agric Food Chem, 29, 239 (1981).
41. Keith, L.H., and W.A. Telliard, "Priority Pollutants I - A Perspective View." Environ Sci Techn, 18, 416 (1979).
42. Keith, L.H., "Organic Pollutants in Water: Identification and Analysis." Environ Sci Techn, 15, 156 (1981).
43. Kelly, W.D., editor, Annals of the American Conference of Governmental Industrial Hygienists - Vol 4, ACGIH Transactions - 1982. Cincinnati, Ohio (1983).
44. Kepner, R.E., "Gas Chromatographic Head Space Techniques for the Quantitative Determination of Volatile Components in Multicomponent Aqueous Solutions." Anal Chem, 36, 77 (1964).
45. Kirk, R.E., and D.F. Othmer, editors, Encyclopedia of Chemical Technology, Interscience Publishers, Inc. (1960).
46. Kobayashi, H. and B.E. Rittman, "Microbial Removal of Hazardous Organic Compounds." Environ Sci Techn, 16, 170 (1982).
47. Koskinen, W.C., "Characterization of Hysteresis in the Desorption of 2,4,5,-T from Soils." Soil Sci Soc Am J, 43, 871 (1979).

48. Kraybill, H.F., "Carcinogenesis of Synthetic Organic Chemicals in Drinking Water." J Am Water Works Assoc, 73, 370 (1981).
49. "Leather Tanner Indicted Under RCRA." Chem Eng News, 61, 13 (1983).
50. Lee, M.C. et al., "Adsorption of Water-Soluble Polychlorinated Biphenyl Arochlor 1242 and Used Capacitor Fluid by Soil Materials and Coal Chars." J Environ Sci Health, 14, 415 (1979)
51. Love, O.T. and R.G. Eilers, "Treatment of Drinking Water Containing Trichlorethylene and Related Industrial Solvents." J Am Water Works Assoc, 74, 413 (1982).
52. Mackay, D. and A.W. Wolkoff, "Rate of Evaporation of Low Solubility Contaminants from Water Bodies to Atmosphere." Environ Sci Techn, 7, 611 (1973).
53. Macmullin, R.B. and M. Weber, Jr., "The Theory of Short-Circuiting in Continuous-Flow Mixing Vessels in Series and the Kinetics of Chemical Reactions in Such Systems." Paper presented at the American Institute of Chemical Engineers Meeting, Wilmington, Delaware, May 13-15, 1935.
54. Marinucci, A.C. and R. Bartha, "Biodegradation of 1,2,3-and 1,2,4 Trichlorobenzene in Soil and Liquid Enrichment Culture." Appl Environ Microbiol, 38, 811 (1979).
55. Means, J.C., et al., "Sorption of Polynuclear Aromatics by Sediments and Soils." Environ Sci Techn, 14, 1524 (1980).
56. Means, J.C., "Sorption Properties of Energy Related Pollutants and Sediments." in Polynuclear Aromatic Hydrocarbons, ed. by P.E. Jones and P. Leber, Ann Arbor Science Publishers, Inc. (1979).
57. McCarty, P.L., et al., "Trace Organics in Groundwater." Environ Sci Techn, 15, 40 (1981).
58. Mieure, J.P., "Survey of Procedures for Determining Volatile Organics in Water." in Chemistry in Water Reuse: Vol. 2, ed. by W.J. Cooper, Ann Arbor Science Publishers, Inc. (1981).

59. "Most Dangerous U.S. Waste Dumps Identified." Chem Eng News, 61, 8 (1983).
60. National Academy of Sciences, Safe Drinking Water Committee, Drinking Water and Health. National Academy Press, Washington, D.C. (1977).
61. National Academy of Sciences, Safe Drinking Water Committee, Drinking Water and Health, Vol. 3. National Academy Press, Washington, D.C. (1980).
62. Parsons, F., et al., "Transformation of Chlorinated Organic Solvents in Groundwater Environments of Southern Florida." Preprint Extended Abstract, Division of Environmental Chemistry, American Chemical Society, Washington, D.C., Sept, 1983.
63. Petura, J.C., "Trichlorethylene and Methyl Chloroform in Groundwater: A Problem Assessment." J Am Water Works, Assoc, 73, 200 (1981).
64. Purdue University Department of Agronomy, "Soil Characterization in Indiana: I. Field and Laboratory Procedures." Research Bulletin No. 943 (1977).
65. Rao, P.S.C. and J.M. Davidson, "Adsorption and Movement of Selected Pesticides at High Concentrations in Soils." Water Res, 13, 375 (1979).
66. Rao, P.S.C., et al., "Evaluation of Conceptual Models for Describing Nonequilibrium Adsorption-Desorption of Pesticides During Steady Flow in Soils." Soil Sci Soc Am J, 43, 22 (1979).
67. Raymond, R.L., et al., "Oil Degradation in Soil." Appl Environ Microbiol, 31, 522 (1976).
68. Renberg, L., "Determination of Volatile Halogenated Hydrocarbons in Water with XAD-4 Resin." Anal Chem, 50, 1836 (1978).
69. Richard, J.J. and G.A. Junk, "Liquid Extraction for Rapid Determination of Halomethanes in Water." J Am Waterworks Assoc, 69, 62 (1977).
70. Richter, R.O., "Adsorption of Trichloroethylene by Soils from Dilute Aqueous Solutions." 1981 USAF-SCEEE Summer Faculty Research Program Final Report, Aug 24, 1981.

71. Rittman, B.E., et al., "Trace Organics Biodegradation in Aquifer Recharge." Groundwater, 18, 236 (1980).
72. Roberts, P.V., et al., "Organic Contaminant Behavior During Groundwater Recharge." J Water Pollut Control Fed, 52, 161 (1980).
73. Roberts, P.V., et al., "Field Study of Organic Water Quality Changes During Groundwater Recharge in the Palo Alto Baylands." Water Res, 16, 1025 (1982).
74. Roberts, P.V., et al., "Movement of Organic Contaminants in Groundwater: Implications for Water Supply." J Am Water Works Assoc, 74, 408 (1982).
75. Rogers, R.D., et al., "Adsorption and Desorption of Benzene in Two Soils and Montmorillonite Clay." Environ Sci Techn, 14, 457 (1980).
76. Sax, N.I., Dangerous Properties of Industrial Materials. 5th Ed., Van Nostrand Reinhold Co, New York (1979).
77. Schwarzenbach, R.P., and J. Westall, "Transport of Nonpolar Organic Compounds from Surface Water to Groundwater: Laboratory Sorption Studies." Environ - Sci Techn, 15, 1360 (1981).
78. Seltzer, R.J., "Reactions Grow to Trichloroethylene Alert." Chem Eng News, 53, 41 (1975).
79. Sharom, M.S., et al., "Behavior of 12 Insecticides in Soil and Aqueous Suspensions of Soil and Sediment." Water Res, 14, 1095 (1980).
80. SRI International, 1982 Directory of Chemical Producers, United States of America, Menlo Park, California (1982).
81. Symons, J.M. et al., "National Organics Reconnaissance Survey for Halogenated Organics." J Am Water Works Assoc, 67, 634 (1975).
82. Tabak, H.H., et al., "Biodegradability Studies With Organic Priority Pollutant Compounds." J Water Pollut Control Fed, 53, 1503 (1981).
83. Tomson, M.B., et al., "Groundwater Contamination By Trace Level Organics from a Rapid Infiltration Site." Water Res, 15, 1109 (1981).

84. Trussell, A.R., and M.D. Umphres, "An Overview of the Analysis of Trace Organics in Water." J Am Water Works Assoc, 70, 595 (1978).
85. Umbreit, W.W. et al., Manometric Techniques. 4th Edition, Burgess Publishing Co., Minneapolis (1964).
86. U.S. Department of Agriculture and Purdue University Agricultural Experiment Station, Soil Survey, Tippecanoe County, Indiana. Series 1940, No. 22 (1959).
87. U.S. Dept of Health, Education, and Welfare, "Criteria for a Recommended Standard: Occupational Exposure to Trichloroethylene." (1973).
88. U.S. Environmental Protection Agency, "Ambient Water Quality Criteria for Trichloroethylene." EPA-440/5-80-077 (1980).
89. U.S. Environmental Protection Agency, "Designation of Hazardous Substances." 43 FR 10474, Mar 13, 1978.
90. U.S. Environmental Protection Agency, "Guidelines Establishing Test Procedures for the Analysis of Pollutants." 44 FR 68666, Nov 29, 1979.
91. U.S. Environmental Protection Agency, "Occupational Exposure to Trichloroethylene." 40 FR 49031, Oct 20, 1975.
92. U.S. Environmental Protection Agency, "National Revised Primary Drinking Water Regulations, Volatile Synthetic Organic Chemicals in Drinking Water." 478 FR 9350, Mar 4, 1982.
93. Vernon, R.J., and R.K. Ferguson, "Effects of TCE on Visual Motor Performance." Arch Env Hlth, 18, 84 (1969).
94. Versar, Inc., Water Related Fate of 129 Priority Pollutants: IV. Halogenated Aliphatics. U.S. EPA, Washington, D.C. (1979).
95. Wahid, P.A. and N. Sethunathan, "Sorption-Desorption of Alpha, Beta, and Gamma Isomers of Hexachlorocyclohexane in Soils." J Agric Food Chem, 27, 1050 (1979).
96. Warner, P.H., et al., "Determination of Henry's Law Constants of Selected Priority Pollutants." U.S. EPA Office of Research and Development, Cincinnati (1980).

97. Waters, E.M., Trichloroethylene: I. An Impact Overview. Oak Ridge National Laboratory, ORNL/TIRC-76/2, (May 1976).
98. Weber, W.J. and J.C. Morris, "Kinetics of Adsorption on Carbon from Solution." J Sanit Eng Div, Am Soc Civ Eng, 89, 31 (1963).
99. Weber, W.J., Physiochemical Processes for Water Quality Control. Wiley-Interscience, New York (1972).
100. Wentick, G.R., "The Exchange of Metal Ions in Soil." M.S. Thesis, School of Civil Engineering, Purdue University (1968).
101. Wilson, J.T., et al., "Biotransformation of Selected Organic Pollutants In Groundwater." Paper presented at the Symposium on Groundwater Microbiology, Annual Meeting of the Society for Industrial Microbiology, St. Paul, Minnesota, Aug 1982.
102. Wilson, J.T., et al., "Biodegradation of Contaminants in the Subsurface." "Proceedings of the First International Conference on Groundwater Quality Research, Oct 7-10, 1981, Rice University, Houston, Texas.
103. Windholz, M., editor, The Merck Index. 9th Edition, Merck and Co., Inc. (1976).

APPENDICES

Appendix A. Sample Calculations.

Sample Calculations

1. Porosity, n (unitless) (11).

$$n = 1 - \frac{BD}{\rho}$$

where BD = Bulk Density, g/cm^3
 ρ = Density of soil solids, g/cm^3

2. Bulk Volume, BV (cm^3)

$$BV = H \times A$$

where H = Height of soil layer, cm
 A = Area of horizontal layer, cm^2
 $(A = 45.6 \text{ cm}^2 \text{ for } 3 \text{ inch diameter})$

3. Pore Volume, PV (cm^3).

$$PV = n \times BV$$

4. Soil Mass, SM (g).

$$SM = BD \times BV$$

5. Organic Carbon Mass, OCM (g).

$$OCM = SM \times f_{OC}$$

where f_{OC} = fraction of organic carbon
 $= \frac{\% \text{ organic carbon}}{100}$

6. Total Bulk Density of Column, TBD (g/cm^3).

$$TBD = \frac{SM \text{ (Total)}}{BV \text{ (Total)}}$$

7. Calculated Porosity of Column, nc (unitless).

$$nc = \frac{\text{Total Pore Volume}}{\text{Total Bulk Volume}}$$

8. Total % Organic Carbon, TPOC, %.

$$\text{TPOC} = \frac{\text{Total OCM}}{\text{Total SM}} \times 100$$

9. Mass of TCE remaining on soil after elution, g (grams).

$$g = (X/M)_e \times M_s$$

where $(X/M)_e$ = mg TCE/g soil (dry weight basis)
determine from extraction

M_s = Calculated mass of soil segment
representative of extracted sample as
indicated below:

Depth of Sample, in	Depth of Column Segment, in.	Ms, g	
		Chalmers	Russell
2.5	0 - 8.25	1251.5	1312.5
15.0	8.25 - 24.75	2746	2864
30.0	24.75 - 33.00	1403	1482.5

10. Calculated average soil water velocity, u (77).

$$u = \frac{QL}{PV}$$

where Q = Water application rate
L = Length of soil column
PV = Pore Volume

11. Cumulative TCE eluted based upon CSTR (53).

$$\% \text{ eluted} = (1 - e^{-\frac{CEV}{PV}}) \times 100\%$$


where CEV = Cumulative Effluent Volume
PV = Pore Volume of Soil
Results listed in Table B18.

12. Theoretical COD of TCE.



$$\text{COD} = \frac{(4.5 \text{ mole O}_2) (32 \text{ g/mole})}{(2 \text{ mole TCE}) (131.4 \text{ g/mole})} = \frac{0.54 \text{ mg O}_2}{\text{mg TCE}}$$

13. Theoretical COD of Glucose.



$$\text{COD} = \frac{(6 \text{ mole O}_2) (32 \text{ g/mole})}{(1 \text{ mole glucose}) (180 \text{ g/mole})} = \frac{1.06 \text{ mg O}_2}{\text{mg glucose}}$$

Appendix B. Tabulated Data from Soil Column Studies.

Table B1. Cross Reference of Column Study
Day With Calendar Date.

Day	Date	Day	Date	Day	Date	Day	Date
A	4/3	(TCE Applied) All dates are for 1983.					
0	4/4	(Water Application Begun)					
1	4/5	36	5/10	71	6/14	106	7/19
2	4/6	37	5/11	72	6/15	107	7/20
3	4/7	38	5/12	73	6/16	108	7/21
4	4/8	39	5/13	74	6/17	109	7/22
5	4/9	40	5/14	75	6/18	110	7/23
6	4/10	41	5/15	76	6/19	111	7/24
7	4/11	42	5/16	77	6/20	112	7/25
8	4/12	43	5/17	78	6/21	113	7/26
9	4/13	44	5/18	79	6/22	114	7/27
10	4/14	45	5/19	80	6/23	115	7/28
11	4/15	46	5/20	81	6/24	116	7/29
12	4/16	47	5/21	82	6/25	117	7/30
13	4/17	48	5/22	83	6/26	118	7/31
14	4/18	49	5/23	84	6/27	119	8/1
15	4/19	50	5/24	85	6/28	120	8/2
16	4/20	51	5/25	86	6/29	121	8/3
17	4/21	52	5/26	87	6/30	122	8/4
18	4/22	53	5/27	88	7/1	123	8/5
19	4/23	54	5/28	89	7/2	124	8/6
20	4/24	55	5/29	90	7/3	125	8/7
21	4/25	56	5/30	91	7/4	126	8/8
22	4/26	57	5/31	92	7/5	127	8/9
23	4/27	58	6/1	93	7/6	128	8/10
24	4/28	59	6/2	94	7/7	129	8/11
25	4/29	60	6/3	95	7/8	130	8/12
26	4/30	61	6/4	96	7/9	131	8/13
27	5/1	62	6/5	97	7/10	132	8/14
28	5/2	63	6/6	98	7/11		
29	5/3	64	6/7	99	7/12		
30	5/4	65	6/8	100	7/13		
31	5/5	66	6/9	101	7/14		
32	5/6	67	6/10	102	7/15		
33	5/7	68	6/11	103	7/16		
34	5/8	69	6/12	104	7/17		
35	5/9	70	6/13	105	7/18		

Table B2. Daily Data for Columns C1, C2, and C3.

Col. Day	C1				C2				C3			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
1	0	0	0.00	-	0	0	0.00	-	0	0	0.00	-
2	42	42	0.02	-	0	0	0.00	-	65	65	0.04	-
3	69	111	0.06	ND	123	123	0.07	ND	60	125	0.07	ND
4	35	146	0.08	-	72	195	0.11	ND	41	166	0.10	-
5	71	217	0.13	ND	36	231	0.14	-	57	223	0.13	-
6	65	282	0.16	-	72	303	0.18	0.039	60	283	0.16	-
7	40	322	0.19	-	65	368	0.22	-	65	348	0.21	0.147
8	62	384	0.22	0.084	66	434	0.25	-	35	383	0.22	-
9	39	423	0.25	-	57	491	0.32	0.326	59	442	0.26	-
10	69	492	0.29	-	60	551	0.35	-	73	515	0.30	0.870
11	79	571	0.33	0.291	48	599	0.39	-	38	543	0.32	-
12	73	644	0.38	-	66	665	0.43	0.542	46	589	0.34	-
13	56	700	0.41	3.4	77	742	0.45	1.2	63	652	0.38	-
14	57	757	0.44	-	33	775	0.49	-	68	720	0.42	-
15	50	807	0.47	8.1	70	845	0.52	6.4	81	801	0.47	4.3
16	37	844	0.49	-	41	886	0.54	-	28	829	0.48	-

Table B2. Continued.

Col.	C1					C2					C3				
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l			
Day															
17	64	908	0.53	-	39	925	0.54	-	36	865	0.51	-			
18	77	985	0.58	39	53	978	0.57	22	67	932	0.54	1.7			
19	44	1029	0.60	-	30	1008	0.59	-	47	979	0.57	-			
20	59	1088	0.64	61	50	1058	0.62	37	70	1049	0.61	7.3			
21	52	1140	0.67	-	42	1100	0.64	-	17	1066	0.62	-			
22	66	1206	0.70	103	58	1158	0.68	72	73	1139	0.67	12			
23	31	1237	0.72	-	67	1225	0.72	-	39	1178	0.69	-			
24	50	1287	0.75	52	63	1288	0.75	132	54	1232	0.72	16			
25	67	1354	0.79	-	60	1348	0.79	-	67	1299	0.76	-			
26	62	1416	0.83	83	76	1424	0.83	194	56	1355	0.79	22			
27	40	1456	0.85	-	59	1483	0.87	-	59	1414	0.83	-			
28	56	1512	0.88	112	73	1556	0.91	188	50	1464	0.86	34			
29	41	1553	0.91	-	36	1592	0.93	-	44	1508	0.88	-			
30	67	1620	0.95	126	50	1642	0.96	238	64	1572	0.92	63			
31	49	1669	0.98	-	70	1712	1.00	-	73	1645	0.96	-			
32	55	1724	1.01	137	66	1778	1.04	263	81	1726	1.01	94			

Table B2. Continued.

Col. Day	C1				C2				C3			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
33	34	1758	1.03	-	44	1822	1.06	-	40	1766	1.03	-
34	69	1827	1.07	148	72	1894	1.11	321	63	1829	1.07	182
35	37	1864	1.09	-	58	1952	1.14	-	69	1898	1.11	-
36	32	1896	1.11	-	61	2013	1.18	-	54	1952	1.14	-
37	53	1949	1.14	206	57	2070	1.21	352	63	2015	1.18	294
38	48	1997	1.17	-	59	2129	1.24	-	58	2073	1.21	-
39	50	2047	1.20	223	56	2185	1.28	-	47	2120	1.24	-
40	53	2100	1.23	-	63	2748	1.32	-	44	2164	1.26	-
41	47	2147	1.26	239	55	2303	1.35	358	48	2212	1.29	314
42	43	2190	1.28	-	42	2345	1.37	-	56	2268	1.32	-
43	38	2228	1.30	276	31	2376	1.39	337	47	2315	1.35	287
44	61	2289	1.34	-	29	2405	1.41	-	50	2365	1.38	-
45	55	2344	1.37	409	36	2441	1.43	-	45	2410	1.41	298
46	56	2400	1.40	-	48	2489	1.46	-	38	2448	1.43	-
47	51	2451	1.43	448	43	2532	1.48	361	55	2503	1.46	318
48	43	2494	1.46	-	51	2583	1.51	-	62	2565	1.50	-

Table B2. Continued.

Col.	C1				C2				C3			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
49	46	2540	1.48	-	63	2646	1.55	-	66	2631	1.54	332
50	59	2599	1.52	-	64	2710	1.58	-	63	2694	1.58	-
51	67	2666	1.56	507	66	2776	1.62	390	66	2760	1.61	413
52	63	2729	1.60	-	68	2844	1.66	-	62	2822	1.65	-
53	61	2790	1.63	547	58	2902	1.70	472	58	2880	1.68	-
54	56	2846	1.66	-	56	2958	1.73	-	55	2935	1.72	-
55	47	2893	1.69	-	59	3017	1.76	483	47	2982	1.74	426
56	52	2945	1.72	-	54	3071	1.80	-	43	3025	1.77	-
57	54	2999	1.75	614	59	3130	1.83	522	46	3071	1.80	437
58	58	3057	1.79	-	61	3191	1.87	-	40	3111	1.82	-
59	60	3117	1.82	632	57	3248	1.90	553	37	3148	1.84	486
60	57	3174	1.86	-	53	3301	1.93	-	46	3194	1.87	-
61	53	3227	1.89	658	48	3349	1.96	582	52	3246	1.90	532
62	47	3274	1.91	-	43	3392	1.98	-	45	3291	1.92	-
63	45	3319	1.94	642	46	3438	2.01	623	44	3335	1.95	540
64	49	3368	1.97	-	50	3488	2.04	-	49	3384	1.98	-

Table B2. Continued.

Col.	C1				C2				C3			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
Day												
65	53	3421	2.00	-	52	3540	2.07	-	58	3442	2.01	-
66	56	3477	2.03	-	46	3586	2.10	-	53	3495	2.04	-
67	58	3535	2.07	693	44	3630	2.12	614	54	3549	2.08	741
68	61	3596	2.10	-	48	3678	2.15	-	50	3599	2.10	-
69	55	3651	2.14	783	45	3723	2.18	681	46	3645	2.13	729
70	51	3702	2.16	-	43	3766	2.20	-	47	3692	2.16	-
71	46	3748	2.19	762	47	3813	2.23	704	51	3743	2.19	806
72	54	3802	2.22	-	52	3865	2.26	-	48	3791	2.22	-
73	56	3858	2.26	812	54	3919	2.29	727	54	3845	2.25	742
74	52	3910	2.29	-	57	3976	2.33	-	53	3898	2.28	-
75	48	3958	2.31	-	51	4027	2.35	761	49	3947	2.31	801
76	45	4003	2.34	-	55	4082	2.39	-	50	3997	2.34	-
77	47	4050	2.37	862	52	4134	2.42	-	52	4049	2.37	823
78	46	4096	2.40	-	46	4180	2.44	-	55	4104	2.40	-
79	49	4145	2.42	837	43	4223	2.47	813	50	4154	2.43	774
80	53	4198	2.45	-	41	4264	2.49	-	48	4202	2.40	-

Table B2. Continued.

Col. Day	C1				C2				C3			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
81	50	4240	2.48	-	49	4313	2.52	834	52	4254	2.49	-
82	46	4294	2.51	-	52	4365	2.55	-	53	4307	2.52	-
83	53	4347	2.54	853	51	4416	2.58	783	56	4363	2.55	833
84	51	4398	2.57	-	53	4469	2.61	-	52	4415	2.58	-
85	45	4443	2.60	879	49	4518	2.64	-	48	4463	2.61	845
86	47	4500	2.63	-	46	4564	2.67	-	46	4509	2.64	-
87	45	4545	2.66	899	49	4613	2.70	822	49	4558	2.67	878
88	51	4596	2.69	-	50	4663	2.73	-	52	4610	2.70	-
89	54	4650	2.72	828	54	4717	2.76	820	51	4661	2.73	822
90	56	4706	2.75	-	52	4769	2.79	-	53	4714	2.76	-
91	52	4758	2.78	-	52	4821	2.82	828	48	4762	2.78	-
92	54	4812	2.81	-	48	4869	2.85	-	42	4804	2.81	-
93	46	4858	2.84	774	46	4915	2.87	798	57	4861	2.84	763
94	47	4905	2.87	-	47	4962	2.90	-	51	4912	2.87	-
95	45	4950	2.89	786	52	5014	2.93	-	54	4966	2.90	817
96	47	4997	2.92	-	53	5067	2.96	-	46	5012	2.93	-

Table B2. Continued.

Col.	C1				C2				C3			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
97	53	5050	2.95	792	46	5113	2.99	753	47	5059	2.96	809
98	53	5103	2.98	-	48	5161	3.02	-	48	5107	2.99	-
99	46	5149	3.01	764	51	5212	3.05	685	53	5160	3.02	794
100	50	5199	3.04	-	55	5267	3.08	-	50	5210	3.05	-
101	52	5251	3.07	753	53	5320	3.11	607	47	5257	3.07	762
102	49	5300	3.10	-	47	5367	3.14	-	49	5306	3.10	-
103	48	5348	3.13	728	49	5416	3.17	612	52	5358	3.13	-
104	47	5395	3.15	-	48	5464	3.20	-	51	5409	3.16	-
105	46	5441	3.18	621	55	5519	3.23	571	53	5462	3.19	731
106	49	5490	3.21	-	53	5572	3.26	-	51	5513	3.22	-
107	53	5543	3.24	653	46	5618	3.29	528	49	5562	3.25	712
108	55	5598	3.27	-	54	5672	3.32	-	50	5612	3.28	-
109	52	5650	3.30	641	51	5723	3.35	-	46	5658	3.31	683
110	56	5706	3.34	-	53	5776	3.38	-	53	5711	3.34	-
111	47	5753	3.36	598	52	5828	3.41	589	51	5762	3.37	684
112	49	5802	3.39	-	51	5879	3.44	-	48	5810	3.40	-

Table B2. Continued.

Col.	C1				C2				C3			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
Day												
113	48	5850	3.42	652	50	5929	3.47	567	49	5859	3.43	654
114	51	5901	3.45	-	52	5981	3.50	-	52	5911	3.46	-
115	52	5953	3.48	679	52	6033	3.53	553	51	5962	3.49	649
116	50	6003	3.51	-	49	6082	3.56	-	52	6014	3.52	-
117	53	6056	3.54	-	48	6130	3.58	576	49	6063	3.55	629
118	46	6102	3.57	-	49	6179	3.61	-	48	6111	3.57	-
119	51	6153	3.60	572	51	6230	3.64	578	49	6160	3.60	-
120	49	6202	3.63	-	52	6282	3.67	-	50	6210	3.63	-
121	48	6250	3.65	531	46	6328	3.70	473	52	6262	3.66	608
122	51	6301	3.68	-	49	6377	3.73	-	49	6311	3.69	-
123	51	6352	3.71	558	52	6429	3.76	508	51	6362	3.72	539
124	48	6400	3.74	-	51	6480	3.79	-	52	6414	3.75	-
125	49	6449	3.77	477	50	6530	3.82	462	49	6463	3.78	507
126	50	6449	3.80	-	51	6581	3.85	-	51	6514	3.81	-
127	48	6547	3.83	492	49	6630	3.88	487	50	6564	3.84	442
128	52	6599	3.86	-	49	6679	3.91	-	48	6612	3.87	-

Table B3. Daily Data for Columns C4, C5, and C6.

Col. Day	C4				C5				C6			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
1	0	0	0.00	-	0	0	0.00	-	0	0	0.00	-
2	23	23	0.01	-	65	65	0.04	-	12	12	0.01	-
3	147	170	0.10	ND	88	153	0.09	ND	125	137	0.08	ND
4	85	255	0.15	ND	127	280	0.16	-	136	273	0.16	-
5	118	373	0.22	-	111	391	0.23	0.087	72	345	0.20	-
6	78	451	0.26	-	88	479	0.28	-	115	460	0.27	ND
7	95	546	0.32	0.068	122	601	0.35	0.464	142	602	0.35	-
8	115	661	0.39	0.228	95	696	0.41	-	110	712	0.42	-
9	83	744	0.44	-	125	821	0.48	1.1	90	802	0.47	-
10	89	833	0.49	-	110	931	0.54	-	97	899	0.52	12
11	90	923	0.54	3.9	135	1066	0.62	-	160	1059	0.62	-
12	131	1054	0.62	-	142	1208	0.71	38	127	1186	0.69	-
13	122	1176	0.69	12	88	1296	0.76	58	138	1324	0.77	-
14	108	1284	0.75	-	103	1399	0.82	-	175	1499	0.88	-
15	113	1397	0.82	29	81	1480	0.86	82	128	1627	0.95	142
16	91	1488	0.87	-	114	1594	0.93	-	86	1713	1.00	-

Table B3. Continued.

Col. Day	C4				C5				C6			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
17	84	1572	0.92	-	107	1701	1.00	-	65	1778	1.04	-
18	71	1643	0.96	3	64	1765	1.03	93	86	1864	1.09	221
19	88	1731	1.01	-	136	1901	1.11	-	95	1959	1.15	-
20	105	1836	1.07	112	93	1994	1.17	241	73	2032	1.19	292
21	88	1924	1.12	-	84	2078	1.22	-	66	2098	1.23	-
22	117	2041	1.19	127	95	2173	1.27	322	132	2230	1.30	336
23	93	2134	1.25	-	79	2252	1.32	-	123	2353	1.38	-
24	96	2230	1.30	222	86	2338	1.37	352	120	2473	1.45	352
25	85	2315	1.35	-	114	2452	1.43	-	96	2569	1.50	-
26	142	2457	1.44	286	73	2525	1.48	453	88	2657	1.55	341
27	120	2577	1.51	-	65	2590	1.51	-	84	2741	1.60	-
28	113	2690	1.57	354	88	2678	1.57	419	113	2854	1.67	637
29	119	2809	1.64	-	126	2804	1.64	-	82	2936	1.72	-
30	86	2895	1.69	542	110	2914	1.70	472	90	3026	1.77	712
31	91	2986	1.75	-	92	3006	1.76	-	87	3113	1.82	-
32	72	3058	1.79	639	81	3087	1.80	558	118	3231	1.89	774

Table B3. Continued.

Col. Day	C4				C5				C6			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
33	131	3189	1.84	-	117	3204	1.87	-	94	3325	1.94	-
34	50	3239	1.89	705	109	3313	1.94	618	83	3408	1.99	793
35	93	3332	1.95	-	114	3427	2.00	-	79	3487	2.04	-
36	114	3440	2.02	-	106	3533	2.07	-	87	3574	2.09	-
37	107	3553	2.08	730	118	3651	2.14	808	106	3680	2.15	761
38	117	3670	2.15	-	126	3777	2.21	-	113	3793	2.22	-
39	111	3781	2.21	716	114	3891	2.28	860	107	3900	2.28	803
40	103	3884	2.27	-	96	3987	2.33	-	94	3994	2.34	-
41	97	3981	2.33	754	93	4080	2.39	897	116	4110	2.40	812
42	114	4095	2.40	-	84	4164	2.44	-	105	4215	2.46	-
43	109	4204	2.46	840	87	4251	2.49	912	85	4300	2.52	836
44	97	4301	2.52	-	76	4327	2.53	-	71	4371	2.56	-
45	88	4389	2.57	922	92	4419	2.58	873	83	4454	2.60	851
46	82	4471	2.62	-	80	4499	2.63	-	94	4548	2.66	-
47	91	4562	2.67	931	96	4595	2.69	881	87	4635	2.71	-
48	97	4649	2.72	-	90	4685	2.74	-	90	4725	2.76	-

Table B3. Continued.

Col.	C4				C5				C6			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
49	104	4763	2.78	878	86	4771	2.79	933	96	4821	2.82	808
50	110	4873	2.85	-	82	4853	2.84	-	93	4914	2.87	-
51	105	4978	2.91	873	87	4940	2.89	876	87	5001	2.92	899
52	108	5086	2.97	-	80	5020	2.94	-	89	5090	2.98	-
53	96	5182	3.03	-	79	5099	2.98	-	84	5174	3.03	804
54	95	5277	30.09	-	85	5184	3.03	-	82	5256	3.07	-
55	97	5374	3.14	803	88	5272	3.08	892	93	5344	3.13	722
56	91	5465	3.20	-	94	5366	3.14	-	95	5444	3.18	-
57	85	5550	3.25	815	87	5453	3.19	768	106	5550	3.25	663
58	81	5631	3.29	-	94	5547	3.24	-	109	5659	3.31	-
59	88	5719	3.34	829	104	5651	3.30	678	103	5762	3.37	642
60	93	5812	3.40	-	101	5752	3.36	-	105	5867	3.43	-
61	99	5911	3.46	809	105	5857	3.43	709	101	5968	3.49	592
62	94	6005	3.51	-	107	5964	3.49	-	103	6071	3.55	-
63	90	6095	3.56	769	98	6062	3.55	622	98	6169	3.61	583
64	95	6190	3.62	-	95	6157	3.60	-	94	6263	3.66	-

Table B3. Continued.

Col.	C4				C5				C6			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
65	103	6293	3.68	684	92	6244	3.65	-	93	6356	3.72	566
66	109	6402	3.74	-	96	6345	3.71	-	97	6453	3.77	-
67	104	6506	3.80	721	102	6447	3.77	571	99	6552	3.83	-
68	102	6608	3.86	-	104	6551	3.83	-	96	6648	3.89	-
69	98	6706	3.92	663	105	6656	3.89	526	97	6745	3.94	487
70	96	6802	3.98	-	101	6757	3.95	-	94	6839	4.00	-
71	105	6907	4.04	581	97	6854	4.01	539	105	6944	4.06	505
72	103	7010	4.10	-	94	6948	4.06	-	107	7051	4.12	-
73	99	7109	4.16	605	98	7040	4.12	482	95	7146	4.18	454
74	96	7205	4.21	-	104	7150	4.18	-	99	7245	4.24	-
75	95	7300	4.27	553	96	7246	4.24	493	103	7348	4.30	423
76	100	7400	4.33	-	95	7344	4.29	-	102	7450	4.36	-
77	93	7493	4.38	579	92	7433	4.35	512	102	7552	4.42	436
78	106	7599	4.44	-	96	7529	4.40	-	94	7646	4.47	-
79	105	7704	4.51	555	93	7622	4.46	415	97	7743	4.53	382
80	97	7801	4.56	-	98	7720	4.51	-	102	7845	4.59	-

Table B3. Continued.

Col. Day	C4				C5				C6			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
81	95	7896	4.62	529	105	7825	4.58	409	99	7944	4.65	415
82	101	7997	4.68	-	106	7931	4.64	-	103	8047	4.71	-
83	104	8101	4.74	541	102	8033	4.70	372	104	8151	4.77	396
84	97	8198	4.79	-	103	8136	4.76	-	103	8254	4.83	-
85	102	8300	4.85	472	100	8236	4.82	322	105	8359	4.89	364
86	108	8408	4.92	-	102	8338	4.88	-	102	8461	4.95	-
87	105	8513	4.98	406	103	8441	4.94	316	95	8556	5.00	329
88	97	8610	5.04	-	104	8545	5.00	-	97	8653	5.06	-
89	96	8706	5.09	417	95	8640	5.05	298	101	8754	5.12	327
90	98	8804	5.15	-	92	8732	5.11	-	100	8854	5.18	-
91	96	8900	5.20	393	94	8826	5.16	224	97	8951	5.23	318
92	99	8999	5.26	-	93	8919	5.22	-	104	9055	5.30	-
93	100	9099	5.32	412	97	9016	5.27	243	98	9153	5.35	-
94	104	9203	5.38	-	99	9115	5.33	-	96	9249	5.41	-
95	106	9309	5.44	351	103	9218	5.39	269	99	9348	5.47	276
96	102	9411	5.50	-	98	9316	5.45	-	101	9449	5.53	-

Table B3. Continued.

Col. Day	C4					C5					C6				
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l			
97	97	9508	5.56	302	101	9417	5.51	244	98	9547	5.58	263			
98	96	9604	5.62	-	97	9514	5.56	-	103	9650	5.64	-			
99	94	9698	5.67	314	96	9610	5.62	248	100	9750	5.70	271			
100	99	9797	5.73	-	102	9712	5.68	-	100	9850	5.76	-			
101	103	9900	5.79	303	98	9810	5.74	229	105	9955	5.82	228			
102	102	10,002	5.85	-	99	9909	5.79	-	98	10,053	5.88	-			
103	104	10,106	5.91	306	99	10,000	5.85	183	102	10,155	5.94	212			
104	98	10,204	5.97	-	93	10,101	5.91	-	101	10,256	6.00	-			
105	96	10,300	6.02	263	93	10,194	5.96	201	104	10,360	6.06	192			
106	90	10,390	6.08	-	97	10,291	6.02	-	102	10,462	6.12	-			
107	103	10,493	6.14	254	104	10,395	6.08	212	99	10,561	6.18	209			
108	102	10,595	6.20	-	107	10,502	6.14	-	97	10,658	6.23	-			
109	99	10,694	6.25	193	101	10,603	6.20	184	98	10,756	6.29	232			
110	96	10,790	6.31	-	96	10,699	6.26	-	100	10,856	6.35	-			
111	100	10,890	6.37	222	98	10,797	6.31	-	105	10,961	6.41	179			
112	105	10,995	6.43	-	99	10,896	6.37	-	101	11,062	6.47	-			

Table B3. Continued.

Col.	C4				C5				C6			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
113	103	11,098	6.49	231	103	10,999	5.43	189	102	11,164	6.53	147
114	101	11,199	6.55	-	104	11,103	6.49	-	99	11,263	6.59	-
115	98	11,297	6.61	198	106	11,209	6.55	170	98	11,361	6.54	183
116	99	11,396	6.66	-	101	11,310	6.61	-	99	11,460	6.70	-
117	101	11,497	6.72	187	101	11,411	6.67	161	97	11,557	6.76	167
118	100	11,597	6.78	-	99	11,510	6.73	-	101	11,658	6.82	-
119	97	11,694	6.84	202	97	11,607	6.79	172	100	11,758	6.88	159
120	98	11,792	6.90	-	98	11,705	6.85	-	102	11,860	6.94	-
121	96	11,888	6.95	183	102	11,807	6.90	152	98	11,958	6.99	-
122	99	11,987	7.01	-	98	11,905	6.96	-	99	12,057	7.05	-
123	101	12,088	7.07	167	102	12,007	7.02	139	96	12,153	7.11	112
124	102	12,190	7.13	-	103	12,110	7.08	-	98	12,251	7.16	-
125	98	12,286	7.19	123	96	12,206	7.14	142	100	12,351	7.22	109
126	99	12,387	7.24	-	97	12,300	7.19	-	101	12,452	7.28	-
127	103	12,490	7.30	103	101	12,404	7.25	106	103	12,555	7.34	103
128	98	12,588	7.36	-	100	12,504	7.31	-	99	12,654	7.40	-

Table B4. Daily Data for Columns C7, C8, and C9.

Col. Day	C7				C8				C9			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
1	0	0	0.00	-	0	0	0.00	-	0	0	0.00	-
2	12	12	0.01	-	0	0	0.00	-	62	62	0.04	-
3	67	79	0.05	ND	89	89	0.05	ND	78	140	0.08	ND
4	65	144	0.08	-	71	160	0.09	ND	32	172	0.10	-
5	56	200	0.12	ND	43	203	0.12	-	56	228	0.13	ND
6	73	273	0.16	-	39	242	0.14	-	79	307	0.18	0.076
7	39	312	0.18	-	77	319	0.19	0.146	78	385	0.22	-
8	71	383	0.22	0.122	65	384	0.22	-	46	431	0.25	-
9	73	456	0.27	-	71	455	0.27	1.6	40	471	0.28	-
10	65	521	0.30	-	73	528	0.31	-	89	560	0.33	2.7
11	85	606	0.35	0.672	68	596	0.35	-	32	592	0.35	-
12	58	664	0.39	-	82	678	0.40	12.8	35	627	0.37	-
13	72	736	0.43	3.2	69	747	0.44	8.2	59	686	0.40	-
14	61	797	0.47	-	52	799	0.47	-	43	729	0.43	-
15	58	855	0.50	9.8	63	862	0.50	17	55	784	0.46	15
16	36	891	0.52	-	39	901	0.53	-	41	825	0.48	-

Table B4. Continued.

Col.	C7				C8				C9			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
17	30	921	0.54	-	45	946	0.55	-	54	879	0.51	-
18	50	971	0.57	42	64	1010	0.59	42	57	936	0.55	13
19	43	1014	0.59	-	26	1036	0.61	-	16	952	0.56	-
20	66	1080	0.63	77	56	1092	0.64	54	63	1015	0.59	18
21	80	1160	0.68	-	54	1146	0.67	-	65	1080	0.63	-
22	59	1219	0.71	139	73	1219	0.71	47	50	1130	0.66	23
23	68	1287	0.75	-	46	1265	0.74	-	47	1177	0.69	-
24	77	1364	0.80	124	68	1333	0.78	63	68	1245	0.73	16
25	46	1410	0.82	-	23	1356	0.79	-	59	1304	0.76	-
26	50	1460	0.85	93	61	1417	0.83	148	71	1375	0.80	42
27	37	1497	0.88	-	28	1445	0.84	-	28	1403	0.82	-
28	82	1579	0.92	147	57	1502	0.88	233	70	1473	0.86	58
29	42	1621	0.95	-	33	1535	0.90	-	47	1514	0.88	-
30	64	1685	0.98	183	53	1588	0.93	322	62	1576	0.92	94
31	62	1747	1.02	-	45	1633	0.96	-	21	1597	0.93	-
32	80	1827	1.07	241	56	1689	0.99	407	77	1674	0.98	113

Table B4. Continued.

Col.	C7					C8					C9				
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l			
Day															
33	29	1856	1.08	-	40	1729	1.01	-	39	1713	1.00	-			
34	66	1922	1.12	307	55	1784	1.04	462	68	1781	1.04	163			
35	61	1983	1.16	-	67	1851	1.08	-	70	1851	1.08	-			
36	69	2052	1.20	-	71	1922	1.12	-	73	1924	1.12	-			
37	64	2116	1.24	376	77	1999	1.17	524	69	1993	1.16	347			
38	59	2175	1.27	-	63	2062	1.21	-	55	2048	1.20	-			
39	62	2237	1.31	442	56	2118	1.24	622	44	2092	1.22	-			
40	55	2292	1.34	-	43	2161	1.26	-	49	2141	1.25	-			
41	46	2338	1.37	492	59	2220	1.30	678	53	2194	1.28	513			
42	41	2379	1.39	-	53	2273	1.33	-	39	2233	1.31	-			
43	55	2434	1.42	-	46	2319	1.36	649	33	2266	1.32	565			
44	67	2501	1.46	-	32	2351	1.38	-	46	2312	1.35	-			
45	59	2560	1.50	3573	38	2389	1.40	-	54	2366	1.38	586			
46	53	2613	1.53	-	34	2423	1.42	-	42	2408	1.41	-			
47	46	2659	1.56	9662	41	2464	1.44	733	57	2465	1.44	608			
48	48	2707	1.58	-	48	2512	1.47	-	51	2516	1.47	-			

Table B4. Continued.

Col.	C7					C8					C9				
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	TCE Conc., mg/l
49	55	2762	1.62	-	56	2568	1.50	761	59	2575	1.51	-			
50	46	2808	1.64	-	62	2630	1.54	-	56	2631	1.54	-			
51	44	2852	1.67	675	69	2699	1.58	793	49	2680	1.57	623			
52	41	2893	1.69	-	57	2756	1.61	-	53	2733	1.60	-			
53	51	2944	1.72	733	49	2805	1.64	790	58	2791	1.63	698			
54	54	2998	1.75	-	46	2351	1.67	-	54	2845	1.66	-			
55	59	3057	1.79	752	60	2911	1.70	08446	63	2908	1.70	706			
56	61	3118	1.82	-	64	2975	1.74	-	57	2965	1.73	-			
57	63	3181	1.86	783	57	3032	1.77	839	52	3017	1.76	776			
58	69	3250	1.90	-	54	3086	1.80	-	47	3064	1.79	-			
59	62	3312	1.94	-	53	3139	1.84	-	45	3109	1.82	792			
60	54	3366	1.97	-	48	3187	1.86	-	52	3161	1.85	-			
61	52	3418	2.00	802	49	3236	1.89	891	53	3214	1.88	813			
62	52	3470	2.03	-	51	3287	1.92	-	52	3266	1.91	-			
63	49	3519	2.06	831	53	3340	1.95	865	48	3314	1.94	922			
64	48	3567	2.09	-	50	3390	1.98	-	47	3361	1.97	-			

AD-A147 918

FATE AND DISPOSITION OF TRICHLOROETHYLENE IN SURFACE
SOILS(U) AIR FORCE INST OF TECH WRIGHT-PATTERSON AFB OH
T J WALKER 1984 AFIT/CI/NR-84-92D


4/4

UNCLASSIFIED

F/G 13/2

NL

1



MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

Table B4. Continued.

Col. Day	C7					C8					C9				
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
65	50	3617	2.12	826	52	3442	2.01	884	44	3405	1.99	-	-	-	-
66	54	3671	2.15	-	47	3489	2.04	-	49	3454	2.02	-	-	-	-
67	56	3727	2.18	888	46	3535	2.07	928	53	3507	2.05	863	-	-	-
68	47	3774	2.21	-	48	3583	2.10	-	51	3558	2.08	-	-	-	-
69	45	3819	2.23	-	52	3635	2.13	939	47	3605	2.11	898	-	-	-
70	46	3865	2.26	-	53	3688	2.16	-	53	3658	2.14	-	-	-	-
71	48	3913	2.29	931	55	3743	2.19	-	55	3713	2.17	938	-	-	-
72	47	3960	2.32	-	51	3794	2.22	-	54	3767	2.20	-	-	-	-
73	52	4012	2.35	908	50	3844	2.25	1024	53	3820	2.23	963	-	-	-
74	53	4065	2.38	-	52	3896	2.28	-	52	3872	2.26	-	-	-	-
75	49	4114	2.41	954	51	3947	2.31	1018	45	3917	2.29	-	-	-	-
76	50	4164	2.44	-	46	3993	2.34	-	46	3963	2.32	-	-	-	-
77	48	4212	2.46	943	49	4042	2.36	1036	48	4011	2.35	941	-	-	-
78	51	4263	2.49	-	56	4098	2.40	-	47	4058	2.37	-	-	-	-
79	47	4310	2.52	980	54	4152	2.43	1062	49	4107	2.40	-	-	-	-
80	53	4363	2.55	-	56	4208	2.46	-	51	4158	2.43	-	-	-	-

Table B4. Continued.

Col.	C7				C8				C9			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
81	50	4413	2.58	-	53	4261	2.49	-	51	4209	2.46	994
82	49	4462	2.61	-	48	4309	2.52	-	52	4261	2.49	-
83	54	4516	2.64	987	54	4363	2.55	1127	51	4312	2.52	1008
84	52	4568	2.67	-	51	4414	2.58	-	46	4358	2.55	-
85	51	4619	2.70	977	47	4461	2.61	1068	48	4406	2.58	996
86	54	4673	2.73	-	48	4509	2.64	-	47	4453	2.60	-
87	51	4724	2.76	1027	52	4561	2.67	1041	49	4502	2.63	965
88	50	4774	2.79	-	49	4610	2.70	-	51	4553	2.66	-
89	49	4823	2.82	1040	51	4661	2.73	1060	53	4606	2.69	988
90	48	4871	2.85	-	47	4708	2.75	-	52	4658	2.72	-
91	48	4919	2.88	1010	50	4758	2.78	-	55	4713	2.76	1044
92	47	4966	2.90	-	49	4807	2.81	-	53	4766	2.79	-
93	52	5018	2.93	1080	51	4858	2.84	1010	53	4819	2.82	1023
94	51	5069	2.96	-	53	4911	2.87	-	51	4870	2.85	-
95	53	5122	3.00	-	52	4963	2.90	1037	47	4917	2.88	1072
96	54	5176	3.03	-	51	5014	2.93	-	49	4966	2.90	-

Table B4. Continued.

Col.	C7					C8					C9				
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV
97	49	5225	3.06	1038	50	5064	2.96	1055	50	5016	2.93	1040	50	5016	2.93
98	46	5271	3.08	-	52	5116	2.99	-	50	5066	2.96	-	50	5066	2.96
99	47	5318	3.11	1076	49	5165	3.02	1075	48	5114	2.99	1028	48	5114	2.99
100	51	5369	3.14	-	46	5211	3.05	-	47	5161	3.02	-	47	5161	3.02
101	49	5418	3.17	1131	48	5259	3.08	1067	49	5210	3.05	983	49	5210	3.05
102	48	5466	3.20	-	49	5308	3.10	-	50	5260	3.08	-	50	5260	3.08
103	52	5518	3.23	1073	52	5360	3.13	1084	51	5311	3.11	1069	51	5311	3.11
104	49	5567	3.26	-	51	5411	3.16	-	48	5359	3.13	-	48	5359	3.13
105	52	5619	3.29	1061	53	5464	3.20	1052	47	5406	3.16	1008	47	5406	3.16
106	54	5673	3.32	-	52	5516	3.23	-	46	5452	3.19	-	46	5452	3.19
107	51	5724	3.35	1122	48	5564	3.25	1037	52	5504	3.22	1013	52	5504	3.22
108	48	5772	3.38	-	53	5617	3.28	-	53	5557	3.25	-	53	5557	3.25
109	49	5821	3.40	1050	52	5669	3.32	1026	53	5610	3.28	1009	53	5610	3.28
110	51	5872	3.43	-	54	5723	3.35	-	51	5661	3.31	-	51	5661	3.31
111	50	5922	3.46	1023	49	5772	3.38	1019	50	5711	3.34	1056	50	5711	3.34
112	52	5974	3.49	-	48	5820	3.40	-	51	5762	3.37	-	51	5762	3.37

Table B5. Daily Data for Columns C10, C11, and C12.

Col. Day	C10					C11					C12				
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV
1	0	0	0.00	-	0	0	0.00	-	0	0	0.00	-	0	0	-
2	41	41	0.02	-	87	87	0.05	-	43	43	0.02	-	43	43	-
3	130	174	0.10	ND	115	202	0.12	ND	140	183	0.11	ND	140	183	ND
4	63	234	0.14	-	122	324	0.19	0.167	105	288	0.17	-	105	288	-
5	124	358	0.21	ND	94	418	0.24	-	123	411	0.24	-	123	411	-
6	136	494	0.29	-	89	507	0.30	-	83	494	0.29	-	83	494	ND
7	124	618	0.36	-	123	6307	0.372	0.392	117	611	0.36	-	117	611	-
8	125	743	0.43	2.8	127	757	0.44	-	65	676	0.40	-	65	676	-
9	87	830	0.48	-	91	848	0.50	3.7	135	811	0.47	-	135	811	-
10	73	903	0.53	-	0	8480	0.50	-	72	883	0.52	14	72	883	14
11	89	992	0.58	72	117	965	0.56	-	83	966	0.56	-	83	966	-
12	111	1103	0.64	-	105	1070	0.63	29	94	1060	0.62	8	94	1060	8
13	118	1221	0.71	118	79	1149	0.67	41	73	1133	0.66	80	73	1133	80
14	107	1328	0.78	-	84	1233	0.72	-	68	1201	0.70	-	68	1201	-
15	132	1460	0.85	173	107	1340	0.78	92	129	1330	0.78	168	129	1330	168
16	113	1573	0.92	-	51	1391	0.81	-	120	1450	0.85	-	120	1450	-

Table B5. Continued.

Col.	C10					C11					C12				
	Vol. of Eff., ml	Qum. Eff., ml	Qum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Qum. Eff., ml	Qum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Qum. Eff., ml	Qum. Eff., PV	Vol. of Eff., ml	Qum. Eff., ml	Qum. Eff., PV	TCE Conc., mg/l
17	96	1669	0.98	108	74	1465	0.86	-	91	1541	0.90	-	-	-	-
18	76	1745	1.02	328	136	1601	0.94	290	107	1648	0.96	387	-	-	-
19	81	1826	1.07	-	91	1692	0.99	-	60	1708	1.00	-	-	-	-
20	68	1894	1.11	392	89	1781	1.04	352	59	1767	1.03	502	-	-	-
21	115	2009	1.18	-	90	1871	1.09	-	94	1861	1.09	-	-	-	-
22	93	2102	1.23	588	86	1957	1.14	515	76	1937	1.13	449	-	-	-
23	86	2188	1.28	-	77	2034	1.19	-	83	2020	1.18	-	-	-	-
24	106	2294	1.34	543	108	2142	1.25	524	91	2111	1.24	452	-	-	-
25	129	2423	1.42	-	85	2227	1.30	-	88	2199	1.29	-	-	-	-
26	116	2539	1.48	594	90	1217	1.36	618	123	2322	1.36	672	-	-	-
27	122	2661	1.56	-	79	2396	1.40	-	96	2418	1.41	-	-	-	-
28	133	2794	1.64	662	115	2511	1.47	730	81	2499	1.46	688	-	-	-
29	114	2908	1.70	-	126	2637	1.54	-	116	2615	1.53	-	-	-	-
30	82	2990	1.75	788	85	2722	1.59	748	119	2734	1.60	704	-	-	-
31	61	3051	1.78	-	93	2815	1.65	-	142	2876	1.68	-	-	-	-
32	126	3177	1.86	835	130	2945	1.72	637	133	3009	1.76	697	-	-	-

Table B5. Continued.

Col.	C10				C11				C12			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
Day												
33	92	3269	1.91	-	124	3069	1.79	-	138	3147	1.83	-
34	80	3349	1.96	827	119	3188	1.86	713	118	3265	1.91	718
35	91	3440	2.01	-	106	3294	1.93	-	121	2286	1.98	-
36	86	3526	2.06	-	98	3392	1.98	-	105	3491	2.04	-
37	97	3623	2.12	898	89	3481	2.04	809	96	3587	2.10	952
38	90	3713	2.17	-	83	3564	2.08	-	91	3678	2.15	-
39	97	3810	2.23	941	91	3655	2.14	833	88	3766	2.20	1009
40	108	3918	2.29	-	103	3758	2.20	-	98	3864	2.26	-
41	114	4032	2.36	980	105	3863	2.26	872	104	3968	2.32	1043
42	122	4154	2.43	-	87	3950	2.31	-	111	4079	2.38	-
43	113	4267	2.50	1050	75	4025	2.35	911	115	4194	2.45	1020
44	119	4386	2.56	-	94	4119	2.41	-	123	4317	2.52	-
45	(Taken out of service, broken)				106	4225	2.47	963	109	4426	2.59	1036
46					111	4336	2.54	-	112	4538	2.65	1052
47					96	4432	2.59	971	107	4645	2.72	1052
48					93	4525	2.65	-	114	4759	2.78	-

Table B5. Continued.

Col.	C10					C11					C12				
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
49					87	4612	2.70	1012	98	4857	2.84	1038			
50					83	4695	2.75	-	92	4949	2.89	-			
51					94	4789	2.80	992	106	5055	2.96	1003			
52					91	4880	2.85	-	112	5167	3.02	-			
53					87	4967	2.90	-	103	5270	3.08	-			
54					94	5061	2.96	-	91	5361	3.14	-			
55					104	5165	3.02	1013	85	5446	3.18	1017			
56					112	5277	3.09	-	81	5527	3.23	-			
57					103	5380	3.15	984	87	5614	3.28	1042			
58					101	5481	3.21	-	93	5707	3.34	-			
59					96	5577	3.26	1021	98	5805	3.39	996			
60					98	5675	3.32	-	94	5899	3.45	-			
61					95	5770	3.37	955	92	5991	3.70	-			
62					91	5861	3.37	-	90	6081	3.56	-			
63					94	5955	3.48	982	89	6170	3.61	938			
64					95	6050	3.54	-	92	6262	3.66	-			

Table B5. Continued.

Col.	C10				C11				C12			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
Day												
65					97	6147	3.59	996	95	6357	3.72	906
66					100	6247	3.65	-	94	6451	3.77	-
67					103	6350	3.71	-	97	6548	3.83	990
68					99	6449	3.77	-	103	6651	3.89	-
69					98	6547	3.83	1028	106	6757	3.95	1017
70					96	6643	3.88	-	103	6860	4.01	-
71					98	6741	3.94	941	108	6968	4.07	-
72					96	6837	4.00	-	101	7069	4.13	-
73					97	6934	4.05	960	96	7165	4.19	1012
74					101	7035	4.11	-	94	7259	4.25	-
75					100	7135	4.17	993	98	7357	4.30	1018
76					104	7239	4.23	-	97	7454	4.36	-
77					106	7345	4.30	1020	97	7551	4.42	961
78					103	7448	4.36	-	102	7653	4.48	-
79					105	7553	4.42	907	103	7756	4.54	994
80					97	7650	4.47	-	107	7863	4.60	-

Table B5. Continued.

Col.	C10					C11					C12				
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., P _v	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l			
Day															
81					99	7749	4.53	963	102	7965	4.66	981			
82					102	7851	4.59	-	103	8086	4.72	-			
83					98	7949	4.65	901	98	8166	4.78	968			
84					95	8044	4.70	-	98	8263	4.83	-			
85					99	8143	4.76	1022	99	8362	4.89	983			
86					103	8246	4.82	-	96	8458	4.95	-			
87					99	8345	4.88	1016	95	8553	5.00	1027			
88					100	8445	4.94	-	94	8647	5.06	-			
89					95	8540	4.99	989	94	8741	5.11	1003			
90					92	8632	5.05	-	97	8838	5.17	-			
91					99	8731	5.11	1041	97	8935	5.23	1071			
92					103	8834	5.17	-	99	9034	5.28	-			
93					103	8937	5.23	992	104	9138	5.34	-			
94					105	9042	5.29	-	102	9240	5.40	-			
95					97	9139	5.34	973	104	9344	5.46	991			
96					96	9235	5.40	-	103	9447	5.52	-			

Table B5. Continued.

Col.	C10					C11					C12				
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV
97					95	9330	5.46	907	105	9552	5.59	952			
98					102	9432	5.52	-	106	9658	5.65	-			
99					98	9530	5.57	952	98	9756	5.71	894			
100					94	9624	5.63	-	94	9850	5.76	-			
101					98	9722	5.69	937	103	9953	5.82	873			
102					97	9819	5.74	-	101	10,054	5.88	-			
103					102	9921	5.80	912	97	10,151	5.94	882			
104					96	10,017	5.86	-	102	10,253	6.00	-			
105					99	10,116	5.92	897	98	10,351	6.05	840			
106					95	10,211	5.97	-	96	10,447	6.11	-			
107					103	10,314	6.03	811	99	10,546	6.17	863			
108					107	10,421	6.09	-	98	10,644	6.22	-			
109					101	10,522	6.15	789	104	10,748	6.29	692			
110					100	10,622	6.21	-	103	10,851	6.35	-			
111					97	10,719	6.27	692	103	10,954	6.41	747			
112					96	10,815	6.32	-	101	11,055	6.46	-			

Table B5. Continued.

Col. Day	C10				C11				C12			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
113					98	10,913	6.38	733	104	11,159	6.53	653
114					101	11,914	6.44	0	102	11,261	6.59	-
115					101	11,115	6.50	670	98	11,359	6.64	583
116					102	11,217	6.56	-	101	11,460	6.70	-
117					95	11,312	6.62	682	97	11,557	6.76	588
118					98	11,410	6.67	-	99	11,656	6.82	-
119					99	11,509	6.73	627	100	11,756	6.87	535
120					101	11,610	6.79	-	100	11,856	6.93	-
121					98	11,708	6.85	612	98	11,954	6.99	490
122					103	11,811	6.91	-	96	12,050	7.05	-
123					104	11,915	6.97	543	99	12,149	7.10	486
124					102	12,017	7.03	-	101	12,250	7.16	-
125					101	12,118	7.09	558	102	12,352	7.22	403
126					100	12,218	7.15	-	97	12,449	7.28	-
127					99	12,317	7.20	541	102	12,551	7.34	407
128					100	12,417	7.26	-	102	12,653	7.40	-

Table B6. Daily Effluent Volume from Chalmers
Soil Control Column.

Day	Effluent Collected, ml	Day	Effluent Collected, ml	Day	Effluent Collected, ml
1	0	24	118	47	111
2	127	25	75	48	102
3	*133	26	133	49	109
4	109	27	86	50	116
5	125	28	96	51	122
6	136	29	67	52	108
7	82	30	85	53	96
8	73	31	113	54	89
9	91	32	89	55	83
10	142	33	75	56	91
11	*83	34	86	57	95
12	116	35	79	58	101
13	108	36	88	59	105
14	85	37	99	60	107
15	*141	38	114	61	103
16	80	39	121	62	109
17	93	40	118	63	101
18	112	41	106	64	*97
19	126	42	122	65	93
20	130	43	136	66	94
21	108	44	*127	67	91
22	110	45	113	68	96
23	127	46	118	69	99

*Indicates sample taken for TCE analysis. No TCE detected in any samples.

Table B6. Continued.

Day	Effluent Collected, ml	Day	Effluent Collected, ml	Day	Effluent Collected, ml
70	95	93	*96	116	96
71	102	94	95	117	99
72	103	95	92	118	103
73	102	96	97	119	*101
74	98	97	98	120	98
75	97	98	101	121	103
76	93	99	100	122	101
77	*96	100	97	123	98
78	97	101	96	124	97
79	96	102	99	125	99
80	101	103	97	126	98
81	103	104	102	127	100
82	100	105	*103	128	102
83	107	106	101	129	104
84	96	107	*104	130	101
85	98	108	97	131	93
86	97	109	103	132	104
87	96	110	102		
88	99	111	102		
89	101	112	101		
90	107	113	99		
91	102	114	102		
92	98	115	100		

*Indicates sample taken for TCE analysis. No TCE detected in any samples.

Table B7. Daily Data for Columns R1, R2, and R3.

Col. Day	R1				R2				R3			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
1	0	0	0.00	-	0	0	0.00	-	0	0	0.00	-
2	92	92	0.06	-	35	35	0.02	-	75	25	0.05	ND
3	73	165	0.10	ND	72	107	0.07	ND	55	130	0.08	-
4	82	247	0.15	-	69	176	0.11	-	62	192	0.12	ND
5	65	312	0.19	-	71	247	0.15	ND	42	234	0.14	-
6	37	349	0.22	-	78	325	0.20	-	90	324	0.20	ND
7	45	394	0.24	-	84	409	0.25	0.289	32	356	0.22	-
8	72	466	0.29	0.146	46	455	0.28	-	35	391	0.24	-
9	63	529	0.33	-	58	513	0.32	0.892	47	438	0.27	-
10	72	601	0.37	-	55	568	0.35	-	92	530	0.33	ND
11	50	651	0.40	0.742	63	631	0.39	-	55	585	0.36	-
12	34	685	0.42	-	67	698	0.43	2.3	59	644	0.40	-
13	68	752	0.46	-	53	751	0.46	-	60	704	0.44	-
14	88	841	0.52	13.8	79	830	0.51	28	71	775	0.48	0.624
15	58	899	0.56	-	42	872	0.54	-	64	839	0.52	-
16	73	971	0.60	28	64	936	0.58	19	62	901	0.56	0.698

Table B7. Continued.

Col. Day	R1				R2				R3			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
17	34	1006	0.62	-	36	972	0.60	-	33	934	0.50	-
18	17	1023	0.63	-	24	996	0.62	-	41	975	0.60	-
19	101	1124	0.69	67	60	1056	0.65	41	77	1052	0.65	3.1-
20	59	1183	0.73	-	31	1087	0.67	-	30	1082	0.67	-
21	50	1233	0.76	53	64	1151	0.71	76	56	1138	0.70	19
22	40	1273	0.79	-	27	1178	0.73	-	39	1177	0.73	-
23	63	1335	0.82	71	59	1237	0.76	97	66	1243	0.77	12
24	43	1379	0.85	-	68	1305	0.81	-	47	1290	0.80	-
25	66	1445	0.89	96	73	1378	0.85	186	61	1351	0.83	31
26	36	1481	0.91	-	80	1458	0.90	-	31	1382	0.85	-
27	50	1531	0.94	148	54	1512	0.93	257	61	1443	0.89	66
28	41	1572	0.97	-	63	1575	0.97	-	38	1481	0.91	-
29	57	1629	1.01	192	71	1646	1.02	368	69	1550	0.96	123
30	31	1660	1.02	-	34	1680	1.04	-	27	1577	0.97	-
31	67	1727	1.07	218	66	1746	1.08	402	50	1627	1.00	231
32	29	1756	1.08	-	36	1782	1.10	-	44	1671	1.03	-

Table B7. Continued.

Col.	R1					R2					R3					
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
33	61	1817	1.12	281	72	1854	1.14	473	23	1752	1.08	238				
34	57	1874	1.16	-	43	1897	1.17	-	23	1775	1.10	-				
35	64	1938	1.20	323	50	1947	1.19	546	50	1825	1.12	327				
36	62	2000	1.23	-	61	2008	1.23	-	61	1886	1.16	-				
37	54	2054	1.27	-	50	2066	1.27	-	54	1940	1.19	-				
38	56	2110	1.30	382	62	2128	1.31	604	57	1997	1.22	339				
39	60	2170	1.33	-	66	2194	1.35	-	64	2061	1.26	-				
40	57	2227	1.37	426	63	2257	1.38	654	69	2130	1.31	-				
41	49	2276	1.40	-	55	2312	1.42	-	58	2188	1.34	-				
42	58	2334	1.43	-	68	2380	1.46	-	47	2235	1.37	489				
43	56	2390	1.47	-	52	2432	1.49	-	46	2281	1.40	-				
44	61	2451	1.50	561	44	2476	1.52	688	54	2335	1.43	537				
45	62	2513	1.54	-	49	2525	1.55	-	59	2394	1.47	-				
46	55	2568	1.58	565	57	2582	1.58	732	64	2458	1.51	-				
47	53	2621	1.61	-	62	2644	1.62	-	55	2513	1.54	-				
48	44	2665	1.64	623	65	2709	1.66	784	57	2570	1.58	613				

Table B7. Continued.

Col.	R1					R2					R3				
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	
49	36	2701	1.66	-	63	2772	1.70	-	52	2622	52	2622	1.61	-	-
50	39	2740	1.69	-	65	2837	1.75	802	54	2676	54	2676	1.65	712	-
51	49	2789	1.72	-	68	2905	1.79	-	58	2734	58	2734	1.69	-	-
52	56	2845	1.76	677	62	2967	1.83	-	67	2801	67	2801	1.73	694	-
53	63	2908	1.80	-	58	3025	1.87	-	71	2872	71	2872	1.77	-	-
54	67	2975	1.84	766	52	3077	1.90	838	72	2944	72	2944	1.82	718	-
55	64	3039	1.88	-	56	3133	1.93	-	74	3018	74	3018	1.86	-	-
56	57	3096	1.91	744	59	3192	1.97	845	76	3094	76	3094	1.91	883	-
57	54	3150	1.94	-	55	3247	2.00	-	70	3164	70	3164	1.95	-	-
58	51	3201	1.98	758	51	3298	2.04	831	64	3228	64	3228	1.99	865	-
59	53	3254	2.01	-	47	3345	2.06	-	63	3291	63	3291	2.03	-	-
60	55	3309	2.04	-	50	3395	2.10	794	54	3345	54	3345	2.06	912	-
61	52	3361	2.07	-	53	3448	2.13	-	48	3393	48	3393	2.09	-	-
62	52	3410	2.10	843	51	3499	2.16	810	44	3437	44	3437	2.12	-	-
63	49	3410	2.13	-	48	3547	2.19	-	46	3483	46	3483	2.15	-	-
64	48	3504	2.16	880	49	3596	2.22	-	47	3530	47	3530	2.18	936	-

Table B7. Continued.

Col.	R1					R2					R3				
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
65	45	3549	2.19	-	46	3642	2.25	-	44	3574	2.21	-	-	-	-
66	50	3599	2.22	836	51	3693	2.28	8648	494	3623	2.24	930	-	-	930
67	53	3652	2.25	-	52	3745	2.31	-	51	3674	2.27	-	-	-	-
68	49	3701	2.28	873	49	3794	2.34	918	53	3727	2.30	1060	-	-	1060
69	44	3745	2.31	-	43	3837	2.37	-	55	3782	2.33	-	-	-	-
70	54	3799	2.35	-	47	3884	2.40	937	56	3838	2.37	1017	-	-	1017
71	49	3848	2.38	-	50	3934	2.43	-	53	3891	2.40	-	-	-	-
72	51	3899	2.41	906	46	3980	2.46	930	48	3939	3.43	1038	-	-	1038
73	50	3949	2.44	-	49	4029	2.49	-	47	3986	2.46	-	-	-	-
74	52	4001	2.47	989	47	4076	2.52	988	52	4038	2.49	1012	-	-	1012
75	49	4050	2.50	-	52	4128	2.55	-	52	4090	2.52	-	-	-	-
76	45	4095	2.53	941	54	4102	2.58	-	49	4139	2.55	1068	-	-	1068
77	43	4138	2.55	-	51	4233	2.61	-	39	4178	2.50	-	-	-	-
78	55	4193	2.59	985	48	4281	2.64	1002	61	4239	2.62	1147	-	-	1147
79	52	4245	2.62	-	46	4327	2.67	-	58	4297	2.65	-	-	-	-
80	53	4298	2.65	979	50	4377	2.70	1048	49	4346	2.68	1062	-	-	1062

Table B7. Continued.

Col.	R1				R2				R3			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
Day												
81	51	4349	2.68	-	52	4429	2.73	-	49	4395	2.71	-
82	47	4396	2.71	1017	49	4478	2.76	991	51	4446	2.74	-
83	49	4445	2.74	-	46	4524	2.79	-	47	4493	2.77	-
84	49	4494	2.77	-	53	4577	2.83	1032	49	4542	2.80	1037
85	53	4547	2.81	-	52	4629	2.86	-	53	4595	2.84	-
86	51	4598	2.84	1063	49	4678	2.89	1065	51	4646	2.87	1045
87	52	4650	2.87	-	48	4726	2.92	-	50	4696	2.90	-
88	52	4702	2.90	1030	52	4778	2.95	1078	49	4745	2.93	1052
89	53	4755	2.94	-	49	4827	2.98	-	45	4790	2.96	-
90	47	4802	2.96	1032	47	4874	3.01	1036	48	4838	2.99	1015
91	46	4848	2.99	-	44	4918	3.04	-	46	4884	3.01	-
92	45	4893	3.02	1117	48	3.07	3.07	-	47	4931	3.04	-
93	46	4939	3.05	-	51	5017	3.10	-	51	4982	3.08	-
94	48	4987	3.08	1068	49	5066	3.13	1046	53	5035	3.11	1129
95	49	5036	3.11	-	50	5116	3.16	-	54	5089	3.14	-
96	51	5087	3.14	1029	50	5166	3.19	1061	54	5143	3.17	1023

Table B7. Continued.

Col.	R1					R2					R3					
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
97	50	5137	3.17	-	52	5218	3.22	-	51	5194	3.21	-	51	5194	3.21	-
98	52	5189	3.20	1004	48	5266	3.25	1069	49	5243	3.24	1074	49	5243	3.24	1074
99	51	5240	3.23	-	46	5312	3.28	-	47	5290	3.27	-	47	5290	3.27	-
100	50	5290	3.27	981	45	5357	3.31	1019	48	5338	3.30	1039	48	5338	3.30	1039
101	51	5341	3.30	-	48	5405	3.34	-	49	5387	3.33	-	49	5387	3.33	-
102	49	5390	3.33	998	49	5454	3.37	1010	53	5440	3.36	1047	53	5440	3.36	1047
103	53	5443	3.35	-	52	5506	3.40	-	52	5492	3.39	-	52	5492	3.39	-
104	51	5474	3.38	907	51	5557	3.43	1024	50	5542	3.42	1117	50	5542	3.42	1117
105	53	5547	3.42	-	51	5608	3.46	-	53	5595	3.45	-	53	5595	3.45	-
106	54	5601	3.46	841	52	5660	3.49	958	46	5641	3.48	989	46	5641	3.48	989
107	51	5652	3.49	-	51	5711	3.53	-	51	5692	3.51	-	51	5692	3.51	-
108	50	5702	3.52	872	47	5758	3.55	947	49	5741	3.54	943	49	5741	3.54	943
109	50	5752	3.55	-	49	5807	3.58	-	48	5789	3.57	-	48	5789	3.57	-
110	47	5799	3.58	883	48	5855	3.61	892	51	5840	3.60	890	51	5840	3.60	890
111	48	5847	3.61	-	51	5906	3.65	-	52	5892	3.64	-	52	5892	3.64	-
112	49	5896	3.64	-	52	5958	3.68	852	53	5945	3.67	912	53	5945	3.67	912

Table B7. Continued.

Col. Day	R1				R2				R3			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
113	47	5943	3.67	-	51	6009	3.71	-	51	5996	3.70	-
114	52	5995	3.70	820	49	6058	3.74	772	49	6045	3.73	855
115	51	6046	3.73	-	48	6106	3.77	-	47	6092	3.76	-
116	51	6097	3.76	804	51	6157	3.80	739	51	6143	3.79	-
117	50	6147	3.79	-	52	6209	3.83	-	50	6193	3.82	-
118	51	6198	3.83	-	51	6260	3.86	-	51	6244	3.85	762
119	48	6246	3.86	-	47	6307	3.89	-	50	6294	3.89	-
120	53	6299	3.89	767	52	6359	3.93	758	49	6343	3.92	781
121	52	6351	3.92	-	48	6407	3.95	-	52	6395	3.95	-
122	49	6400	3.95	683	49	6456	3.99	745	51	6446	3.98	670
123	48	6448	3.98	-	51	6507	4.02	-	48	6494	4.01	-
124	50	6498	4.01	-	50	6557	4.05	-	49	6543	4.04	682
125	51	6549	4.04	-	52	6609	4.08	-	47	6590	4.07	-
126	48	6597	4.07	632	49	6658	4.11	682	51	6641	4.10	718
127	50	6647	4.10	-	48	6706	4.14	-	50	6691	4.13	-
128	49	6696	4.13	610	51	6757	4.17	752	49	6740	4.16	651

Table B8. Daily Data for Columns R4, R5, and R6.

Col. Day	R4				R5				R6			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
1	0	0	0.00	-	0	0	0.00	-	0	0	0.00	-
2	106	106	0.06	ND	71	71	0.04	-	94	94	0.06	-
3	90	196	0.12	-	112	183	0.11	-	119	213	0.13	-
4	73	269	0.17	-	87	270	0.17	ND	121	334	0.20	ND
5	70	339	0.21	ND	122	392	0.24	-	86	420	0.26	-
6	75	414	0.26	-	138	530	0.33	-	110	530	0.32	0.623
7	143	557	0.34	-	122	652	0.40	0.583	92	622	0.38	-
8	87	644	0.40	0.542	63	715	0.44	-	125	747	0.46	-
9	109	753	0.46	-	50	765	0.47	3.7	119	866	0.53	-
10	85	838	0.52	-	73	838	0.52	-	89	955	0.59	3.9
11	92	930	0.57	1.5	125	963	0.59	-	93	1048	0.64	-
12	126	1056	0.65	-	106	1069	0.66	44	84	1132	0.69	-
13	138	1194	0.74	-	90	1159	0.72	-	76	1208	0.74	-
14	107	1301	0.80	26	97	1256	0.78	94	71	1279	0.78	43
15	96	1397	0.86	-	115	1371	0.85	-	87	1376	0.84	-
16	118	1515	0.94	83	93	1464	0.90	169	99	1465	0.90	52

Table B8. Continued.

Col.	R4				R5				R6			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
17	93	1608	0.99	-	74	1538	0.95	-	112	1577	0.97	-
18	113	1721	1.06	-	85	1623	1.00	-	92	1669	1.02	-
19	91	1812	1.12	212	62	1685	1.04	253	115	1784	1.09	204
20	67	1879	1.16	-	59	1744	1.08	-	126	1910	1.17	-
21	84	1963	1.21	316	91	1835	1.13	288	58	1968	1.21	246
22	89	2052	1.27	-	81	1916	1.18	-	73	2041	1.25	-
23	116	2168	1.34	436	93	2009	1.23	411	67	2108	1.29	358
24	123	2291	1.41	-	114	2123	1.29	-	84	2192	1.34	-
25	110	2401	1.48	462	89	2212	1.37	572	96	2288	1.40	514
26	137	2538	1.57	-	95	2307	1.42	-	101	2389	1.47	-
27	109	2647	1.63	528	112	2419	1.49	543	92	2481	1.52	636
28	92	2739	1.69	-	127	2546	1.57	-	81	2562	1.57	-
29	116	2855	1.76	649	93	2639	1.63	607	109	2671	1.64	668
30	83	2930	1.81	-	69	2708	1.67	-	84	2755	1.69	-
31	96	3034	1.87	672	124	2832	1.75	763	130	2885	1.77	809
32	87	3121	1.93	-	139	2971	1.83	-	77	2962	1.82	-

Table B8. Continued.

Col.	R4				R5				R6			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
33	76	3197	1.97	776	121	3092	1.91	855	88	3050	1.87	799
34	79	3276	2.02	-	86	3178	1.97	-	67	3117	1.90	-
35	86	3362	2.06	843	92	3270	2.01	892	85	3202	1.96	852
36	97	3459	2.12	-	89	3359	2.06	-	91	3293	2.02	-
37	88	3547	2.18	-	97	3456	2.12	-	92	3385	2.08	-
38	93	3640	2.23	867	108	3564	2.19	903	89	3474	2.13	941
39	104	3744	2.30	-	103	3667	2.25	-	80	3554	2.18	-
40	111	3855	2.36	958	90	3757	2.30	873	76	3630	2.23	929
41	118	3973	2.44	-	82	3839	2.36	-	93	3723	2.28	-
42	123	4096	2.51	942	88	3927	2.41	912	99	3822	2.34	1021
43	131	4227	2.59	-	80	4007	2.46	-	88	3910	2.40	-
44	134	4361	2.68	963	96	4103	2.52	991	83	3993	2.45	967
45	120	4481	2.75	-	93	4196	2.57	-	90	4083	2.50	-
46	116	4597	2.82	1004	86	4282	2.63	1016	91	4174	2.56	913
47	121	4718	2.89	-	80	4362	2.68	-	84	4258	2.61	-
48	106	4824	2.96	1015	82	4444	2.73	979	78	4336	2.66	930

Table B8. Continued.

Col.	R4				R5				R6			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
Day												
49	96	4920	3.02	-	94	4538	2.78	-	90	4426	2.72	-
50	94	5014	3.10	982	106	4644	2.87	-	93	4519	2.79	1053
51	90	5104	3.15	-	110	4754	2.93	-	85	4604	2.84	-
52	92	5196	3.21	-	111	4865	3.00	922	91	4695	2.90	898
53	84	5280	3.26	-	114	4979	3.07	-	96	4791	2.96	-
54	86	5366	3.31	971	118	5097	3.15	937	107	4898	3.02	912
55	91	5457	3.37	-	109	5206	3.21	-	112	5010	3.09	-
56	103	5560	3.43	961	97	5303	3.27	877	117	5127	3.16	-
57	105	5665	3.50	-	102	5405	3.34	-	108	5235	3.23	-
58	106	5771	3.56	979	104	5509	3.40	849	106	5341	3.30	951
59	102	5873	3.63	-	100	5609	3.46	-	103	5444	3.36	-
60	95	5968	3.68	921	96	5705	3.52	863	94	5538	3.42	1038
61	90	6058	3.74	-	93	5798	3.58	-	91	5629	3.47	-
62	94	6152	3.80	952	94	5892	3.64	-	99	5728	3.54	983
63	96	6248	3.86	-	97	5989	3.70	-	96	5824	3.60	-
64	103	6351	3.92	906	95	6084	3.76	803	106	5930	3.66	948

Table B8. Continued.

Col.	R4				R5				R6			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
65	101	6452	3.98	-	102	6186	3.82	-	109	6039	3.73	-
66	104	6556	4.05	933	106	6292	3.88	-	104	6143	3.79	906
67	106	6662	4.11	-	103	6395	3.95	-	102	6245	3.85	-
68	101	6763	4.17	-	104	6499	4.01	817	98	6343	3.92	873
69	95	6858	4.23	-	109	6608	4.08	-	97	6440	3.98	-
70	91	6949	4.29	862	105	6713	4.14	773	101	6541	4.04	769
71	95	7044	4.35	-	107	6820	4.21	-	97	6638	4.10	-
72	98	7142	4.41	827	105	6925	4.27	722	95	6733	4.16	823
73	96	7238	4.47	-	103	7028	4.34	-	92	6825	4.21	-
74	100	7338	4.53	678	103	7131	4.40	712	98	6923	4.27	778
75	102	7440	4.59	-	100	7231	4.46	-	102	7025	4.34	-
76	106	7546	4.66	627	97	7328	4.52	576	99	7124	4.40	636
77	104	7650	4.72	-	94	7422	4.58	-	100	7224	4.46	-
78	97	7747	4.78	588	98	7520	4.64	548	96	7320	4.52	622
79	95	7842	4.84	-	104	7624	4.71	-	98	7418	4.58	-
80	98	7940	4.90	453	103	7727	4.77	506	101	7519	4.64	518

Table B8. Continued.

Col. Day	R4					R5					R6				
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	TCE Conc., mg/l
81	96	8036	4.96	-	105	7832	4.83	-	97	7616	4.70	-			
82	99	8135	5.02	402	99	7931	4.90	392	103	7719	4.76	453			
83	103	8238	5.09	-	96	8027	4.95	-	104	7823	4.83	-			
84	104	8342	5.15	412	98	8125	5.02	374	97	7920	4.89	427			
85	102	8444	5.21	-	97	8222	5.08	-	96	8016	4.95	-			
86	99	8543	5.27	305	96	8318	5.13	339	95	8111	5.01	449			
87	96	8639	5.33	-	95	8413	5.19	-	94	8205	5.06	-			
88	102	8741	5.40	220	99	8512	5.25	327	97	8302	5.12	395			
89	96	8837	5.45	-	102	8614	5.32	-	103	8405	5.19	-			
90	95	8932	5.51	203	101	8715	5.38	358	101	8506	5.25	386			
91	97	9029	5.57	-	98	8813	5.44	-	96	8602	5.31	-			
92	96	9125	5.63	227	100	8913	5.50	308	98	8700	5.37	-			
93	98	9223	5.69	-	101	9014	5.56	-	102	8802	5.43	-			
94	101	9324	5.76	212	103	9117	5.63	273	99	8901	5.49	338			
95	103	9427	5.82	-	99	9216	5.69	-	96	8997	5.55	-			
96	105	9532	5.88	218	95	9311	5.75	179	95	9092	5.61	264			

Table B8. Continued.

Col. Day	R4				R5				R6			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
97	104	9636	5.95	-	97	9408	5.81	-	101	9193	5.67	-
98	103	9739	6.01	189	99	9507	5.87	-	97	9290	5.73	247
99	97	9836	6.07	-	104	9611	5.93	-	100	9390	5.80	-
100	94	9930	6.13	212	102	9713	6.00	164	93	9483	5.85	249
101	98	10028	6.19	-	103	9816	6.06	-	94	9577	5.91	-
102	101	10129	6.25	174	103	9919	6.12	151	102	9679	5.97	223
103	103	10232	6.32	-	98	10017	6.18	-	96	9775	6.03	-
104	101	10333	6.38	147	96	10113	6.24	135	98	9873	6.09	202
105	103	10436	6.44	-	98	10211	6.30	-	103	9976	6.16	-
106	96	10532	6.50	139	100	10311	6.36	124	104	10080	6.22	180
107	99	10631	6.56	-	101	10412	6.43	-	103	10183	6.29	-
108	99	10730	6.62	102	97	10509	6.49	139	101	10284	6.35	187
109	105	10835	6.69	-	95	10604	6.55	-	99	10383	6.41	-
110	104	10939	6.75	123	98	10702	6.61	146	106	10489	6.47	189
111	100	11039	6.81	-	104	10806	6.67	-	103	10592	6.54	-
112	101	11140	6.88	110	105	10911	6.74	84	102	10694	6.60	163

Table B8. Continued.

Col.	R4					R5					R6					
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
Day																
113	100	11240	6.94	-	102	11013	6.80	-	100	10794	6.66	-	100	10794	6.66	-
114	99	11339	7.00	75	95	11108	6.86	87	101	10895	6.73	154	101	10895	6.73	154
115	97	11436	7.06	-	99	11207	6.92	-	99	10994	6.79	-	99	10994	6.79	-
116	98	11534	7.12	79	103	11310	6.98	93	100	11094	6.85	147	100	11094	6.85	147
117	97	11631	7.18	-	100	11470	7.04	-	97	11191	6.91	-	97	11191	6.91	-
118	101	11732	7.24	112	99	11509	7.10	104	98	11289	6.97	185	98	11289	6.97	185
119	102	11834	7.30	-	102	11611	7.17	-	97	11386	7.03	-	97	11386	7.03	-
120	100	11934	7.37	-	97	11708	7.23	96	103	11489	7.09	124	103	11489	7.09	124
121	99	12033	7.43	-	96	11804	7.29	-	104	11593	7.16	-	104	11593	7.16	-
122	101	12134	7.49	97	99	11903	7.35	78	101	11694	7.22	127	101	11694	7.22	127
123	99	12233	7.55	-	101	12004	7.41	-	94	11788	7.28	-	94	11788	7.28	-
124	97	12330	7.61	84	95	12099	7.47	139	103	11891	7.34	92	103	11891	7.34	92
125	100	12430	7.67	-	98	12197	7.53	-	101	11992	7.40	-	101	11992	7.40	-
126	101	12531	7.74	63	98	12295	7.59	84	94	12086	7.46	67	94	12086	7.46	67
127	98	12629	7.80	-	102	12397	7.65	-	97	12183	7.52	-	97	12183	7.52	-
128	97	12726	7.86	74	99	12496	7.71	68	99	12282	7.58	-	99	12282	7.58	-

Table B9. Daily Data for Columns R7, R8, and R9.

Col. Day	C7				C8				C9			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
1	0	0	0.00	-	0	0	0.00	-	0	0	0.00	-
2	75	75	0.05	-	56	56	0.03	-	62	62	0.04	-
3	31	106	0.06	-	62	118	0.07	ND	78	140	0.09	ND
4	74	180	0.11	ND	37	155	0.09	-	67	207	0.13	ND
5	90	270	0.17	0.189	69	224	0.14	ND	41	248	0.15	-
6	23	293	0.18	-	65	289	0.18	-	92	340	0.21	0.131
7	61	354	0.22	-	77	366	0.22	0.216	17	357	0.22	-
8	77	431	0.26	0.842	38	404	0.25	-	85	442	0.27	-
9	37	468	0.29	-	66	470	0.29	0.792	78	520	0.32	-
10	54	522	0.32	-	23	493	0.30	-	87	607	0.37	0.568
11	89	611	0.38	1.2	65	558	0.34	-	65	672	0.41	-
12	46	657	0.40	-	91	649	0.40	3.8	27	699	0.43	-
13	12	669	0.41	-	48	697	0.43	-	38	737	0.45	-
14	93	762	0.47	22	69	766	0.47	18	79	816	0.50	1.6
15	35	797	0.49	-	60	826	0.51	-	31	847	0.52	-
16	80	877	0.54	68	59	885	0.54	24	64	911	0.56	41

Table B9. Continued.

Col.	C7				C8				C9			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
Day												
17	66	943	0.58	-	40	925	0.57	-	24	935	0.57	-
18	78	1021	0.63	-	37	962	0.59	-	63	998	0.61	-
19	50	1071	0.66	153	62	1024	0.63	33	50	1048	0.64	18
20	14	1085	0.67	-	38	1062	0.65	-	36	1084	0.66	-
21	68	1153	0.71	234	71	1133	0.70	78	50	1134	0.70	48
22	37	1190	0.73	-	43	1176	0.72	-	41	1175	0.72	-
23	71	1261	0.77	217	57	1233	0.76	113	71	1246	0.76	77
24	36	1297	0.80	-	31	1264	0.78	-	65	1311	0.80	-
25	70	1367	0.84	342	54	1318	0.81	154	60	1371	0.84	229
26	29	1396	0.86	-	40	1358	0.83	-	57	1428	0.88	-
27	64	1460	0.90	325	50	1408	0.86	191	59	1487	0.91	406
28	19	1479	0.91	-	36	1444	0.89	-	53	1540	0.94	-
29	58	1537	0.94	396	71	1515	0.93	282	67	1607	0.99	497
30	16	1553	0.95	-	30	1545	0.95	-	29	1636	1.00	-
31	50	1603	0.98	408	63	1608	0.99	335	70	1706	1.05	615
32	31	1634	1.00	-	37	1645	1.01	-	26	1732	1.06	-

Table B9. Continued.

Col. Day	C7				C8				C9			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
33	57	1691	1.04	462	71	1716	1.05	527	57	1789	1.10	653
34	39	1730	1.07	-	35	1751	1.07	-	42	1831	1.12	-
35	50	1780	1.09	522	63	1814	1.11	506	70	1901	1.17	682
36	56	1836	1.13	-	69	1883	1.16	-	66	1967	1.21	-
37	63	1899	1.16	-	53	1936	1.19	-	53	2020	1.24	-
38	59	1958	1.20	761	50	1986	1.22	541	57	2077	1.27	788
39	53	2011	1.23	-	42	2028	1.24	-	61	2138	1.31	-
40	46	2057	1.26	892	37	2065	1.27	623	55	2193	1.34	812
41	56	2113	1.30	-	54	2119	1.30	-	59	2252	1.38	-
42	62	2175	1.33	886	58	2177	1.34	744	55	2307	1.42	913
43	51	2226	1.37	-	63	2240	1.37	-	53	2360	1.45	-
44	45	2271	1.39	Saturated	68	2308	1.42	852	46	2406	1.47	928
45	(Removed from service)				59	2367	1.45	-	54	2460	1.51	-
46					53	2420	1.48	803	58	2518	1.54	941
47					42	2462	1.51	-	66	2584	1.58	-
48					47	2509	1.54	-	52	2636	1.62	973

Table B9. Continued.

Col.	C7				C8				C9			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
49					54	2563	1.57	-	44	2680	1.64	-
50					52	2615	1.61	838	55	2735	1.69	923
51					58	2673	1.65	-	57	2792	1.72	-
52					55	2728	1.68	948	60	2852	1.76	952
53					59	2787	1.72	-	62	2914	1.80	-
54					63	2850	1.76	992	65	2979	1.84	978
55					57	2907	1.79	-	67	3046	1.88	-
56					61	2968	1.83	-	63	3109	1.92	-
57					53	3021	1.86	-	59	3168	1.96	-
58					50	3071	1.90	996	51	3219	1.99	988
59					57	3128	1.93	-	53	3272	2.02	-
60					55	3183	1.96	978	51	3323	2.05	994
61					53	3236	2.00	-	55	3378	2.08	-
62					55	3291	2.03	1046	56	3434	2.12	929
63					52	3343	2.06	-	53	3487	2.15	-
64					49	3392	2.09	-	54	3541	2.19	1011

Table B9. Continued.

Col.	C7				C8				C9			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
Day												
65					50	3443	2.12	-	52	3593	2.22	-
66					52	3494	2.16	987	49	3642	2.25	-
67					54	3548	2.19	-	47	3689	2.28	-
68					56	3604	2.22	-	49	3738	2.31	965
69					51	3655	2.26	-	50	3788	2.34	-
70					54	3709	2.29	1053	56	3844	2.37	1022
71					53	3762	2.32	-	53	3897	2.41	-
72					56	3818	2.36	941	49	3946	2.44	1058
73					49	3867	2.39	-	48	3994	2.47	-
74					46	3913	2.42	996	46	4040	2.49	979
75					48	3961	2.45	-	50	4090	2.52	-
76					47	4008	2.47	-	49	4139	2.55	1092
77					49	4057	2.50	-	47	4186	2.58	-
78					54	4111	2.54	1018	54	4240	2.62	-
79					51	4162	2.57	-	53	4293	2.65	-
80					50	4212	2.60	985	52	4345	2.68	1053

Table B9. Continued.

Col.	C7				C8				C9			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
81					51	4263	2.63	-	54	4399	2.72	-
82					48	4311	2.66	1025	47	4446	2.74	1060
83					47	4358	2.69	-	51	4497	2.78	-
84					55	4413	2.72	1039	51	4596	2.84	-
85					48	4461	2.75	-	48	4596	2.84	-
86					47	4508	2.78	978	47	4643	2.87	1056
87					46	4554	2.81	-	51	4694	2.90	-
88					45	4599	2.84	1019	54	4748	2.93	1063
89					47	4646	2.87	-	53	4801	2.96	-
90					48	4694	2.90	1038	52	4853	3.00	954
91					51	4745	2.93	-	53	4906	3.03	-
92					53	4798	2.96	1021	50	4956	3.06	1040
93					52	4850	2.99	-	51	5007	3.09	-
94					54	4904	3.03	1027	49	5056	3.12	-
95					55	4959	3.06	-	47	5103	3.15	-
96					51	5010	3.09	981	48	5151	3.18	1043

Table B9. Continued.

Col.	C7					C8					C9				
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV
97					52	5062	3.12	-	49	520	3.21	-			
98					49	5111	3.15	990	52	5252	3.24	1027			
99					50	5161	3.19	-	51	5303	3.27	-			
100					51	5212	3.22	1004	52	5355	3.31	1036			
101					53	5265	3.25	-	51	5406	3.34	-			
102					49	5314	3.28	971	50	5456	3.37	1061			
103					52	5366	3.31	-	48	5504	3.40	-			
104					51	5417	3.34	1106	53	5557	3.43	1059			
105					51	5468	3.38	-	52	5609	3.46	-			
106					47	5515	3.40	998	49	5658	3.49	1045			
107					49	5564	3.43	-	51	5709	3.52	-			
108					54	5618	3.47	1013	50	5759	3.55	1023			
109					53	5671	3.50	-	51	5810	3.59	-			
110					47	5718	3.53	1076	47	5857	3.62	1069			
111					49	5767	3.56	-	48	5905	3.65	-			
112					49	5816	3.59	1031	51	5956	3.68	1048			

Table B9. Continued.

Col.	C7				C8				C9			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
113					50	5866	3.62	-	50	6006	3.71	-
114					50	5916	3.65	1004	53	6059	3.74	1043
115					50	5966	3.68	-	51	6110	3.77	-
116					47	6013	3.71	1032	50	6160	3.80	1071
117					48	6061	3.74	-	48	6208	3.83	-
118					48	6109	3.77	-	49	6257	3.86	-
119					51	6160	3.80	-	52	6309	3.89	-
120					50	6210	3.83	994	49	6358	3.92	1052
121					52	6262	3.87	-	47	6405	3.95	-
122					51	6313	3.90	1017	53	6458	3.99	1017
123					50	6363	3.93	-	52	6510	4.02	-
124					48	6411	3.96	-	49	6559	4.05	-
125					51	6462	3.99	-	50	6609	4.08	-
126					47	6509	4.02	952	51	6660	4.11	1050
127					50	6559	4.05	-	48	6708	4.14	-
128					51	6610	4.08	1023	52	6760	4.17	1078

Table B10. Daily Data for Columns R10, R11, and R12.

Col. Day	R10				R11				R12			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
1	0	0	0.00	-	0	0	0.00	-	0	0	0.00	-
2	82	82	0.05	-	75	75	0.05	-	70	70	0.04	-
3	83	165	0.10	ND	117	192	0.12	ND	132	202	0.12	ND
4	76	241	0.15	-	86	278	0.17	-	91	293	0.18	ND
5	22	263	0.16	ND	130	408	0.25	0.190	83	376	0.23	-
6	137	400	0.24	-	83	491	0.30	-	113	489	0.30	9.7
7	92	492	0.30	-	125	616	0.38	2.1	92	581	0.36	-
8	82	574	0.35	2.3	142	758	0.46	-	137	718	0.44	-
9	121	695	0.43	-	93	851	0.52	65	86	804	0.49	-
10	138	833	0.51	-	127	978	0.60	-	131	935	0.57	101
11	93	926	0.57	32	105	1083	0.66	-	126	1061	0.65	-
12	114	1040	0.64	-	112	1195	0.73	122	119	1180	0.72	83
13	122	1162	0.71	205	88	1283	0.79	-	136	1316	0.81	-
14	129	1291	0.79	263	91	1374	0.84	432	115	1431	0.88	339
15	109	1400	0.86	-	90	1464	0.90	-	83	1514	0.93	-
16	89	1489	0.91	506	79	1543	0.95	592	121	1635	1.00	471

Table B10. Continued.

Col. Day	R10				R11				R12			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
17	84	1573	0.96	-	102	1645	1.01	-	92	1727	1.06	-
18	123	1696	1.04	390	122	1767	1.08	-	80	1807	1.11	495
19	118	1814	1.11	646	84	1851	1.14	604	74	1881	1.15	753
20	92	1906	1.17	-	88	1939	1.19	-	68	1949	1.20	-
21	77	1983	1.22	690	88	2027	1.24	812	128	2077	1.27	875
22	81	2064	1.27	-	103	2130	1.31	-	119	2196	1.35	-
23	96	2160	1.32	802	128	2258	1.38	822	103	2299	1.41	930
24	87	2247	1.38	-	89	2347	1.44	-	90	2389	1.47	-
25	135	2382	1.46	855	78	2425	1.49	818	117	2506	1.54	1055
26	126	2508	1.54	-	74	2499	1.53	-	73	2579	1.58	-
27	94	2602	1.60	872	113	2612	1.60	942	89	2668	1.64	988
28	79	2681	1.64	-	94	2706	1.66	-	82	2750	1.69	-
29	118	2799	1.72	923	131	2837	1.74	982	83	2833	1.74	1047
30	75	2874	1.76	-	90	2927	1.80	-	94	2927	1.80	-
31	131	3005	1.84	972	115	3042	1.87	915	105	3032	1.86	1024
32	114	3119	1.91	-	99	3141	1.93	-	83	3115	1.91	-

Table B10. Continued.

Col. Day	R10					R11					R12				
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
33	123	3242	1.99	994	74	3215	1.97	1041	70	3185	1.95	1122			
34	96	3338	2.05	-	82	3297	2.02	-	122	3307	2.02	-			
35	91	3429	2.10	1027	76	3373	2.07	1008	110	3417	2.09	1080			
36	87	3516	2.16	-	71	3444	2.11	-	114	3531	2.17	-			
37	95	3611	2.22	-	81	3525	2.16	-	96	3627	2.22	-			
38	109	3720	2.28	986	87	3612	2.22	1036	91	3718	2.28	1090			
39	116	3836	2.35	-	94	3706	2.27	-	83	3801	2.33	-			
40	117	3953	2.42	1041	92	3798	2.33	1068	90	3891	2.39	1193			
41	107	4060	2.49	-	98	3896	2.39	-	81	3972	2.44	-			
42	96	4156	2.55	1036	94	3990	2.45	-	96	4068	2.50	1154			
43	86	4242	2.60	-	109	4099	2.52	-	92	4160	2.55	-			
44	80	4322	2.65	1009	101	4200	2.58	993	103	4263	2.62	1120			
45	88	4410	2.71	-	93	4293	2.63	-	96	4359	2.69	-			
46	94	4504	2.76	1019	103	4396	2.70	1080	(Removed from service - broken.)						
47	108	4612	2.83	-	110	4506	2.76	-							
48	114	4726	2.90	979	137	4643	2.85	1026							

Table B10. Continued.

Col. Day	R10				R11				R12			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
49	121	4847	2.97	-	124	4767	2.92	-				
50	113	4960	3.06	1020	115	4882	3.01	1047				
51	112	5072	3.13	-	108	4990	3.08	-				
52	106	5178	3.20	-	104	5094	3.14	1006				
53	100	5278	3.26	-	101	5195	3.21	-				
54	95	5373	3.32	1054	105	5300	3.27	978				
55	93	5466	3.37	-	96	5396	3.33	-				
56	88	5554	3.43	1043	88	5484	3.39	1066				
57	94	5648	3.49	-	94	5578	3.44	-				
58	96	5744	3.55	1012	98	5676	3.50	1079				
59	99	5843	3.61	-	96	5772	3.56	-				
60	103	5946	3.67	1038	96	5868	3.62	-				
61	104	6050	3.73	-	102	5970	3.69	-				
62	109	6159	3.80	-	95	6065	3.74	975				
63	111	6270	3.87	-	94	6159	3.80	-				
64	107	6377	3.94	1136	105	6264	3.87	1031				

Table B10. Continued.

Col. Day	R10				R11				R12			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
65	105	6482	4.00	-	103	6367	3.93	-				
66	99	6581	4.06	1032	104	6471	3.99	-				
67	100	6681	4.12	-	98	6569	4.05	-				
68	106	6787	4.19	-	96	6665	4.11	1012				
69	108	6895	4.26	-	98	6763	4.17	-				
70	101	6996	4.32	998	92	6855	4.23	967				
71	109	7105	4.39	-	95	6950	4.29	-				
72	105	7210	4.45	1046	99	7049	4.35	1018				
73	101	7311	4.51	-	105	7154	4.42	-				
74	95	7406	4.57	1023	98	7252	4.48	992				
75	100	7506	4.63	-	96	7348	4.54	-				
76	97	7603	4.69	1038	103	7451	4.60	1078				
77	96	7699	4.75	-	100	7551	4.66	-				
78	91	7790	4.81	1011	104	7655	4.73	963				
79	96	7886	4.87	-	101	7756	4.79	-				
80	106	7992	4.93	982	97	7853	4.85	1014				

Table B10. Continued.

Col.	R10					R11					R12				
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV
81	101	8093	5.00	-	96	7949	4.91	-							
82	97	8190	5.06	1037	99	8048	4.97	1063							
83	98	8288	5.12	-	102	8150	5.03	-							
84	105	8393	5.18	1003	103	8253	5.09	1153							
85	103	8496	5.24	-	109	8362	5.16	-							
86	99	8595	5.31	1019	103	8465	5.23	1047							
87	102	8697	5.37	-	106	8571	5.29	-							
88	100	8797	5.43	984	97	8668	5.35	1059							
89	96	8893	5.49	-	99	8767	5.41	-							
90	95	8988	5.55	979	98	8865	5.47	1033							
91	93	9081	5.61	-	96	8961	5.53	-							
92	103	9184	5.67	1026	99	9060	5.59	1018							
93	104	9288	5.73	-	102	9162	5.66	-							
94	106	9394	5.80	968	104	9266	5.72	1043							
95	101	9495	5.86	-	105	9371	5.78	-							
96	98	9593	5.92	952	101	9472	5.85	1019							

Table B10. Continued.

Col.	R10					R11					R12				
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	TCE Conc., mg/l
97	98	9691	5.98	-	97	9569	5.91	-							
98	101	9792	6.04	1038	94	9663	5.96	1025							
99	104	9896	6.11	-	98	9761	6.03	-							
100	98	9994	6.17	931	100	9861	6.09	1053							
101	97	10091	6.23	-	103	9964	6.15	-							
102	102	10193	6.29	1013	101	10065	6.21	1029							
103	98	10291	6.35	-	97	10162	6.27	-							
104	99	10390	6.41	978	102	10264	6.34	987							
105	101	10491	6.48	-	101	10365	6.40	-							
106	99	10590	6.54	918	102	10467	6.46	1017							
107	103	10693	6.60	-	103	10570	6.52	-							
108	102	10795	6.66	941	96	10666	6.58	1043							
109	102	10897	6.73	-	98	10764	6.64	-							
110	100	10997	6.79	878	97	10861	6.70	1072							
111	98	11095	6.85	-	103	10964	6.77	-							
112	99	11194	6.91	792	95	11059	6.83	966							

Table B10. Continued.

Col. Day	R10				R11				R12			
	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l	Vol. of Eff., ml	Cum. Eff., ml	Cum. Eff., PV	TCE Conc., mg/l
113	101	11295	6.97	-	97	11156	6.89	-				
114	100	11395	7.03	807	96	11252	6.95	850				
115	97	11492	7.09	-	101	11353	7.01	-				
116	102	11594	7.16	723	100	11453	7.07	792				
117	101	11695	7.22	-	102	11555	7.13	-				
118	103	11798	7.28	685	102	11657	7.20	623				
119	96	11894	7.34	-	99	11756	7.26	-				
120	98	11992	7.40	543	100	11856	7.32	628				
121	98	12090	7.46	-	101	11957	7.38	-				
122	99	12189	7.52	469	99	12056	7.44	590				
123	102	12291	7.59	-	100	12156	7.50	-				
124	101	12392	7.65	-	101	12257	7.57	605				
125	100	12492	7.71	-	96	12353	7.63	-				
126	97	12589	7.77	482	99	12452	7.69	494				
127	99	12688	7.83	-	102	12554	7.75	-				
128	101	12789	7.89	495	100	12654	7.81	463				

Table B11. Daily Effluent Volume from Russell
Soil Control Column.

Day	Effluent Collected, ml	Day	Effluent Collected, ml	Day	Effluent Collected, ml
1	0	24	121	47	108
2	32	25	*120	48	106
3	*77	26	103	49	110
4	130	27	91	50	105
5	68	28	90	51	101
6	117	29	84	52	103
7	135	30	71	53	95
8	106	31	95	54	96
9	85	32	86	55	93
10	98	33	98	56	91
11	125	34	93	57	*88
12	*123	35	*94	58	86
13	103	36	89	59	80
14	111	37	99	60	94
15	137	38	92	61	97
16	115	39	87	62	95
17	122	40	96	63	102
18	129	41	108	64	106
19	*116	42	118	65	109
20	144	43	131	66	111
21	136	44	120	67	112
22	127	45	113	68	109
23	139	46	104	69	106

*Indicates sample taken for TCE analysis. No TCE detected
in any samples.

Table B11. Continued.

Day	Effluent Collected, ml	Day	Effluent Collected, ml	Day	Effluent Collected, ml
70	107	93	99	116	98
71	103	94	97	117	100
72	105	95	95	118	*101
73	97	96	94	119	103
74	96	97	96	120	102
75	100	98	99	121	107
76	102	99	104	122	101
77	94	100	97	123	98
78	97	101	98	124	96
79	103	102	98	125	*97
80	98	103	102	126	99
81	100	104	101	127	102
82	97	105	99	128	100
83	104	106	*101	129	*104
84	*101	107	102	130	98
85	96	108	96	131	102
86	95	109	98	132	103
87	94	110	99		
88	94	111	101		
89	98	112	100		
90	106	113	102		
91	102	114	98		
92	103	115	96		

*Indicates sample taken for TCE analysis. No TCE detected in any samples.

Table B12. TCE Time of Saturation

Time of Contact, hours	TCE Concentration (as fraction of maximum TCE solubility in water, 1100 mg/l)
0.5	0.183
1.0	0.196
1.5	0.164
2.0	0.207
3.0	0.268
4.0	0.294
5.0	0.463
7.5	0.588
10.0	0.601
13.0	0.660
17.0	0.705
24.0	0.896
28.0	1.024
36.0	0.983
48.0	0.972
53.0	0.990

Table B13. pH of Chalmers Soil Column Effluent.

Day	C1	C2	C3	C4	C5	C6	C7	C8	C9	C10	C11	C12	Control
4	6.09	6.23	6.56	6.26	6.02	6.61	7.25	6.15	6.31	6.38	6.28	5.97	6.45
14	6.17	6.39	5.91	6.19	6.24	6.28	6.67	6.23	6.12	6.79	7.21	6.21	6.27
21	6.13	6.72	6.43	6.09	5.83	6.12	6.28	6.06	6.78	7.11	7.23	6.89	6.78
29	6.39	6.12	6.14	6.03	6.22	6.57	6.83	6.47	7.23	5.92	6.17	6.28	7.33
36	6.05	6.33	5.89	6.58	6.20	6.15	6.46	6.62	6.18	6.12	6.82	6.35	6.84
44	6.16	6.62	6.17	5.97	6.31	6.19	6.74	6.41	6.82	5.90	7.16	6.36	7.22
53	6.42	5.93	6.21	6.13	7.19	5.82	6.33	7.21	6.69	-	5.93	7.28	6.07
62	6.23	5.38	6.37	6.21	6.34	5.93	6.19	6.48	7.25	-	6.81	6.12	6.50
70	6.30	6.24	6.22	5.86	6.65	6.87	7.27	6.35	7.30	-	5.80	6.27	5.99
76	6.59	6.35	6.33	6.28	6.81	6.26	6.89	6.25	7.15	-	6.19	7.31	6.47
82	5.94	6.41	6.63	6.34	6.03	6.47	7.35	6.64	6.39	-	6.40	6.38	6.62
89	6.36	5.32	6.74	6.61	5.62	6.81	7.49	6.93	6.43	-	6.34	6.47	7.31
94	6.63	5.73	6.58	6.72	6.54	7.08	6.65	7.12	6.71	-	6.82	6.29	6.90
100	6.91	6.61	5.70	6.37	7.27	6.67	6.17	6.69	6.23	-	7.39	5.76	5.92
106	6.27	6.39	6.46	6.21	6.74	6.31	6.58	5.85	6.59	-	6.68	6.42	6.34
114	5.52	6.26	6.35	5.83	5.99	6.24	6.36	6.16	6.32	-	6.46	6.47	6.66
122	6.33	6.38	6.29	6.22	6.80	6.28	-	6.19	7.27	-	6.37	7.59	6.71
128	6.01	6.19	6.04	6.18	6.55	6.57	-	6.86	6.35	-	6.41	6.53	7.09

Table B14. pH of Russell Soil Column Effluent.

Day	R1	R2	R3	R4	R5	R6	R7	R8	R9	R10	R11	R12	Control
3	6.36	6.20	6.14	6.63	6.27	6.73	6.08	5.92	6.19	6.32	6.25	5.95	6.42
13	6.12	6.28	6.39	6.51	6.16	6.27	6.17	6.14	6.23	6.20	5.97	6.40	6.06
24	6.29	6.35	6.42	6.17	6.12	6.19	6.14	6.28	6.81	6.48	6.14	6.36	6.00
32	5.95	6.41	6.46	6.24	6.22	6.48	6.21	6.15	6.10	6.19	6.01	6.82	5.87
39	6.27	6.11	6.39	6.32	6.45	6.59	6.30	6.03	6.02	6.17	5.90	6.01	6.48
47	6.49	5.91	5.74	6.41	6.29	6.17	-	6.09	5.97	6.25	6.08	-	6.67
54	7.23	6.58	6.12	6.64	7.23	6.35	-	6.04	6.85	6.16	6.22	-	6.15
63	6.42	6.41	6.26	6.20	6.40	6.16	-	6.15	6.27	6.08	5.94	-	6.72
71	6.28	6.32	6.19	5.81	6.63	6.46	-	6.21	6.44	6.25	6.23	-	6.43
77	6.34	6.08	6.36	6.17	6.38	6.55	-	5.83	6.63	6.06	6.44	-	5.91
83	5.62	6.81	6.28	6.43	6.19	6.23	-	6.34	6.49	6.34	6.29	-	6.57
90	6.18	6.23	7.37	6.29	5.92	6.51	-	6.26	6.86	5.90	6.82	-	6.63
95	6.82	5.41	6.46	7.16	5.71	6.34	-	6.38	6.67	5.84	6.64	-	6.52
101	6.91	5.62	6.54	6.58	6.83	6.03	-	6.27	6.90	5.91	6.85	-	6.03
107	6.47	5.79	6.30	6.91	6.40	6.32	-	6.75	7.25	6.15	6.66	-	6.14
115	6.65	6.68	6.25	6.80	6.57	6.65	-	6.89	6.45	6.31	7.21	-	6.44
123	6.58	6.52	6.50	6.40	6.29	6.83	-	7.16	6.51	6.20	6.32	-	5.98
129	6.11	6.34	6.09	6.33	5.96	6.40	-	6.55	6.39	6.67	6.27	-	6.05

Table B15. Effluent Volume and TCE Concentrations Used to Determine TCE Eluted from Columns by Simpson's Approximation.

TCE Concentration, mg/l (from Figures 15-22)								
Cum. Eff. Vol., l	C1-3	C4-6	C7-9	C10-12	R1-3	R4-6	R7-9	R10-12
0.00	0	0	0	0	0	0	0	0
0.33	0	0	0	0	0	0	0	0
0.67	0	0	5	2	2	2	5	15
1.00	3	10	22	25	22	15	35	60
1.33	50	32	80	150	80	70	205	250
1.67	155	100	270	300	275	200	465	480
2.00	235	210	435	450	432	350	710	715
2.33	325	312	530	570	560	440	865	860
2.67	405	420	690	670	670	620	940	945
3.00	500	510	780	760	760	760	970	1000
3.33	600	615	845	835	840	850	990	1015
3.67	680	730	905	900	910	915	1005	1040
4.00	790	810	950	950	960	950	1005	1040
4.33	820	850	985	990	1010	925	1010	1035
4.67	830	880	1020	1005	1035	980	1015	1035
5.00	780	860	1035	1010	1045	980	1030	1035
5.33	700	815	1050	1010	1035	960	1030	1035
5.67	660	720	1050	1000	960	940	1035	1032
6.00	590	670	1050	990	840	910	1040	1030
6.33	503	605	1050	985	755	860	1040	1030
6.67	470	550	1050	980	670	800	1040	1030
7.00		510		980		720		1030
7.33		470		990		635		1030
7.67		430		990		520		1030
8.00		400		995		440		1030
8.33		370		1000		370		1030
8.67		340		990		315		1030
9.00		320		975		265		1028
9.33		295		950		230		1028
9.67		270		915		195		1028
10.00		240		875		170		1020
10.33		215		830		150		990
10.67		205		770		130		940
11.00		180		715		110		870
11.33		160		640		105		800
11.67		140		570		80		710
12.00		120		510		65		610
12.33		105		450		55		530
12.67		100		400		40		460
13.00		98		340		35		395

Table B16. Cumulative Mass of TCE Eluted from Chalmers Soil Columns.

Cum. Eff. Vol., l	TCE Eluted in Column Group							
	C1-3		C4-6		C7-9		C10-12	
	Mass, g	%	Mass, g	%	Mass, g	%	Mass, g	%
0.00	0.00	0.0	0.00	0.0	0.00	0.0	0.00	0.0
0.33	0.00	0.0	0.00	0.0	0.00	0.0	0.00	0.0
0.67	0.00	0.0	0.00	0.0	0.00	0.0	0.00	0.0
1.00	0.00	0.0	0.01	0.1	0.01	0.1	0.01	0.1
1.33	0.01	0.1	0.01	0.1	0.02	0.1	0.03	0.2
1.67	0.04	0.5	0.03	0.4	0.07	0.5	0.10	0.7
2.00	0.11	1.5	0.08	1.1	0.20	1.4	0.23	1.6
2.33	0.20	2.7	0.16	2.2	0.35	2.4	0.40	2.7
2.67	0.32	4.4	0.28	3.8	0.55	3.8	0.60	4.1
3.00	0.46	6.3	0.44	6.0	0.80	5.5	0.84	5.8
3.33	0.65	8.9	0.62	8.5	1.06	7.3	1.10	7.5
3.67	0.86	11.8	0.85	11.6	1.36	9.3	1.39	9.5
4.00	1.10	15.1	1.10	15.1	1.66	11.4	1.69	11.6
4.33	1.37	18.8	1.38	18.9	1.98	13.6	2.02	13.8
4.67	1.64	22.5	1.66	22.7	2.31	15.8	2.34	16.0
5.00	1.91	26.2	1.95	26.7	2.65	18.2	2.68	18.4
5.33	2.15	29.5	2.23	30.5	2.99	20.5	3.01	20.6
5.67	2.38	32.6	2.48	34.0	3.34	22.9	3.34	22.9
6.00	2.58	35.3	2.71	37.1	3.69	25.3	3.67	25.1
6.33	2.77	37.9	2.93	40.1	4.04	27.7	4.00	27.4
6.67	2.94	40.3	3.10	42.5	4.38	30.0	4.32	29.6
7.00			3.29	45.1			4.64	31.8
7.33			3.44	47.1			4.97	34.0
7.67			3.60	49.3			5.30	36.3
8.00			3.73	51.1			5.62	38.5
8.33			3.86	52.9			5.95	40.8
8.67			3.97	54.4			6.28	43.0
9.00			4.09	56.0			6.61	45.3
9.33			4.18	57.3			6.92	47.4
9.67			4.28	58.6			7.23	49.5
10.00			4.36	59.7			7.52	51.5
10.33			4.44	60.8			7.81	53.5
10.67			4.50	61.6			8.07	55.3
11.00			4.57	62.6			8.32	57.0
11.33			4.62	63.3			8.54	58.5
11.67			4.68	64.1			8.74	59.9
12.00			4.72	64.7			8.92	61.6
12.33			4.76	65.2			9.08	62.2
12.67			4.79	65.6			9.21	63.1
13.00			4.84	66.3			9.34	64.0

Table B17. Cumulative Mass of TCE Eluted from Russell Soil Columns.

Cum. Eff. Vol., l	TCE Eluted in Column Group							
	R1-3		R4-6		R7-9		R10-12	
	Mass, g	%	Mass, g	%	Mass, g	%	Mass, g	%
0.00	0.00	0.0	0.00	0.0	0.00	0.0	0.00	0.0
0.33	0.00	0.0	0.00	0.0	0.00	0.0	0.00	0.0
0.67	0.00	0.0	0.00	0.0	0.01	0.1	0.02	0.1
1.00	0.01	0.1	0.01	0.1	0.01	0.1	0.03	0.2
1.33	0.02	0.3	0.01	0.1	0.04	0.3	0.06	0.4
1.67	0.07	1.0	0.06	0.8	0.15	1.0	0.18	1.2
2.00	0.20	2.7	0.15	2.1	0.34	2.3	0.37	2.5
2.33	0.35	4.8	0.28	3.8	0.61	4.2	0.64	4.4
2.67	0.56	7.7	0.45	6.2	0.91	6.2	0.94	6.4
3.00	0.79	10.8	0.69	9.5	1.22	8.4	1.26	8.6
3.33	1.06	14.5	0.95	13.0	1.55	10.6	1.59	10.9
3.67	1.35	18.5	1.24	17.0	1.88	12.9	1.94	13.3
4.00	1.66	22.7	1.55	21.2	2.21	15.1	2.27	15.5
4.33	1.98	27.1	1.86	25.5	2.54	17.4	2.62	17.9
4.67	2.33	31.9	2.17	29.7	2.87	19.7	2.96	20.3
5.00	2.66	36.4	2.51	34.4	3.21	22.0	3.30	22.6
5.33	3.01	41.2	2.81	38.5	3.55	24.3	3.64	24.9
5.67	3.34	45.8	3.14	43.0	3.89	26.6	3.99	27.3
6.00	3.64	49.9	3.43	47.0	4.24	29.0	4.32	29.6
6.33	3.90	53.4	3.74	51.2	4.58	31.4	4.67	32.0
6.67	4.04	55.3	3.99	54.7	4.92	33.7	5.08	34.8
7.00			4.26	58.4			5.35	36.6
7.33			4.47	61.2			5.68	38.9
7.67			4.68	64.1			6.03	41.3
8.00			4.82	66.0			6.36	43.6
8.33			4.97	68.1			6.71	46.0
8.67			5.06	69.3			7.04	48.2
9.00			5.18	71.0			7.39	50.6
9.33			5.24	71.8			7.72	52.9
9.67			5.33	73.0			8.06	55.2
10.00			5.37	73.6			8.40	57.5
10.33			5.44	74.5			8.74	59.9
10.67			5.47	74.9			9.05	62.0
11.00			5.53	75.8			9.35	64.0
11.33			5.54	75.9			9.62	65.9
11.67			5.60	76.7			9.88	67.7
12.00			5.60	76.7			10.09	69.1
12.33			5.64	77.3			10.28	70.4
12.67			5.65	77.4			10.44	71.4
13.00			5.66	77.5			10.47	72.5

Table B18. Cumulative Mass of TCE Eluted Based Upon Comparison to a CSTR (53).

CEV, ^a l	Chalmers % Eluted	Russell % Eluted	CEV, l	Chalmers % Eluted	Russell % Eluted
0.00	0	0	3.9	90	91
0.05	3	3	4.2	91	93
0.1	6	6	4.5	93	94
0.2	11	12	4.8	94	94
0.3	16	17	5.1	95	96
0.4	21	22	5.4	96	96
0.5	25	27	5.7	96	97
0.6	29	31	6.0	97	98
0.7	33	35	6.3	97	98
0.8	37	39	6.6	98	98
0.9	41	43	6.9	98	99
1.2	50	52	7.2	98	99
1.5	58	60	7.5	99	99
1.8	65	67	7.8	99	99
2.4	75	77	8.4	99	99
2.7	79	81	8.7	99	100
3.0	83	84	9.0	99	-
3.3	85	87	9.3	100	-
3.6	88	89			

Note: ^aCEV = Cumulative Effluent Volume

Table B19. Ammonia Concentrations in Soil Column Effluents.

Ammonia Concentration, mg/l, for indicated days									
Col.	Day 71	Day 78	Day 83	Day 87	Day 92	Day 97	Day 104	Day 113	Day 122
<u>Chalmers Soil</u>									
CC	0.39	0.31	0.44	0.37	0.29	0.48	0.33	0.28	0.36
*C1	0.72	0.51	0.87	1.41	2.86	3.97	9.21	9.73	7.62
C2	0.63	0.68	-	-	-	0.83	-	0.56	-
C3	0.88	0.52	-	-	0.49	-	0.72	0.51	-
C4	0.75	0.61	-	-	0.53	-	-	0.44	-
C5	0.59	0.71	4.95	8.73	7.91	8.23	11.4	7.49	2.12
C6	0.58	0.39	-	0.68	-	-	0.45	0.32	-
*C7	0.69	0.48	0.72	1.96	1.74	2.94	8.47	8.33	9.14
C8	0.60	0.55	-	0.77	-	-	0.71	0.58	-
C9	0.46	0.52	-	-	-	0.68	-	0.57	-
C10	Removed from service on Day 44.								
*C11	0.61	0.70	2.84	4.96	6.46	8.72	10.6	5.53	3.16
C12	0.37	0.48	-	-	0.42	-	-	0.49	-
<u>Russell Soil</u>									
RC	0.26	0.37	0.48	0.42	0.51	0.33	0.49	0.25	0.34
*R1	0.28	0.31	0.39	0.96	1.95	2.14	10.3	8.91	7.40
R2	0.42	0.39	-	-	-	0.35	-	0.52	-
R3	0.35	0.63	-	-	0.59	-	0.43	0.39	-
*R4	0.43	0.34	0.83	3.46	6.87	5.93	8.78	3.92	3.14
R5	0.45	0.33	-	0.56	-	-	-	0.37	-
R6	0.32	0.67	-	-	0.75	-	-	0.54	-
R7	Removed from service on Day 44.								
*R8	0.39	0.52	0.65	1.83	1.74	2.46	12.2	5.20	8.79
R9	0.27	0.46	-	0.35	-	-	-	0.31	-
*R10	0.31	0.55	0.86	2.57	7.13	6.19	9.42	3.71	1.94
R11	0.42	0.62	-	0.73	-	-	0.58	0.53	-
R12	Removed from service on Day 45.								

*Indicates columns to which 10 mg/l ammonia nitrogen added to water applied to columns for Days 75-100.

Table B20. Nitrate Concentrations in Soil Column Effluents.

Nitrate Concentration, mg/l, for indicated days						
Col	Day 64	Day 73	Day 78	Day 84	Day 93	Day 105
<u>Chalmers Soil</u>						
CC	0.42	0.56	0.85	0.74	0.53	0.69
*C1	-	0.21	0.16	0.19	0.92	0.52
C2	-	0.23	0.27	-	0.39	0.57
C3	-	0.20	0.22	0.31	-	0.28
C4	-	0.27	0.21	-	-	0.30
*C5	-	0.21	0.19	0.23	0.80	0.96
C6	-	0.20	0.23	-	-	0.32
*C7	-	0.28	0.22	0.25	0.43	0.58
C8	-	0.19	0.32	-	0.49	0.34
C9	-	0.24	0.28	0.22	-	0.35
C10	Removed from service on Day 44.					
*C11	-	0.22	0.27	0.34	0.72	0.79
C12	-	0.23	0.29	-	-	0.14
<u>Russell Soil</u>						
RC	0.63	0.90	0.87	0.71	0.68	0.46
*R1	-	0.19	0.26	0.36	0.40	0.62
R2	-	0.22	0.25	-	0.16	0.18
R3	-	0.20	0.15	0.24	-	0.26
*R4	-	0.19	0.23	0.27	0.63	0.77
R5	-	0.26	0.31	-	0.39	0.33
R6	-	0.24	0.36	-	-	0.14
R7	Removed from service on Day 44.					
*R8	-	0.21	0.37	0.18	0.52	0.77
R9	-	0.19	0.19	0.25	-	0.22
*R10	-	0.23	0.16	0.65	0.87	0.54
R11	-	0.20	0.25	-	-	0.36
R12	Removed from service on Day 45.					

*Indicates columns to which 10 mg/l ammonia nitrogen added to water applied to columns for Days 75-100.

Table B21. Chloride Concentrations in Soil Column Effluents.

Chloride Concentrations, mg/l, for indicated days									
Col.	Day 66	Day 72	Day 79	Day 86	Day 94	Day 103	Day 110	Day 119	Day 127
<u>Chalmers Soil</u>									
CC	1.2	2.8	2.1	3.2	1.9	2.4	2.2	1.6	1.0
*C1	1.9	4.1	9.6	7.1	5.9	6.8	4.2	4.9	3.2
C2	3.9	3.7	5.2	6.1	4.8	5.1	6.3	5.4	5.8
C3	2.4	2.9	4.6	3.7	4.2	5.7	3.8	5.1	4.0
C4	3.1	2.2	1.8	3.3	3.9	4.1	3.3	4.2	4.8
*C5	3.6	5.6	2.8	8.7	6.9	7.5	8.5	4.7	5.9
C6	1.7	2.2	3.0	3.8	2.1	4.1	<1.0	3.6	4.2
*C7	4.1	6.9	7.4	9.7	11.4	7.8	12.2	9.0	-
C8	2.3	2.9	2.5	3.5	2.0	3.2	2.2	2.8	1.1
C9	2.9	1.1	1.4	2.6	1.0	3.6	4.1	2.0	1.4
C10	Removed from service on Day 44.								
*C11	3.8	10.1	6.4	8.8	12.1	9.4	7.8	9.1	7.4
C12	1.4	1.6	3.1	3.5	4.0	4.8	4.0	2.2	3.6
<u>Russell Soil</u>									
RC	2.2	3.1	1.2	1.9	<1.0	1.5	1.5	1.1	1.4
*R1	4.8	5.0	7.3	10.8	7.9	6.6	7.2	8.4	9.6
R2	3.7	2.1	1.7	4.6	3.2	2.8	2.6	1.3	2.4
R3	2.3	2.5	3.2	1.9	2.9	2.8	3.0	<1.0	1.4
*R4	6.2	3.6	3.9	7.0	10.2	5.9	4.8	6.2	6.7
R5	1.6	2.2	4.2	3.3	4.6	3.4	3.8	3.0	2.4
R6	1.8	2.2	3.1	1.2	3.6	4.2	4.4	2.8	<1.0
R7	Removed from service on Day 44.								
*R8	2.8	5.5	6.3	7.6	4.8	10.6	9.4	8.6	6.9
R9	2.4	3.6	4.4	5.3	3.0	2.0	1.8	3.5	2.8
R10	1.4	3.9	6.9	5.1	4.0	8.4	7.4	8.5	8.1
R11	2.7	1.8	2.0	4.2	1.2	3.2	2.4	1.4	3.6
R12	2.7	1.8	2.0	4.2	1.2	3.2	2.4	1.4	3.6
R12	Removed from service on Day 45.								

*Indicates columns to which 10 mg/l ammonia nitrogen added to water applied to columns for Days 75-100.

Appendix C. Tabulated Data from TCE:Soil Adsorption
Studies.

Table C1. Data For Determination of
Soil Adsorption Isotherms.

Coarse Particle Size				Fine Particle Size		
C_i , mg/l	*Vl, ml	*M, g	+X, μg	*Vl, ml	*M, g	+X, μg
<u>Chalmers Soil</u>						
110	20.3	10.143	426	-	-	-
220	20.1	10.192	744	20.5	10.065	1548
440	20.4	10.098	1656	20.6	10.129	2350
660	20.6	10.078	2963	21.0	10.148	4343
880	20.5	10.192	3129	20.3	10.082	4950
1100	20.4	10.018	3997	20.4	10.096	7341
<u>Russell Soil</u>						
110	20.4	9.879	326	20.4	9.979	469
220	20.6	10.313	330	20.5	10.094	616
440	20.4	10.074	816	20.7	10.130	1408
660	20.5	10.168	1271	20.1	10.146	1806
880	20.6	10.071	1833	20.6	10.080	2631
1100	20.4	10.202	2530	20.4	10.118	4472

*Average of two values.

+Calculated from average values.

NOTE: Information from this table used in conjunction with C_e and C_b values of Table 23 to calculate X/M values of Table 23.

Table C2. Data For Determination of X/M Values
In Time of Adsorption Experiment.

Time, Hours	<u>Ci = 220 mg/l</u>			<u>Ci = 880 mg/l</u>		
	*Vl, ml	*M, g	+X, μg	*Vl, ml	*M, g	+X, μg
<u>Chalmers Soil, Coarse Particle Size</u>						
2	20.2	10.131	182	20.8	9.942	457
4	20.3	10.187	162	20.7	10.168	580
6	20.1	9.829	462	20.4	10.210	1654
9	20.0	10.009	620	20.6	10.164	2287
13	20.1	10.039	763	20.7	10.103	2960
23	20.2	10.215	808	20.4	10.134	3182
33	20.5	10.127	738	20.5	10.130	3424
48	21.0	10.111	819	20.7	9.967	3229
<u>Chalmers Soil, Fine Particle Size</u>						
2	20.6	9.986	494	20.4	10.149	1591
4	20.5	10.093	963	20.5	10.088	3054
6	20.2	10.236	1010	20.6	9.894	3605
9.5	20.6	9.841	1256	20.4	10.136	4998
13	20.4	10.108	1265	20.5	10.034	5166
16	20.4	10.073	1326	20.3	10.217	5399
24	20.5	10.042	1374	20.6	10.118	5520
36	20.3	9.903	1299	20.4	10.302	5650
48	20.6	9.873	1195	20.4	10.104	5222
<u>Russell Soil, Coarse Particle Size</u>						
2	20.2	10.121	81	20.4	10.039	306
4	20.3	10.110	142	20.3	10.174	365
6	20.3	10.125	243	20.2	10.116	889
9	20.5	10.127	226	20.3	10.143	1258
14	20.3	10.139	365	20.5	9.972	1742
18	20.4	10.193	571	20.2	10.218	1899
24	20.3	10.146	487	20.4	10.193	1816
38	20.2	10.211	470	20.3	10.106	1860
48	20.5	10.012	512	20.1	10.088	1930

Table C2. Continued.

Time, Hours	<u>Ci = 220 mg/l</u>			<u>Ci = 880 mg/l</u>		
	*Vl, ml	*M, g	+X, µg	*Vl, ml	*M, g	+X, µg
<u>Russell Soil, Fine Particle Size</u>						
2	20.4	10.016	163	20.3	10.136	710
4	20.2	10.127	263	20.5	9.986	779
6	20.3	10.108	487	20.5	10.014	2193
10	20.5	9.992	656	20.2	10.190	2362
15	20.2	10.139	727	20.6	9.897	2699
24	20.3	10.201	751	20.4	10.029	2897
33	20.4	10.028	734	20.3	10.201	2984
37	20.5	10.176	697	20.4	10.088	2713
48	20.6	9.903	783	20.3	10.219	2964

* Average of two values.

+ Calculated from average values.

NOTE: Information from this table used in conjunction with C_e and C_b values of Table 26 and 27 to calculate appropriate X/M values.

Table C3. Data for Determination of Glass Adsorption Isotherm.

C_i , mg/l	V_l , ml	M_g , g	X , μg	A_g , cm^2
220	125.3	78.161	626	537
440	125.5	74.870	376	514
660	126.0	76.212	-1003	524
880	125.4	75.961	-1630	522
1100	124.2	76.323	124	528

Surface area of glass bead = $0.503 \text{ cm}^2/\text{bead} = SA$
 Mass of one glass bead = $0.0732 \text{ g}/\text{bead} = MGB$

$SA = \frac{0.503 \text{ cm}^2/\text{bead}}{0.0732 \text{ g}/\text{bead}} = 6.87 \text{ cm}^2/\text{g}$
 $A_g = \text{Area of glass beads}$

$M_g = \text{Mass of glass beads}$

$A_g = M_g \times 6.87 \text{ cm}^2/\text{g}$

Area of glass exposed in column is that of a cylinder 8 cm in diameter and 35" (88.9 cm) long.

$\text{Area} = \pi \times D \times L = \pi \times 8 \times 88.9 = 2234 \text{ cm}^2$

Table C4. Data for Determination of Gravel Adsorption Isotherm.

C_i , mg/l	V_l , ml	M_{gr} , g	X , μg
110	136.5	71.24	137
220	136.0	70.78	-816
440	136.0	76.52	408
550	134.2	76.00	-268
660	134.4	78.40	941
880	133.6	76.49	267
1100	133.8	78.63	535

Mass of gravel in 2" length of 80mm i.d. tubing is approximately 369g.

Appendix D. Tabulated Data from TCE:Soil Warburg
Respirometry Studies.

Table D1. Warburg Data for Unacclimated Chalmers Soil Supplemented with TCE from 2.5 Inch Depth.

Cumulative Oxygen Utilization, ul O ₂						
Time, hrs.	End.	Glucose, 1,000 mg/l	TCE, 1,100 mg/l	TCE, 550 mg/l	TCE, 110 mg/l	TCE, 55 mg/l
0.5	3.37	17.81	-2.49	-2.34	-0.61	0.41
1.0	4.21	26.22	-5.08	-3.14	+1.05	0.59
1.5	4.89	42.67	-4.22	-3.25	+1.52	0.73
2.0	10.23	45.14	-7.93	-3.80	-1.83	-0.08
2.5	11.14	58.36	-8.46	-7.91	-1.07	-0.99
3.0	14.09	72.96	-9.05	-8.46	-2.18	-1.86
4.0	18.64	80.45	-11.17	-9.04	-5.27	-3.01
5.0	19.55	101.67	-11.48	-9.68	-5.06	-2.66
6.0	22.61	111.42	-13.95	-12.42	-5.82	-2.82
8.0	30.74	128.43	-17.38	-14.17	-7.63	-3.66
10.0	46.67	132.48	-26.51	-15.48	-9.46	-6.27
12.0	52.30	143.19	-31.42	-17.16	-9.72	-6.70
15.0	59.78	145.67	-38.90	-20.29	-14.35	-10.44
17.0	78.46	141.88	-45.68	-23.72	-17.41	-22.72
24.0	107.52	144.05	-56.18	-36.41	-20.16	-12.69
27.0	121.26	140.16	-67.82	-37.05	-24.47	-14.51
28.0	123.52	142.56	-69.52	-38.42	-25.52	-13.83
30.0	132.11	140.32	-76.37	-45.62	-27.20	-16.58
32.0	136.63	136.93	-80.89	-48.40	-29.04	-17.45
36.0	171.51	129.58	-107.15	-53.22	-58.68	-25.30

Volume of soil used = 2ml Chalmers from 2.5 inch depth (2.70 g on dry wt basis).

Volume of liquid solution added = 1.0 ml

Table D1. Continued.

End. = Oxygen utilization by soil with DI water as solution added, classified as endogenous metabolism.

Cumulative Oxygen Utilization = Oxygen utilization by soil over and above endogenous metabolism for metabolism of substrate indicated.

^aIndicates solution contained 2 mg/l ammonia nitrogen.

Table D2. Warburg Data for Acclimated Chalmers Soil Supplemented with TCE
from 2.5 Inch Depth.

Time, hrs.	End.	Cumulative Oxygen Utilization, ul O ₂			
		Glucose, 500 mg/l	TCE, 110 mg/l	TCE, 55 mg/l	TCE,b 55 mg/l
0.5	5.21	22.51	-2.35	-0.27	0.92
1.0	9.69	37.71	-1.42	-0.13	-0.15
1.5	17.92	57.19	-0.63	0.12	-0.22
2.5	28.37	84.71	-1.74	-0.09	0.11
3.5	29.90	90.18	-0.39	0.18	0.69
4.5	34.38	89.98	-2.15	0.58	0.78
5.5	42.65	92.27	-0.28	0.96	1.26
6.5	49.35	93.53	0.46	1.50	0.83
7.5	50.07	96.11	0.68	1.94	1.31
8.5	54.52	95.36	0.42	2.41	2.43
10.0	60.45	95.01	-0.48	2.42	3.42
12.5	61.18	101.70	0.43	2.76	4.38
15.25	68.50	105.79	-0.68	3.38	4.94
24.5	92.09	105.36	-1.48	4.03	5.73
26.0	103.12	110.92	-2.97	4.26	5.68
27.5	109.13	111.98	-0.41	4.44	5.72
29.5	118.85	109.43	0.65	4.45	5.38
31.5	121.88	109.96	1.92	4.37	5.10
33.75	124.06	108.65	0.73	4.26	4.95

Volume of soil used = 2 ml Chalmers from 2.5 inch depth from Column C12 (2.62 g on dry weight basis).

Volume of liquid solution added = 1.0 ml.

Table D2. Continued.

End. = Oxygen utilization by soil with DI water as solution added, classified as endogenous metabolism.

Cumulative Oxygen Utilization = Oxygen utilization by soil over and above endogenous metabolism for metabolism of substrate indicated.

aIndicates solution contained 1 mg/l ammonia nitrogen.

bIndicates solution contained 2 mg/l ammonia nitrogen.

Table D3. Warburg Data for Acclimated Chalmers Soil Supplemented with TCE from 15 Inch Depth.

Cumulative Oxygen Utilization, ul O ₂						
Time, hrs.	End.	Glucose, 500 mg/l	TCE, 110 mg/l	TCE, 55 mg/l	TCE, a 55 mg/l	TCE, b 55 mg/l
0.5	0	1.57	0.47	-0.65	-0.49	0.67
1.0	4.40	2.14	-0.64	0.10	-0.04	-0.21
1.5	7.47	8.36	-0.83	0.14	0.33	0.54
2.0	8.35	11.17	0.06	0.30	-0.12	0.22
2.5	9.40	24.36	-0.31	0.21	0.29	0.14
3.0	9.40	33.71	1.27	0.62	0.29	0.14
3.5	10.78	47.62	0.31	-0.14	0.48	0.69
4.0	11.83	57.03	0.40	0.97	0.86	1.30
5.0	12.04	62.14	0.19	1.23	0.79	1.57
6.0	13.12	64.37	-0.08	1.66	1.24	1.49
7.0	15.97	68.32	1.02	1.74	1.69	2.08
9.0	21.09	73.09	0.67	1.82	1.37	1.96
11.0	26.29	75.41	0.82	1.98	1.85	2.32
14.0	46.15	77.89	0.41	2.01	1.75	2.12
16.0	47.00	78.64	1.35	2.18	1.92	1.99
24.0	78.64	83.67	2.28	1.86	1.99	1.65
26.0	80.65	86.41	1.64	2.17	2.14	2.58
28.0	81.49	88.53	1.95	2.10	2.36	2.69
30.0	88.73	89.43	1.26	0.99	2.29	2.79
34.0	90.74	88.02	2.20	2.13	1.31	2.08

Volume of soil used = 2 ml Chalmers from Column C12 (2.88 g on dry weight basis).

Volume of liquid solution added = 1.0 ml.

Table D3. Continued.

End = Oxygen utilization by soil with DI water as solution added, classified as endogenous metabolism.

Cumulative Oxygen Utilization = Oxygen utilization by soil over and above endogenous metabolism for metabolism of substrate indicated.

^aIndicates solution contained 1 mg/l ammonia nitrogen.

^bIndicates solution contained 2 mg/l ammonia nitrogen.

Table D4. Warburg Data for Acclimated Chalmers Soil Supplemented with TCE from 31 Inch Depth.

Cumulative Oxygen Utilization, ul O ₂						
Time, hrs.	End.	Glucose, 500 mg/l	TCE, 110 mg/l	TCE, 55 mg/l	TCE, ^a 55 mg/l	TCE, ^b 55 mg/l
0.5	2.61	3.70	-2.61	-0.50	-0.78	-0.65
1.0	5.33	5.71	-2.96	-0.10	-0.37	-2.93
1.5	7.11	10.92	0.01	-0.83	-0.46	-0.58
2.0	7.11	12.43	0.53	0.21	0.41	-0.58
2.5	10.66	11.59	-1.12	-0.14	-0.65	-0.82
3.0	13.93	13.27	0.37	-0.42	0.71	-0.86
4.0	16.00	13.99	-1.70	0.54	0.82	0.95
5.0	17.77	14.64	-0.65	0.62	0.89	-0.16
6.0	17.77	15.19	0.07	1.07	1.83	-0.16
8.0	19.55	17.93	0.83	0.91	1.17	0.14
10.0	23.10	18.61	-0.03	0.14	1.51	1.18
13.0	28.43	20.49	-2.41	-2.12	-1.18	1.25
15.0	31.99	25.20	-0.16	0.97	-1.26	1.56
17.0	35.54	23.66	-0.96	0.88	0.68	-0.40
23.0	49.76	25.82	-1.38	1.05	0.25	-0.71
25.0	58.64	28.73	-2.43	1.21	-0.91	0.16
26.0	58.64	29.99	0.21	1.21	-0.91	1.62
28.0	63.97	29.69	0.94	0.62	-0.94	1.69
30.0	67.53	26.88	-0.32	-0.83	-0.26	1.64
36.0	71.42	24.99	+0.55	-1.62	+0.59	0.67

Volume of soil used = 2 ml Chalmers from Column C12 (2.96 g on dry weight basis).

Volume of liquid solution added = 1.0 ml.

Table D4. Continued.

End. = Oxygen utilization by soil with DI water as solution added, classified as endogenous metabolism.

Cumulative Oxygen Utilization = Oxygen utilization by soil over and above endogenous metabolism for metabolism of substrate indicated.

^aIndicates solution contained 1 mg/l ammonia nitrogen.

^bIndicates solution contained 2 mg/l ammonia nitrogen.

Table D5. Warburg Data for Acclimated Russell Soil Supplemented with TCE
from 2.5 Inch Depth.

Cumulative Oxygen Utilization, ul O ₂						
Time, hrs.	End.	Glucose, 500 mg/l	TCE, 550 mg/l	TCE, 55 mg/l	TCE,a 55 mg/l	TCE,b 55 mg/l
0.5	3.02	1.81	-2.31	-0.17	0.09	-0.76
0.75	3.02	3.00	-0.63	-0.17	0.09	0.22
1.0	3.75	2.27	-0.29	0.52	-0.64	0.22
1.25	6.73	5.30	-2.46	0.66	0.11	-0.24
1.75	6.73	7.68	-2.46	1.21	0.11	1.35
2.25	8.91	9.20	-3.97	1.91	0.21	0.86
3.0	8.91	18.71	-3.97	1.91	0.82	0.86
3.5	8.91	18.71	-2.05	2.37	0.82	1.21
4.5	12.20	36.27	-4.56	1.84	0.99	1.52
5.5	15.56	65.34	-6.98	1.62	0.28	2.25
6.5	16.53	70.02	-7.51	2.89	2.00	2.65
7.5	21.09	73.48	-9.03	2.53	2.64	1.72
8.5	21.31	78.09	-8.78	3.28	2.82	3.56
11.0	36.95	86.24	-13.47	3.46	3.08	3.73
14.0	42.17	86.97	-18.21	3.95	2.42	3.94
16.0	51.11	90.97	-22.10	3.92	4.27	2.81
21.25	66.13	92.78	-20.64	4.15	3.24	4.69
25.0	70.64	96.75	-18.58	4.21	4.08	4.39
26.0	70.64	96.18	-16.73	4.21	4.69	4.39
27.0	82.62	103.62	-19.84	4.16	5.06	2.91
28.0	82.62	103.81	-18.32	4.16	5.06	4.02
29.5	84.84	102.24	-20.54	1.94	2.84	1.80
31.5	86.30	102.52	-20.72	3.12	3.22	3.68
34.0	93.80	100.95	-24.63	-0.28	3.08	1.87
36.0	95.30	101.56	-22.99	2.67	2.93	2.93

Table D5. Continued.

Volume of soil used = 2 ml Russell 11 from Column 2.5 inch depth from Column R10. (2.74 g on a dry weight basis).

Volume of liquid solution added = 1.0 ml.

End. = Oxygen utilization by soil with DI water as solution added, classified as endogenous metabolism.

Cumulative Oxygen Utilization = Oxygen utilization by soil over and above endogenous metabolism for metabolism of substrate indicated.

^aIndicates solution contained 1 mg/l ammonia nitrogen.

^bIndicates solution contained 2 mg/l ammonia nitrogen.

Table D6. Warburg Data for Acclimated Russell Soil Supplemented with TCE from 15 Inch Depth.

Time, hrs.	End.	Cumulative Oxygen Utilization, ul O ₂			
		Glucose, 500 mg/l	TCE, 110 mg/l	TCE, 55 mg/l	TCE, ^b 55 mg/l
0.5	1.51	-1.51	-1.51	-1.03	-1.51
1.0	1.51	0.12	-1.51	-0.68	-0.89
1.5	2.36	4.39	-1.23	-0.24	-0.05
2.0	2.36	8.82	-0.45	-0.24	-0.48
2.5	4.72	17.11	-2.81	0.09	-0.19
3.0	5.37	18.24	-2.67	0.13	-0.22
4.0	6.27	24.37	-3.57	0.21	-0.37
5.0	9.33	40.70	-4.29	0.42	-0.68
6.0	13.17	43.22	-8.13	0.74	0.14
7.0	15.46	44.29	-6.94	0.83	0.22
8.0	17.06	47.56	-5.77	1.54	1.03
9.0	17.06	52.08	-4.31	1.82	2.62
10.0	19.28	50.63	-6.52	1.31	2.75
13.0	27.74	56.29	-7.11	1.87	2.63
15.0	30.87	55.12	-7.69	1.88	1.61
17.0	32.39	54.68	-4.72	2.04	2.16
24.0	41.74	62.37	-3.26	1.93	2.03
26.0	44.26	64.88	-2.84	1.32	1.89
28.0	50.35	63.01	-6.93	0.54	2.35
33.0	54.81	67.46	-3.45	1.56	1.41
34.0	56.37	65.90	-5.01	1.42	2.57

Volume of soil used = 2 ml Russell from Column R10 (3.0 g on dry weight basis).

Volume of liquid solution added = 1.0 ml.

Table D6. Continued.

End. = Oxygen utilization by soil with DI water as solution added, classified as endogenous metabolism.

Cumulative Oxygen Utilization = Oxygen utilization by soil over and above endogenous metabolism for metabolism of substrate indicated.

a Indicates solution contained 1 mg/l ammonia nitrogen.

b Indicates solution contained 2 mg/l ammonia nitrogen.

Table D7. Warburg Data for Acclimated Russell Soil Supplemented with TCE from 31 Inch Depth.

Cumulative Oxygen Utilization, ul O ₂						
Time, hrs.	End.	Glucose, 500 mg/l	TCE, 110 mg/l	TCE, 55 mg/l	TCE, a 55 mg/l	TCE, b 55 mg/l
0.5	1.57	-0.79	-1.57	-0.83	-0.93	0.53
1.5	3.15	1.54	-1.83	-0.61	-0.15	-1.05
2.0	4.68	1.40	-2.01	-0.28	-0.18	0.25
2.5	4.68	2.47	-0.62	0.84	1.32	1.63
3.0	6.38	2.18	-1.49	-0.10	0.21	-0.07
4.0	7.79	4.80	-2.90	-1.29	-0.29	-0.39
6.0	7.79	9.45	-0.14	0.32	0.31	0.07
7.0	11.16	11.68	-3.51	-2.41	0.41	-2.41
8.0	11.93	14.91	-1.79	-0.68	-0.36	-1.03
9.0	14.35	15.30	-2.34	1.70	0.23	-0.84
10.0	20.84	17.22	-6.29	-0.69	0.56	-3.85
13.0	22.63	19.50	-8.08	0.84	0.79	-2.62
16.0	27.01	21.90	-7.23	0.80	0.11	-3.81
17.0	33.88	21.84	-9.26	-2.22	-2.41	-1.49
23.0	35.07	22.10	-5.65	0.28	-0.92	1.88
25.0	36.26	21.73	-3.01	-0.91	-2.11	0.69
27.0	39.85	20.30	-6.60	-1.32	1.10	-1.52
30.0	44.63	21.73	-9.48	-0.58	0.26	-1.69

Volume of soil used = 2 ml Russell from Column R10 (3.12 g on dry weight basis).

Volume of liquid solution added = 1.0 ml.

Table D7. Continued.

End. = Oxygen utilization by soil with DI water as solution added, classified as endogenous metabolism.

Cumulative Oxygen Utilization = Oxygen utilization by soil over and above endogenous metabolism for metabolism of substrate indicated.

^aIndicates solution contained 1 mg/l ammonia nitrogen.

^bIndicates solution contained 2 mg/l ammonia nitrogen.

VITA

VITA

Thomas Joseph Walker was born September 9, 1947 in Pascagoula, Mississippi to Bernard B. and Elsie J. Walker. He was married to Jane E. Hicks on June 7, 1969. They have three daughters, Jennifer, Rachel, and Katherine.

Mr. Walker was graduated from Our Lady of Victories High School in Pascagoula, Mississippi in May, 1965. He received his Bachelor of Science degree in Civil Engineering from Mississippi State University in January, 1970 where, upon graduation, he was commissioned a second lieutenant in the United States Air Force through ROTC. He earned his Master of Science degree in Sanitary Engineering from Mississippi State University in May 1971.

Mr. Walker began active duty service with the Air Force in July, 1971 and has served at Whiteman Air Force Base, Missouri; Osan Air Base, Korea; Reese Air Force Base, Texas; and Tyndall Air Force Base, Florida.

END

FILMED

1-85

DTIC